### Project Specific Water Quality Management Plan

A Template for Projects located within the Santa Ana Watershed Region of Riverside County

#### Project Title: Seaton Ave Warehouses

Development No: .

Design Review/Case No: PPT210022





Original Date Prepared: March 24, 2021

**Revision Date(s)**: June 18, 2021, July 12, 2021

Prepared for Compliance with Regional Board Order No. <u>R8-2010-0033</u> <u>Template revised June 30, 2016</u>

#### **Contact Information:**

#### Prepared for:

Dedeaux Properties 1430 S. Eastman Avenue Los Angeles, CA 90023 909-730-0186

#### Prepared by:

Douglas L. Goodman, Owner Goodman & Associates, Inc. 2079 Sky View Drive Colton, CA 92324 (909) 824-2775

#### **A Brief Introduction**

This Project-Specific WQMP Template for the **Santa Ana Region** has been prepared to help guide you in documenting compliance for your project. Because this document has been designed to specifically document compliance, you will need to utilize the WQMP Guidance Document as your "how-to" manual to help guide you through this process. Both the Template and Guidance Document go hand-in-hand, and will help facilitate a well prepared Project-Specific WQMP. Below is a flowchart for the layout of this Template that will provide the steps required to document compliance.



#### **OWNER'S CERTIFICATION**

This Project-Specific Water Quality Management Plan (WQMP) has been prepared for Dedeaux Properties by Goodman & Associates, Inc. for the Seaton Ave Warehouses project.

This WQMP is intended to comply with the requirements of the County of Riverside for Seaton Ave Warehouses, Planning Case PPT210022 which includes the requirement for the preparation and implementation of a Project-Specific WQMP.

The undersigned, while owning the property/project described in the preceding paragraph, shall be responsible for the implementation and funding of this WQMP and will ensure that this WQMP is amended as appropriate to reflect up-to-date conditions on the site. In addition, the property owner accepts responsibility for interim operation and maintenance of Stormwater BMPs until such time as this responsibility is formally transferred to a subsequent owner. This WQMP will be reviewed with the facility operator, facility supervisors, employees, tenants, maintenance and service contractors, or any other party (or parties) having responsibility for implementing portions of this WQMP. At least one copy of this WQMP will be maintained at the project site or project office in perpetuity. The undersigned is authorized to certify and to approve implementation of this WQMP. The undersigned is aware that implementation of this WQMP is enforceable under the County of Riverside Water Quality Ordinance (Municipal Code Section 1194).

"I, the undersigned, certify under penalty of law that the provisions of this WQMP have been reviewed and accepted and that the WQMP will be transferred to future successors in interest."

Owner's Signature

Benjamin Horning Owner's Printed Name Date

Owner Representative Owner's Title/Position

#### PREPARER'S CERTIFICATION

"The selection, sizing and design of stormwater treatment and other stormwater quality and quantity control measures in this plan meet the requirements of Regional Water Quality Control Board Order No. **R8-2010-0033** and any subsequent amendments thereto."

Preparer's Signature

Douglas L.	Goodman
Preparer's	Printed Name

Date

Owner Preparer's Title/Position

Preparer's Licensure: RCE 28500, Expires March 31, 2022

### **Table of Contents**

Section A: Project and Site Information	. 6
<ul> <li>A.1 Maps and Site Plans</li> <li>A.2 Identify Receiving Waters</li> <li>A.3 Additional Permits/Approvals required for the Project:</li> </ul>	.7 .7 .7
Section B: Optimize Site Utilization (LID Principles)	. 9
Section C: Delineate Drainage Management Areas (DMAs)1	10
Section D: Implement LID BMPs	13
D.1 Infiltration Applicability	13 14 16
D.4 Feasibility Assessment Summaries	17 18
Section E: Alternative Compliance (LID Waiver Program)	20
E.1 Identify Pollutants of Concern       2         E.2 Stormwater Credits       2         E.3 Sizing Criteria       2         E.4 Treatment Control BMP Selection       2	21 22 22 22 23
Section F: Hydromodification	<u>2</u> 4
F.1 Hydrologic Conditions of Concern (HCOC) Analysis	24 25
Section G: Source Control BMPs2	26
Section H: Construction Plan Checklist	29
Section I: Operation, Maintenance and Funding	30

### List of Tables

Table A.1 Identification of Receiving Waters	7
Table A.2 Other Applicable Permits	7
Table C.1 DMA Classifications	10
Table C.2 Type 'A', Self-Treating Areas	10
Table C.3 Type 'B', Self-Retaining Areas	11
Table C.4 Type 'C', Areas that Drain to Self-Retaining Areas	11
Table C.5 Type 'D', Areas Draining to BMPs	12
Table D.1 Infiltration Feasibility	13
Table D.2 LID Prioritization Summary Matrix	17
Table D.3 DCV Calculations for LID BMPs	18
Table E.1 Potential Pollutants by Land Use Type	21
Table E.2 Water Quality Credits	22
Table E.3 Treatment Control BMP Sizing	22
Table E.4 Treatment Control BMP Selection	23
Table F.1 Hydrologic Conditions of Concern Summary	24
Table G.1 Permanent and Operational Source Control Measures	26
Table H.1 Construction Plan Cross-reference	29

### List of Appendices

Appendix 1: Maps and Site Plans	31
Appendix 2: Construction Plans	32
Appendix 3: Soils Information	33
Appendix 4: Historical Site Conditions	34
Appendix 5: LID Infeasibility	35
Appendix 6: BMP Design Details	36
Appendix 7: Hydromodification	37
Appendix 8: Source Control	
Appendix 9: O&M	
Appendix 10: Educational Materials	6 -

### **Section A: Project and Site Information**

The proposed project is for the construction of two warehouse buildings with truck loading docks and associated parking on 9 acres. The project is located on Seaton Avenue, extending westerly to Beck Street, between Perry Street and Markham Street, in the unincorporated Perris Area, County of Riverside. Access to the proposed site building will be from two driveway entrances off of Seaton Avenue on the east side of the site.

The existing vacant property generally slopes from west to east at approximately 3%. Existing drainage sheet flows across the site, discharging to an existing inlet structure at the northeast corner of the site. There is an existing 48" storm drain pipe in Seaton Avenue, constituting the current upstream end of Perris Valley Area Drain Plan Lateral F-1. The project will be required to extend Lateral F-1 to the west side in order to collect off-site runoff. There is also existing runoff from properties to the south that will be collected by a system on-site and conveyed directly to Lateral F-1. No run-on from off-site areas will surface drain to the site.

The proposed project will consist of two buildings, each on dedicated parcel. Each parcel will have a dedicated LID BMP, proposed to be a CDS clarifier for pre-treatment ahead of an underground infiltration system. Each system is proposed to be situated to the east of each building. Over-flows in excess of water quality capture volume requirements will be directed to the aforementioned Lateral F-1 for conveyance off-site.

PROJECT INFORMATION				
Type of Project:	Industrial/Warehouse			
Planning Area:	n/a			
Community Name:	n/a			
Development Name:	Seaton Ave Warehouses			
PROJECT LOCATION				
Latitude & Longitude (DMS):	33.8496°N / 117.2637°W			
Project Watershed and Sub-V	Vatershed: San Jacinto River			
Gross Acres: 9.807				
APN(s): 0314-091-005				
Map Book and Page No.:				
PROJECT CHARACTERISTICS				
Proposed or Potential Land U	lse(s)	Warehouse		
Proposed or Potential SIC Coo	de(s)	4214		
Area of Impervious Project Footprint (SF) 342,345 sf				
Total Area of proposed Impervious Surfaces within the Project Footprint (SF)/or Replacement342,345 sf				
Does the project consist of offsite road improvements? $\qquad \qquad \qquad$				
Does the project propose to construct unpaved roads?				
Is the project part of a larger	common plan of development (phased project)?	🗌 Y 🛛 N		
EXISTING SITE CHARACTERISTICS				

Total area of existing Impervious Surfaces within the Project limits Footprint (SF)	0 sf	
Is the project located within any MSHCP Criteria Cell?	<b>Y</b>	$\boxtimes$ N
If so, identify the Cell number:	n/a	
Are there any natural hydrologic features on the project site?	☐ Y	🖂 N
Is a Geotechnical Report attached?	<u> ү</u>	□ N
If no Geotech. Report, list the NRCS soils type(s) present on the site (A, B, C and/or D)	A,C,D	
What is the Water Quality Design Storm Depth for the project?	0.591	

### A.1 Maps and Site Plans

When completing your Project-Specific WQMP, include a map of the local vicinity and existing site. In addition, include all grading, drainage, landscape/plant palette and other pertinent construction plans in Appendix 2. At a **minimum**, your WQMP Site Plan should include the following:

- Drainage Management Areas
- Proposed Structural BMPs
- Drainage Path
- Drainage Infrastructure, Inlets, Overflows
- Source Control BMPs
- Buildings, Roof Lines, Downspouts
- Impervious Surfaces
- Standard Labeling
- BMP Locations (Lat/Long)

Use your discretion on whether or not you may need to create multiple sheets or can appropriately accommodate these features on one or two sheets. Keep in mind that the Co-Permittee plan reviewer must be able to easily analyze your project utilizing this template and its associated site plans and maps.

### A.2 Identify Receiving Waters

Using Table A.1 below, list in order of upstream to downstream, the receiving waters that the project site is tributary to. Continue to fill each row with the Receiving Water's 303(d) listed impairments (if any), designated beneficial uses, and proximity, if any, to a RARE beneficial use. Include a map of the receiving waters in Appendix 1.

Receiving Waters	EPA Approved 303(d) List Impairments	Designated Beneficial Uses	Proximity to RARE Beneficial Use
San Jacinto River	n/a	n/a	n/a
Canyon Lake	Nutrients, Pathogens	MUN,AGR,GWR,REC1,REC2,WARM,WILD	n/a
Lake Elsinore	Nutrients, Organic Enrichment, Low Dissolved Oxygen, PCBs, Sediment, Unknown Toxicity	REC1,REC2,WARM,COLD, WILD	n/a

#### **Table A.1** Identification of Receiving Waters

### A.3 Additional Permits/Approvals required for the Project:

Agency	Permit Re	quired
State Department of Fish and Game, 1602 Streambed Alteration Agreement	Υ	🖂 N
State Water Resources Control Board, Clean Water Act (CWA) Section 401 Water Quality Cert.	Y	N
US Army Corps of Engineers, CWA Section 404 Permit	<b>Y</b>	N

US Fish and Wildlife, Endangered Species Act Section 7 Biological Opinion	<b>Y</b>	N
Statewide Construction General Permit Coverage	X 🛛	🗌 N
Statewide Industrial General Permit Coverage	Υ	N
Western Riverside MSHCP Consistency Approval (e.g., JPR, DBESP)	□ Y	N 🛛
Other (please list in the space below as required) RIVERSIDE COUNTY	×Υ	🗌 N

If yes is answered to any of the questions above, the Co-Permittee may require proof of approval/coverage from those agencies as applicable including documentation of any associated requirements that may affect this Project-Specific WQMP.

### **Section B: Optimize Site Utilization (LID Principles)**

#### **Site Optimization**

Did you identify and preserve existing drainage patterns? If so, how? If not, why?

The proposed project maintains this drainage pattern.

Did you identify and protect existing vegetation? If so, how? If not, why?

The existing parcel is a vacant parcel. The only vegetation on site are annual weeds and grasses typical of urban areas in Southern California. As such, the existing vegetation is ephemeral and not a permanent feature of the site. The proposed project will clear the existing site.

Did you identify and preserve natural infiltration capacity? If so, how? If not, why?

The project will preserve natural infiltration capacity where required for the proposed stormwater BMPs. The proposed landscaped areas will introduce planting media that will likely enhance the capability to store runoff on-site within the media. The infiltration capacity of the existing soils remains unchanged.

Did you identify and minimize impervious area? If so, how? If not, why?

The project is subject to numerous development requirements, including minimum number of parking stalls, minimum driveway widths, ADA standards, etc. The project meets these requirements with as small a footprint and as much landscaping as possible.

Did you identify and disperse runoff to adjacent pervious areas? If so, how? If not, why?

Some of the runoff will drain to nearby landscaping areas. The project calculations do not take credit for this as a treatment mechanism, however. The remainder of the project is designed to flow to the proposed BMPs shown on the plan. Stormwater is directed to these BMPs with minimal use of inlets and pipes (except for pretreatment needs), which is nearly equivalent to dispersing runoff to various pervious areas around the project.

# Section C: Delineate Drainage Management Areas (DMAs)

Table C.1 DMA Classifications

DMA Name or ID	Surface Type(s) <sup>12</sup>	Area (Sq. Ft.)	DMA Type
DA 1/A	Concrete or Asphalt	119103	D
DA 1/B	Ornamental Landscaping	34403	A
DA 1/C	Roofs	49680	D
DA 1/D	Concrete or Asphalt	10050	D
DA 2/A	Concrete or Asphalt	123882	D
DA 2/B	Ornamental Landscaping	33940	A
DA 2/C	Roofs	49680	D

 $^1 Reference$  Table 2-1 in the WQMP Guidance Document to populate this column  $^2 lf$  multi-surface provide back-up

#### Table C.2 Type 'A', Self-Treating Areas

DMA Name or ID	Area (Sq. Ft.)	Stabilization Type	Irrigation Type (if any)
DA 1/B 34403		Plants, turf, trees, ground cover	automatic
DA 2/B 33940		Plants, turf, trees, ground cover	automatic

#### Table C.3 Type 'B', Self-Retaining Areas

Self-Retai	ning Area			Type 'C' DM Area	As that are drair	ning to the Self-Retaining
DMA Name/ ID	Post-project surface type	Area (square feet) [A]	Storm Depth (inches) [B]	DMA Name / ID	[C] from Table C.4 = [C]	Required Retention Depth (inches) [D]
			[D] =	$[B] + \frac{[B] \cdot [C]}{[A]}$	]	

DMA					Receiving Self-R	etaining DMA	
MA Name/ ID	Rea Area (square feet)	ost-project urface type	면 Impervious fraction	Product [C] = [A] x [B]	DMA name //D	Area (square feet)	Ratio
	L1	P.	-1		DIVIA Hame / ID	[-]	

DMA Name or ID	BMP Name or ID
DA 1/A	BMP 1
DA 1/C	BMP 1
DA 1/D	BMP 1
DA 2/A	BMP 2
DA 2/C	BMP 2

#### Table C.5 Type 'D', Areas Draining to BMPs

<u>Note</u>: More than one drainage management area can drain to a single LID BMP, however, one drainage management area may not drain to more than one BMP.

### **Section D: Implement LID BMPs**

### **D.1 Infiltration Applicability**

Is there an approved downstream 'Highest and Best Use' for stormwater runoff (see discussion in Chapter 2.4.4 of the WQMP Guidance Document for further details)?  $\Box$  Y  $\boxtimes$  N

#### **Geotechnical Report**

A Geotechnical Report or Phase I Environmental Site Assessment may be required by the Copermittee to confirm present and past site characteristics that may affect the use of Infiltration BMPs. In addition, the Co-Permittee, at their discretion, may not require a geotechnical report for small projects as described in Chapter 2 of the WQMP Guidance Document. If a geotechnical report has been prepared, include it in Appendix 3. In addition, if a Phase I Environmental Site Assessment has been prepared, include it in Appendix 4.

Is this project classified as a small project consistent with the requirements of Chapter 2 of the WQMP Guidance Document?  $\Box$  Y  $\boxtimes$  N

#### **Infiltration Feasibility**

#### Table D.1 Infiltration Feasibility Does the project site... YES NO ...have any DMAs with a seasonal high groundwater mark shallower than 10 feet? Х If Yes, list affected DMAs: ...have any DMAs located within 100 feet of a water supply well? Х If Yes, list affected DMAs: ...have any areas identified by the geotechnical report as posing a public safety risk where infiltration of Х stormwater could have a negative impact? If Yes, list affected DMAs: ... have measured in-situ infiltration rates of less than 1.6 inches / hour? Х If Yes, list affected DMAs: ALL ...have significant cut and/or fill conditions that would preclude in-situ testing of infiltration rates at the final Х infiltration surface? If Yes, list affected DMAs: ...geotechnical report identify other site-specific factors that would preclude effective and safe infiltration? Х Describe here:

If you answered "Yes" to any of the questions above for any DMA, Infiltration BMPs should not be used for those DMAs and you should proceed to the assessment for Harvest and Use below.

### **D.2 Harvest and Use Assessment**

Please check what applies:

 $\square$  Reclaimed water will be used for the non-potable water demands for the project.

 $\Box$  Downstream water rights may be impacted by Harvest and Use as approved by the Regional Board (verify with the Copermittee).

□ The Design Capture Volume will be addressed using Infiltration Only BMPs. In such a case, Harvest and Use BMPs are still encouraged, but it would not be required if the Design Capture Volume will be infiltrated or evapotranspired.

If any of the above boxes have been checked, Harvest and Use BMPs need not be assessed for the site. If none of the above criteria applies, follow the steps below to assess the feasibility of irrigation use, toilet use and other non-potable uses (e.g., industrial use).

#### Irrigation Use Feasibility

Complete the following steps to determine the feasibility of harvesting stormwater runoff for Irrigation Use BMPs on your site:

Step 1: Identify the total area of irrigated landscape on the site, and the type of landscaping used.

Total Area of Irrigated Landscape: 1.57 ac

*Type of Landscaping (Conservation Design or Active Turf)*: Conservative Design

Step 2: Identify the planned total of all impervious areas on the proposed project from which runoff might be feasibly captured and stored for irrigation use. Depending on the configuration of buildings and other impervious areas on the site, you may consider the site as a whole, or parts of the site, to evaluate reasonable scenarios for capturing and storing runoff and directing the stored runoff to the potential use(s) identified in Step 1 above.

Total Area of Impervious Surfaces: 7.86 ac

Step 3: Cross reference the Design Storm depth for the project site (see Exhibit A of the WQMP Guidance Document) with the left column of Table 2-3 in Chapter 2 to determine the minimum area of Effective Irrigated Area per Tributary Impervious Area (EIATIA).

Enter your EIATIA factor: 0.79

Step 4: Multiply the unit value obtained from Step 3 by the total of impervious areas from Step 2 to develop the minimum irrigated area that would be required.

Minimum required irrigated area: 6.21 ac

Step 5: Determine if harvesting stormwater runoff for irrigation use is feasible for the project by comparing the total area of irrigated landscape (Step 1) to the minimum required irrigated area (Step 4).

Minimum required irrigated area (Step 4)	Available Irrigated Landscape (Step 1)
6.21 ac	1.57 ac

Minimum required acreage not met; Irrigation Use not Feasible.

#### **Toilet Use Feasibility**

Complete the following steps to determine the feasibility of harvesting stormwater runoff for toilet flushing uses on your site:

Step 1: Identify the projected total number of daily toilet users during the wet season, and account for any periodic shut downs or other lapses in occupancy:

Projected Number of Daily Toilet Users: 200

Project Type: Industrial

Step 2: Identify the planned total of all impervious areas on the proposed project from which runoff might be feasibly captured and stored for toilet use. Depending on the configuration of buildings and other impervious areas on the site, you may consider the site as a whole, or parts of the site, to evaluate reasonable scenarios for capturing and storing runoff and directing the stored runoff to the potential use(s) identified in Step 1 above.

Total Area of Impervious Surfaces: 7.86 ac

Step 3: Enter the Design Storm depth for the project site (see Exhibit A) into the left column of Table 2-2 in Chapter 2 to determine the minimum number or toilet users per tributary impervious acre (TUTIA).

Enter your TUTIA factor: 132

Step 4: Multiply the unit value obtained from Step 3 by the total of impervious areas from Step 2 to develop the minimum number of toilet users that would be required.

Minimum number of toilet users: 1037

Step 5: Determine if harvesting stormwater runoff for toilet flushing use is feasible for the project by comparing the Number of Daily Toilet Users (Step 1) to the minimum required number of toilet users (Step 4).

Minimum required Toilet Users (Step 4)	Projected number of toilet users (Step 1)
1037	200

#### Therefore, Toilet Use is <u>NOT</u> feasible

#### **Other Non-Potable Use Feasibility**

Are there other non-potable uses for stormwater runoff on the site (e.g. industrial use)? See Chapter 2 of the Guidance for further information. If yes, describe below. If no, write N/A.

n/a

Step 1: Identify the projected average daily non-potable demand, in gallons per day, during the wet season and accounting for any periodic shut downs or other lapses in occupancy or operation.

Average Daily Demand: n/a

Step 2: Identify the planned total of all impervious areas on the proposed project from which runoff might be feasibly captured and stored for the identified non-potable use. Depending on the configuration of buildings and other impervious areas on the site, you may consider the site as a whole, or parts of the site, to evaluate reasonable scenarios for capturing and storing runoff and directing the stored runoff to the potential use(s) identified in Step 1 above.

Total Area of Impervious Surfaces: n/a

Step 3: Enter the Design Storm depth for the project site (see Exhibit A) into the left column of Table
 2-4 in Chapter 2 to determine the minimum demand for non-potable uses per tributary impervious acre.

Enter the factor from Table 2-4: n/a

Step 4: Multiply the unit value obtained from Step 3 by the total of impervious areas from Step 2 to develop the minimum number of gallons per day of non-potable use that would be required.

Minimum required use: n/a

Step 5: Determine if harvesting stormwater runoff for other non-potable use is feasible for the project by comparing the projected average daily use (Step 1) to the minimum required non-potable use (Step 4).

Minimum required non-potable use (Step 4)	Projected average daily use (Step 1)
n/a	n/a

If Irrigation, Toilet and Other Use feasibility anticipated demands are less than the applicable minimum values, Harvest and Use BMPs are not required and you should proceed to utilize LID Bioretention and Biotreatment per Section 3.4.2 of the WQMP Guidance Document.

#### **D.3 Bioretention and Biotreatment Assessment**

Other LID Bioretention and Biotreatment BMPs as described in Chapter 2.4.7 of the WQMP Guidance Document are feasible on nearly all development sites with sufficient advance planning.

Select one of the following:

 $\Box$  LID Bioretention/Biotreatment BMPs will be used for some or all DMAs of the project as noted below in Section D.4 (note the requirements of Section 3.4.2 in the WQMP Guidance Document).

□ A site-specific analysis demonstrating the technical infeasibility of all LID BMPs has been performed and is included in Appendix 5. If you plan to submit an analysis demonstrating the technical infeasibility of LID BMPs, request a pre-submittal meeting with the Copermittee to discuss this option. Proceed to Section E to document your alternative compliance measures.

### **D.4 Feasibility Assessment Summaries**

From the Infiltration, Harvest and Use, Bioretention and Biotreatment Sections above, complete Table D.2 below to summarize which LID BMPs are technically feasible, and which are not, based upon the established hierarchy.

The proposed Underground Infiltration BMP is a form of Infiltration Basin or Infiltration Trench. The County sizing methodology for an Infiltration Trench was utilized in this report. An underground BMP is selected for this project because of insufficient surface landscape area that could support a standard trench or basin.

		No LID			
DMA Name/ID	1. Infiltration	Infiltration 2. Harvest and use 3. Bioretention 4. Biotreatment		(Alternative Compliance)	
DA 1/A	$\boxtimes$				
DA 1/B	$\boxtimes$				
DA 1/C	$\boxtimes$				
DA 1/D	$\boxtimes$				
DA 2/A	$\boxtimes$				
DA 2/B	$\boxtimes$				
DA 2/C	$\boxtimes$				

 Table D.2 LID Prioritization Summary Matrix

For those DMAs where LID BMPs are not feasible, provide a brief narrative below summarizing why they are not feasible, include your technical infeasibility criteria in Appendix 5, and proceed to Section E below to document Alternative Compliance measures for those DMAs. Recall that each proposed DMA must pass through the LID BMP hierarchy before alternative compliance measures may be considered.

n/a

### **D.5 LID BMP Sizing**

Each LID BMP must be designed to ensure that the Design Capture Volume will be addressed by the selected BMPs. First, calculate the Design Capture Volume for each LID BMP using the  $V_{BMP}$  worksheet in Appendix F of the LID BMP Design Handbook. Second, design the LID BMP to meet the required  $V_{BMP}$  using a method approved by the Copermittee. Utilize the worksheets found in the LID BMP Design Handbook or consult with your Copermittee to assist you in correctly sizing your LID BMPs. Complete Table D.3 below to document the Design Capture Volume and the Proposed Volume for each LID BMP. Provide the completed design procedure sheets for each LID BMP in Appendix 6. You may add additional rows to the table below as needed.

DMA Type/ID	DMA Area (square feet)	Post-Project Surface Type	Effective Impervious Fraction, I <sub>f</sub>	DMA Runoff Factor	DMA Areas x Runoff Factor	Enter BMP Name / Here		/ Identifier
	[A]		[B]	[C]	[A] x [C]	BMP 1/Ur	nderground	Infiltration
DA 1/A	119103	Concrete or Asphalt	1	0.89	106002			Proposed Volume on Plans (cubic feet)
DA 1/B	34403	Ornamental Landscaping	0.1	0.11	3784	Design	Design Capture Volume, VBMP (cubic faat)	
DA 1/C	49680	Roofs	1	0.89	44215	Storm		
DA 1/D	10050	Concrete or Asphalt	1	0.89	8965	(in)		
							Jeelj	
	213,236				163,319	0.59	8044	8044

 Table D.3 DCV Calculations for LID BMPs

DMA Type/ID	DMA Area (square feet)	Post-Project Surface Type	Effective Imperviou s Fraction, I <sub>f</sub>	DMA Runoff Factor	DMA Areas x Runoff Factor	Enter BMP Name / Here		/ Identifier	
	[A]		[B]	[C]	[A] x [C]	BMP 2/Underground Infiltration			
DA 2/A	123882	Concrete or Asphalt	1	0.89	110255		Design Capture Pro Volume, Vol Volume, on Vвмр (cu (cubic feet)		
DA 2/B	33940	Ornamental Landscaping	0.1	0.11	3733	Design		Proposed Volume on Plans (cubic feet)	
DA 2/C	49680	Roofs	1	0.89	44215	Storm Denth			
						(in)			
	207,502				158,203	0.59	7,809	7,809	

[B], [C] is obtained as described in Section 2.3.1 of the WQMP Guidance Document

[E] is obtained from Exhibit A in the WQMP Guidance Document

[G] is obtained from a design procedure sheet, such as in LID BMP Design Handbook and placed in Appendix 6

### Section E: Alternative Compliance (LID Waiver Program)

LID BMPs are expected to be feasible on virtually all projects. Where LID BMPs have been demonstrated to be infeasible as documented in Section D, other Treatment Control BMPs must be used (subject to LID waiver approval by the Copermittee). Check one of the following Boxes:

⊠ LID Principles and LID BMPs have been incorporated into the site design to fully address all Drainage Management Areas. No alternative compliance measures are required for this project and thus this Section is not required to be completed.

- Or -

□ The following Drainage Management Areas are unable to be addressed using LID BMPs. A site-specific analysis demonstrating technical infeasibility of LID BMPs has been approved by the Co-Permittee and included in Appendix 5. Additionally, no downstream regional and/or sub-regional LID BMPs exist or are available for use by the project. The following alternative compliance measures on the following pages are being implemented to ensure that any pollutant loads expected to be discharged by not incorporating LID BMPs, are fully mitigated.

### E.1 Identify Pollutants of Concern

Utilizing Table A.1 from Section A above which noted your project's receiving waters and their associated EPA approved 303(d) listed impairments, cross reference this information with that of your selected Priority Development Project Category in Table E.1 below. If the identified General Pollutant Categories are the same as those listed for your receiving waters, then these will be your Pollutants of Concern and the appropriate box or boxes will be checked on the last row. The purpose of this is to document compliance and to help you appropriately plan for mitigating your Pollutants of Concern in lieu of implementing LID BMPs.

Priority Development		General P	General Pollutant Categories								
Proje Proje that a	ct Categories and/or ct Features (check those apply)	Bacterial Indicators	Metals	Nutrients	Pesticides	Toxic Organic Compounds	Sediments	Trash & Debris	Oil & Grease		
	Detached Residential Development	Р	N	Ρ	Ρ	Ν	Р	Ρ	Р		
	Attached Residential Development	Р	N	Р	Р	N	Р	Ρ	P <sup>(2)</sup>		
	Commercial/Industrial Development	P <sup>(3)</sup>	Р	P <sup>(1)</sup>	P <sup>(1)</sup>	P <sup>(5)</sup>	P <sup>(1)</sup>	Ρ	Р		
	Automotive Repair Shops	N	Р	N	N	P <sup>(4, 5)</sup>	N	Р	Р		
	Restaurants (>5,000 ft²)	Р	N	N	N	N	N	Ρ	Р		
	Hillside Development (>5,000 ft <sup>2</sup> )	Р	N	Р	Р	N	Р	Ρ	Р		
	Parking Lots (>5,000 ft <sup>2</sup> )	P <sup>(6)</sup>	Р	P <sup>(1)</sup>	P <sup>(1)</sup>	P <sup>(4)</sup>	P <sup>(1)</sup>	Ρ	Р		
	Retail Gasoline Outlets	Ν	Р	N	N	Р	Ν	Р	Р		
Proj of C	ect Priority Pollutant(s) oncern										

#### Table E.1 Potential Pollutants by Land Use Type

P = Potential

N = Not Potential

<sup>(1)</sup> A potential Pollutant if non-native landscaping exists or is proposed onsite; otherwise not expected

<sup>(2)</sup> A potential Pollutant if the project includes uncovered parking areas; otherwise not expected

<sup>(3)</sup> A potential Pollutant is land use involving animal waste

<sup>(4)</sup> Specifically petroleum hydrocarbons

<sup>(5)</sup> Specifically solvents

<sup>(6)</sup> Bacterial indicators are routinely detected in pavement runoff

### **E.2 Stormwater Credits**

Projects that cannot implement LID BMPs but nevertheless implement smart growth principles are potentially eligible for Stormwater Credits. Utilize Table 3-8 within the WQMP Guidance Document to identify your Project Category and its associated Water Quality Credit. If not applicable, write N/A.

#### Table E.2 Water Quality Credits

Qualifying Project Categories	Credit Percentage <sup>2</sup>
n/a	
Total Credit Percentage <sup>1</sup>	

<sup>1</sup>Cannot Exceed 50%

<sup>2</sup>Obtain corresponding data from Table 3-8 in the WQMP Guidance Document

### E.3 Sizing Criteria

After you appropriately considered Stormwater Credits for your project, utilize Table E.3 below to appropriately size them to the DCV, or Design Flow Rate, as applicable. Please reference Chapter 3.5.2 of the WQMP Guidance Document for further information.

DMA Type/ID	DMA Area (square feet)	Post- Project Surface Type	Effective Impervious Fraction, I <sub>f</sub>	DMA Runoff Factor	DMA Area x Runoff Factor		Enter BMP Na	Enter BMP Name / Identifier Here			
	[A]		[B]	[C]	[A] x [C]						
n/a											
							Minimum		Proposed		
							Design		Volume		
						Destan	Capture	Total Storm	or Flow		
						Design Storm	Volume or Design Flow	water Credit %	on Plans (cubic		
						Depth	Rate (cubic	Reduction	feet or		
						(in)	feet or cfs)		cfs)		
	A <sub>T</sub> = Σ[A]				Σ= [D]	[E]	$[F] = \frac{[D]x[E]}{[G]}$	[F] X (1-[H])	[1]		

Table E.3 Treatment Control BMP Sizing

[B], [C] is obtained as described in Section 2.3.1 from the WQMP Guidance Document

[E] is for Flow-Based Treatment Control BMPs [E] = .2, for Volume-Based Control Treatment BMPs, [E] obtained from Exhibit A in the WQMP Guidance Document

[G] is for Flow-Based Treatment Control BMPs [G] = 43,560, for Volume-Based Control Treatment BMPs, [G] = 12

[H] is from the Total Credit Percentage as Calculated from Table E.2 above

[I] as obtained from a design procedure sheet from the BMP manufacturer and should be included in Appendix 6

### E.4 Treatment Control BMP Selection

Treatment Control BMPs typically provide proprietary treatment mechanisms to treat potential pollutants in runoff, but do not sustain significant biological processes. Treatment Control BMPs must have a removal efficiency of a medium or high effectiveness as quantified below:

- **High**: equal to or greater than 80% removal efficiency
- **Medium**: between 40% and 80% removal efficiency

Such removal efficiency documentation (e.g., studies, reports, etc.) as further discussed in Chapter 3.5.2 of the WQMP Guidance Document, must be included in Appendix 6. In addition, ensure that proposed Treatment Control BMPs are properly identified on the WQMP Site Plan in Appendix 1.

able E.4 Treatment Control BMP Selection								
Selected Treatment Control BMP	Priority Pollutant(s) of	Removal Efficiency						
Name or ID <sup>1</sup>	Concern to Mitigate <sup>2</sup>	Percentage <sup>3</sup>						
n/a								

 Table E.4 Treatment Control BMP Selection

<sup>1</sup> Treatment Control BMPs must not be constructed within Receiving Waters. In addition, a proposed Treatment Control BMP may

be listed more than once if they possess more than one qualifying pollutant removal efficiency.

 $^{\rm 2}$  Cross Reference Table E.1 above to populate this column.

<sup>3</sup> As documented in a Co-Permittee Approved Study and provided in Appendix 6.

### Section F: Hydromodification

#### F.1 Hydrologic Conditions of Concern (HCOC) Analysis

Once you have determined that the LID design is adequate to address water quality requirements, you will need to assess if the proposed LID Design may still create a HCOC. Review Chapters 2 and 3 (including Figure 3-7) of the WQMP Guidance Document to determine if your project must mitigate for Hydromodification impacts. If your project meets one of the following criteria which will be indicated by the check boxes below, you do not need to address Hydromodification at this time. However, if the project does not qualify for Exemptions 1, 2 or 3, then additional measures must be added to the design to comply with HCOC criteria. This is discussed in further detail below in Section F.2.

**HCOC EXEMPTION 1**: The Priority Development Project disturbs less than one acre. The Copermittee has the discretion to require a Project-Specific WQMP to address HCOCs on projects less than one acre on a case by case basis. The disturbed area calculation should include all disturbances associated with larger common plans of development.

Does the project qualify for this HCOC Exemption?  $\Box$  Y  $\boxtimes$  N If Yes, HCOC criteria do not apply.

**HCOC EXEMPTION 2**: The volume and time of concentration<sup>1</sup> of storm water runoff for the postdevelopment condition is not significantly different from the pre-development condition for a 2-year return frequency storm (a difference of 5% or less is considered insignificant) using one of the following methods to calculate:

- Riverside County Hydrology Manual
- Technical Release 55 (TR-55): Urban Hydrology for Small Watersheds (NRCS 1986), or derivatives thereof, such as the Santa Barbara Urban Hydrograph Method
- Other methods acceptable to the Co-Permittee

Does the project qualify for this HCOC Exemption?

□ Y □ N

If Yes, report results in Table F.1 below and provide your substantiated hydrologic analysis in Appendix 7.

		2 year – 24 hour		
		Pre-condition	Post-condition	% Difference
Time of		n/a	n/a	
	Concentration			
	Volume (Cubic Feet)	n/a	n/a	

Table F.1	Hydrologic	Conditions of	of Concern	Summar
-----------	------------	---------------	------------	--------

<sup>1</sup> Time of concentration is defined as the time after the beginning of the rainfall when all portions of the drainage basin are contributing to flow at the outlet.

**HCOC EXEMPTION 3**: All downstream conveyance channels to an adequate sump (for example, Prado Dam, Lake Elsinore, Canyon Lake, Santa Ana River, or other lake, reservoir or naturally erosion resistant feature) that will receive runoff from the project are engineered and regularly maintained to ensure design flow capacity; no sensitive stream habitat areas will be adversely affected; or are not identified on the Co-Permittees Hydromodification Susceptibility Maps. (No longer accepted by the Santa Ana Regional Waterboard)

Does the project qualify for this HCOC Exemption?  $\Box Y \boxtimes N$ 

If Yes, HCOC criteria do not apply and note below which adequate sump applies to this HCOC qualifier:

#### F.2 HCOC Mitigation

If none of the above HCOC Exemption Criteria are applicable, HCOC criteria is considered mitigated if they meet one of the following conditions:

- a. Additional LID BMPS are implemented onsite or offsite to mitigate potential erosion or habitat impacts as a result of HCOCs. This can be conducted by an evaluation of site-specific conditions utilizing accepted professional methodologies published by entities such as the California Stormwater Quality Association (CASQA), the Southern California Coastal Water Research Project (SCCRWP), or other Co-Permittee approved methodologies for site-specific HCOC analysis.
- b. The project is developed consistent with an approved Watershed Action Plan that addresses HCOC in Receiving Waters.
- c. <u>Mimicking the pre-development hydrograph with the post-development hydrograph, for a 2-year return frequency storm. Generally, the hydrologic conditions of concern are not significant, if the post-development hydrograph is no more than 10% greater than pre-development hydrograph. In cases where excess volume cannot be infiltrated or captured and reused, discharge from the site must be limited to a flow rate no greater than 110% of the pre-development 2-year peak flow.</u>

Be sure to include all pertinent documentation used in your analysis of the items a, b or c in Appendix 7.

Please see HCOC calculations in Appendix 7. The 2-year existing condition runoff for the area tributary to the upstream end of Lateral F-1 is 49.6 cfs. When the subject site is substituted in the hydrology calculations, the 2-year proposed condition runoff is 51.3 cfs. The developed runoff is 103% of the existing condition, therefore the project is in compliance with HCOC Mitigation Criteria.

### **Section G: Source Control BMPs**

Source control BMPs include permanent, structural features that may be required in your project plans — such as roofs over and berms around trash and recycling areas — and Operational BMPs, such as regular sweeping and "housekeeping", that must be implemented by the site's occupant or user. The MEP standard typically requires both types of BMPs. In general, Operational BMPs cannot be substituted for a feasible and effective permanent BMP. Using the Pollutant Sources/Source Control Checklist in Appendix 8, review the following procedure to specify Source Control BMPs for your site:

- 1. *Identify Pollutant Sources*: Review Column 1 in the Pollutant Sources/Source Control Checklist. Check off the potential sources of Pollutants that apply to your site.
- Note Locations on Project-Specific WQMP Exhibit: Note the corresponding requirements listed in Column 2 of the Pollutant Sources/Source Control Checklist. Show the location of each Pollutant source and each permanent Source Control BMP in your Project-Specific WQMP Exhibit located in Appendix 1.
- 3. **Prepare a Table and Narrative:** Check off the corresponding requirements listed in Column 3 in the Pollutant Sources/Source Control Checklist. In the left column of Table G.1 below, list each potential source of runoff Pollutants on your site (from those that you checked in the Pollutant Sources/Source Control Checklist). In the middle column, list the corresponding permanent, Structural Source Control BMPs (from Columns 2 and 3 of the Pollutant Sources/Source Control Checklist) used to prevent Pollutants from entering runoff. Add additional narrative in this column that explains any special features, materials or methods of construction that will be used to implement these permanent, Structural Source Control BMPs.
- 4. Identify Operational Source Control BMPs: To complete your table, refer once again to the Pollutant Sources/Source Control Checklist. List in the right column of your table the Operational BMPs that should be implemented as long as the anticipated activities continue at the site. Copermittee stormwater ordinances require that applicable Source Control BMPs be implemented; the same BMPs may also be required as a condition of a use permit or other revocable Discretionary Approval for use of the site.

Potential Sources of Runoff pollutants	Permanent Structural Source Control BMPs	Operational Source Control BMPs		
Landscaping/Outdoor Pesticide Use	Final Landscape Plans will accomplish all of the following:	<ul> <li>Maintain landscaping using minimum or no pesticides</li> </ul>		
	<ul> <li>Preserve existing native trees, shrubs, and ground cover to the maximum extent possible.</li> <li>Design landscaping to minimize irrigation and runoff, to promote surface infiltration where appropriate, and to minimize</li> </ul>	• Do not rake or blow leaves, clippings or pruning waste into the street, gutter or storm drain. Instead dispose of green waste by composting, hauling it to a permitted landfill, or recycling through the City of Riverside's recycling program		

#### Table G.1 Permanent and Operational Source Control Measures

	•	the use of fertilizers and pesticides that can contribute to stormwater pollution. Where landscaped areas are used to retain or detain stormwater, specify plants that are tolerant of saturated soil conditions.	<ul> <li>Provide integrated Pest Management information to new owners, lessees, and operators</li> </ul>
	•	Consider using pest-resistant plants, especially adjacent to hardscape.	
	•	To ensure successful establishment, select plants appropriate to site soils, slopes, climate, sun, wind, rain, land use, air movement, ecological consistence, and plant interactions.	
Refuse Areas	•	Trash receptacles shall be emptied by trained personnel on a regular basis to maintain clean facilities Trash enclosures area shall be kept clean by sweeping on a regular basis. Trash enclosures shall be emptied by a qualified, contracted waste management company or the City of Riverside. Signs will be posted on or near dumpsters with the words, "Do not dump hazardous materials here" or similar.	<ul> <li>Provide adequate number of receptacles</li> <li>Inspect receptacles regularly, and repair or replace leaky receptacles</li> <li>Keep receptacles covered</li> <li>Prohibit/prevent dumping of liquid or hazardous wastes</li> <li>Post "No Hazardous Materials signs"</li> <li>Inspect and pick up litter daily and clean up spills immediately</li> <li>Keep spill control materials on-site</li> </ul>
Condensate Drain Lines	•	Condensate lines for equipment get drained into the sanitary sewer at the mop sink.	
Plazas, sidewalks, loading docks and parking lots			Sweep plazas, sidewalks, and parking lots regularly to prevent accumulation of litter and debris. Collect debris from pressure

washing to prevent entry into
the storm drain system. Collect
washwater containing and
cleaning agent or degreaser and
discharge to the sanitary sewer,
not to a storm drain.

### **Section H: Construction Plan Checklist**

 Table H.1 Construction Plan Cross-reference

BMP No. or		Corresponding Plan Sheet(s)	BMP Location (Lat/Long)
ID	BMP Identifier and Description		
BMP 1	Underground Infiltration		
BMP 2	Underground Infiltration		

### Section I: Operation, Maintenance and Funding

The Copermittee will periodically verify that Stormwater BMPs on your site are maintained and continue to operate as designed. To make this possible, your Copermittee will require that you include in Appendix 9 of this Project-Specific WQMP:

- 1. A means to finance and implement facility maintenance in perpetuity, including replacement cost.
- 2. Acceptance of responsibility for maintenance from the time the BMPs are constructed until responsibility for operation and maintenance is legally transferred. A warranty covering a period following construction may also be required.
- 3. An outline of general maintenance requirements for the Stormwater BMPs you have selected.
- 4. Figures delineating and designating pervious and impervious areas, location, and type of Stormwater BMP, and tables of pervious and impervious areas served by each facility. Geolocating the BMPs using a coordinate system of latitude and longitude is recommended to help facilitate a future statewide database system.
- 5. A separate list and location of self-retaining areas or areas addressed by LID Principles that do not require specialized O&M or inspections but will require typical landscape maintenance as noted in Chapter 5, pages 85-86, in the WQMP Guidance. Include a brief description of typical landscape maintenance for these areas.

Your local Co-Permittee will also require that you prepare and submit a detailed Stormwater BMP Operation and Maintenance Plan that sets forth a maintenance schedule for each of the Stormwater BMPs built on your site. An agreement assigning responsibility for maintenance and providing for inspections and certification may also be required.

Details of these requirements and instructions for preparing a Stormwater BMP Operation and Maintenance Plan are in Chapter 5 of the WQMP Guidance Document.

#### Maintenance Mechanism:

N

Facility maintenance is self-funded as part of continuing business operations. Employee shall perform maintenance duties as part of their job requirements except for specialized or contracted services to be provided by qualified personnel.

Will the proposed BMPs be maintained by a Home Owners' Association (HOA) or Property Owners Association (POA)?



Operation and Maintenance Plan and Maintenance Mechanism is included in Appendix 9. Educational materials for those personnel that will be maintaining the proposed BMPs within this Project-Specific WQMP are included in Appendix 10.

### Appendix 1: Maps and Site Plans

Location Map, WQMP Site Plan and Receiving Waters Map



## **RECEIVING WATERS EXHIBIT**





REV.	REVISION DESCRIPTION	DAT

APN 314-091-005



G	ood	man
	SZA!	SSOCIATES

DOUGLAS L. GOODMAN RCE 28500, 3-31-2022

Y	PIC	AL	ALL L	AND	SCA	PINC	3			
G	OF	Ĺ	NDSC	APE	AR	EAS	AM		UM	0
#	то	2"	BELO	W TO	c. si	DEW	ALK.	OR	PA	VE

## Appendix 2: Construction Plans

Grading and Drainage Plans

## Appendix 3: Soils Information

Geotechnical Study and Other Infiltration Testing Data


45090 Golf Center Parkway, Suite F, Indio, CA. 92201 (760) 863-0713 Fax (760) 863-0847 6782 Stanton Avenue, Suite C, Buena Park, CA. 90621 (714) 523-0952 Fax (714) 523-1369 450 Egan Avenue, Beaumont, CA. 92223 (951) 845-7743 Fax (951) 845-8863 www.SladdenEngineering.com

December 23, 2020

Project No. 644-20039 20-12-094

Dedeaux Properties P.O. Box 82706 Goleta, California 93118-2706

Project: Proposed Warehouse Building APN 314-091-005 Seaton Avenue Perris Area Riverside County, California

Subject: Percolation/Infiltration Testing for On-Site Storm Water Management

Ref: Geotechnical Investigation report prepared by Sladden Engineering dated December 23, 2020; Project No. 644-20039, Report No. 20-12-093.

In accordance with your request, we have performed infiltration/percolation testing on the subject site to evaluate the infiltration potential of the near surface soil to assist in storm water management system design. It is our understanding that on-site storm water retention and infiltration are proposed for the project.

Percolation testing was performed on December 9, 2020 within two (2) shallow test bores excavated on the site. Testing was performed at a depth of approximately 5.0 feet below existing grade. The approximate locations of the tests are presented on the attached Exploration Location Plan (Figure 3). Testing was performed by placing water within the test bores and recording the drop in the water surface with time. Testing was performed in general accordance with the *United States Bureau of Reclamation (BOR) Procedure 7300-89 (1999)*. Test results are summarized in the following table.

### PERCOLATION TEST RESULTS

Test No.	Depth (Ft)	Percolation Rate (in/hr)	*Infiltration Rate (in/hr)
P-1	5.00	37.50	4.07
P-2	5.00	26.47	2.73

\*Porchet Method

The percolation rates determined represent ultimate field rates that do not include a safety factor. The corresponding infiltration rates were calculated using the Porchet Method. An appropriate safety factor should be applied to account for long-term saturation, subsoil inconsistencies and the potential for silting of the percolating soil. The safety factor should be determined with consideration to other factors in the storm water retention system design (specifically storm water volume estimates) and the safety factors associated with these design components. It should be noted that the rates determined are representative of the alluvial surface soil but may not be representative of the underlying bedrock.

If you have any questions regarding this memo, please contact the undersigned.

Respectfully submitted, SLADDEN ENGINEERING

GIONAL GEO PRO James W. Minor III JAMES W. Senior Geologist MINOR III No. 9735 OF CALIF

Copies: 4 / Addressee

BRETTL ANDERSON No. C45389 CIVIL ENGINEERING OF CAL Brett L. Anderson

**Principal Engineer** 

### FIGURES

SITE LOCATION MAP REGIONAL GEOLOGIC MAP EXPLORATION LOCATION PLAN







- Netherland a Chinese States

### Negeria de la Coloria de Coloria d

### APPENDIX A

BORELOGS STORMWATER PERCOLATION TESTING DATA SHEETS PERCOLATION RATE CONVERSION (PORCHET'S METHOD)

					BORE LOG							
<b>ADD</b>	EN	ENC	SINE	EERIN	IG	I	Drill Rig:	Mobile B-61	Date Drilled:	12/8/20	)20	
<u> </u>	1	r			1	E N	levation:	1550 Ft (MSL)	Boring No:	BH-1	1	
Bulk Sample	Expansion Index	% Minus #200	% Moisture	Dry Density	Depth (Feet)	Graphic Litholog		Des	cription			
Bulks	Expan	45.2 11.2	6.6 7.2	Q Å Q	$\begin{array}{c} \text{Hjd}_{2} \\ \text{Hjd}_{2} $	Graph	Silty Sand gravel (Fill Silty Sand fine-to coar Granitic Be strong, hig type.	(SM); brown, dry, fine /Disturbed). (SM); yellowish brown :se-grained with trace drock (gr); light gray, hly weathered, breaks Terminated : No Groundwater of Bedrock Encount	e-to coarse-grained w n, slightly moist, med of gravel (Qal). moderately hard, m a down into silty sand at ~11.5 Feet bgs r Seepage Encounter tered at ~8.0 Feet bgs	tium dense oderately d (SM) soil		
25:					-3638		PROPOSED INDUSTRIAL BUILDING APN 314-091-005					
	Bulk Sample	Bulk Sample Bulk Sample Expansion Index	ADDEN ENG Barly Sample Bulk Sample Expansion Index 11.2	ADDEN ENGINE	ADDEN ENGINEERIN	ADDEN ENGINEERING	ADDEN ENGINEERING I B B B B B B B B B B B B B	ADDEN ENGINEERING         Drill Rig: Elevation:           a         a         a         b         b         c         b           a         a         a         b         b         c         b         b           a         a         a         b         c         b         c	ADDEN ENGINEERING         DORE           9         39         00         111 <t< td=""><td>BORE LOG       Drill Rug:     Mobile B-61     Date Drilled:       Bevation:     1350 Pf (MSL)     Boring No:       add add add add add add add add add ad</td><td>BORE LOG       Drill Rig: Mobile B-61 Date Drilled: 12/8/20 Elevation: 1550.Pt (MSL) Boring No: BH- Bering No: BH- BH- Bering No: BH- BH- Bering No: BH- BH- Bering No: BH- BH- BH- BH- BH- BH- BH- BH- BH- BH-</td></t<>	BORE LOG       Drill Rug:     Mobile B-61     Date Drilled:       Bevation:     1350 Pf (MSL)     Boring No:       add add add add add add add add add ad	BORE LOG       Drill Rig: Mobile B-61 Date Drilled: 12/8/20 Elevation: 1550.Pt (MSL) Boring No: BH- Bering No: BH- BH- Bering No: BH- BH- Bering No: BH- BH- Bering No: BH- BH- BH- BH- BH- BH- BH- BH- BH- BH-	

				·			,,,,			BORE	LOG			
	SLA	DD	EN	ENC	SINE	ERIN	G	I I	Drill Rig:	Mobile B-61	Date Drilled:	12/8/	/2020	
				<u> </u>				E E	levation:	1550 Ft (MSL)	Boring No:	BI	1-2	
Sample	Blow Counts	Bulk Sample	Expansion Index	% Minus #200	% Moisture	Dry Density	Depth (Feet)	Graphic Litholog		Des	cription			
		1	38				- 2 -		Silty Sand ( gravel (Fill/ Silty Sand ( grained wit	SM); brown, dry, fine Disturbed). SM); yellowish brow th trace of gravel (Qal	e-to coarse-grained w n, slightly moist, fine- l).	ith trace -to coars	of e-	
	18/32/50-6"			13.4	4.1		 - 6 -							
	13/24/23			13.5	5.9		- 8 - 		Granitic Be	drock (gr); light gray,	, moderately hard, mo	oderately	,	
	37/50-3"			6.8	5.3	131.7	- 12 - - 12 - - 14 -		strong, highly weathered, breaks down into silty sand (SM) soil type.					
	26/50-6"			14.0	8.0		- 16 - - 18 -							
							- 20 -	Terminated at ~16.5 Feet bgs No Groundwater or Seepage Encountered Bedrock Encountered at ~4.0 Feet bgs						
							- 24 -							
							- 26 -  - 28							
							- 30 -							
							- 34 -							
							- 36 -  - 38 -							
							- 40 -							
							46 -							
							- 50 -							
Com	pletion Note	s:				• • • • • • • • • • • • • • • • • • •				PROPOSED IND	USTRIAL BUILDING			
									Project Me	APN 3	14-091-005	<b></b>		
1									Report No:	20-12-094		Page	2	

Sole (bill sole breach sole)

www.analestication.com/analestication/

										BORE	LOG			
	SLA	DD	EN	ENC	GINE	ERIN	G		Drill Rig:	Mobile B-61	Date Drilled:	12/8	/2020	
T	<u> </u>	<b></b>		<u> </u>			<u>r</u>	E E	levation:	1550 Ft (MSL)	Boring No:	BF	<del>1</del> -3	
Sample	Blow Counts	Bulk Sample	Expansion Index	% Minus #200	% Moisture	Dry Density	Depth (Feet)	Graphic Litholog		De	scription			
	P								Silty Sand (S gravel (Fill/I	M); brown, dry, fir Disturbed).	ne-to coarse-grained wi	th trace	of	
	12/12/13			36.3	5.1	121.1	 - 4 -		Silty Sand (S	M); yellowish brov	vn, slightly moist, med	ium der	ıse,	
	4/5/7			37.2	5.6		- 6 -		fine-to coars	e-grained with trac	e of gravel (Qal).			
	20/26/29			18.7	9.9	133.4	- 8 - - 10 -		Granitic Bedrock (gr); light gray, moderately hard, moderately strong, highly weathered, breaks down into silty sand (SM) soil type.					
							-12 - 12 - 14 - 14 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 16 - 18 - 18			Terminated No Groundwater Bedrock Encour	t at ~10.0 Feet bgs or Seepage Encounterentered at ~7.0 Feet bgs	d		
Comp	letion Note	:S:	I	1	1	£	J	i		PROPOSED INE	USTRIAL BUILDING			
									Project No:	APN 644-20039	314-091-005	Page	2	
<u> </u>									Report No:	20-12-094		age	J	

_	_					****				BO	RE LO	DG		
	E) SL/	ADD	EN	ENG	GINE	EERIN	G	I	Drill Rig:	Mobile B-61		Date Drilled:	12/8	/2020
		T	ſ			ſ	[	E No	levation:	1550 Ft (MSL	.)	Boring No:	B	H-4
Sample	Blow Counts	Bulk Sample	Expansion Index	% Minus #200	% Moisture	Dry Density	Depth (Feet)	Graphic Litholog			Descri	ption		
								/	Silty Sand	(SM); brown, dry	, fine-to	o coarse-grained w	vith trace	of
	3/6/12			14.2	6.0		- 2 -		gravel (Fill	/Distubed).			·~	
							- 4 -		Granitic Be	drock (gr); light ;	gray, m	oderately hard, m	oderatel	v
	21/506"			12.2	6.2	133.2			strong, hig type.	hly weathered, b	reaks d	own into silty san	d (SM) so	oil
							 - 8 -							
							L _		E	Termin No Groundwa	ated at ter or S	~6.5 Feet bgs leepage Encounter	ed	
							- 10 - 		Bedrock Encountered at ~3.0 Feet bgs					
							- 12 -							
			1				- 14 -							
								1						
							- 18 -							
			1				20 -	1						
							<u>⊢</u>							
							- 24 -		1					
							- 26							
					]									
							- 30 							
							- 32 -		ł					
							 - 34 -							
			ļ					}	ļ					
							- 36 -	4						
						ļ	- 38 -	1	]					
							40-							
		1						]	ļ					
1			1											
1					1		<u> </u> 44 −	]						
			1				- 46 -							
			ļ		]		- - 48	]						
			1											
		<u> </u>		<u> </u>			- 50 -							
əml	pletion Note	es:					_			PROPOSED	INDUS PNI 314	TRIAL BUILDING	3	
									Project No:	644-20039		-071-000	Dane	л
									Report No:	20-12-094			rage	4

(http://www.englowers.com) (http://www.englowers.com)

										BORE	LOG		
	E) SL/	DD	EN	ENC	SINE	EERIN	G		Drill Rig:	Mobile B-61	Date Drilled:	12/8/	/2020
<u> </u>	······	<u>[</u>	Γ	<u> </u>			r——	E F	levation:	1550 Ft (MSL)	Boring No:	BI	I-5
Sample	Blow Counts	Bulk Sample	Expansion Index	% Minus #200	% Moisture	Dry Density	Depth (Feet)	Graphic Litholog:		Des	scription		
Samp	3/5/8 7/12/28	Bulk	Expan	ITW 32 29.6 16.8	oW %	112.4	1       A       B       C         1.4       -       -       Silty Sand (SM); brown, dry, fine-to coarse-grained with gravel (Fill/Distubed).         1.4       -       -       Silty Sand (SM); yellowish brown, slightly moist, loose, f coarse-grained with trace of gravel (Qal).         -       -       -       Silty Sand (SM); yellowish brown, slightly moist, loose, f coarse-grained with trace of gravel (Qal).         -       -       -       Cranitic Bedrock (gr); light gray, moderately hard, mode strong, highly weathered, breaks down into silty sand (S type.         -       10       Terminated at ~6.5 Feet bgs         10       Terminated at ~5.0 Feet bgs         12       Bedrock Encountered at ~5.0 Feet bgs         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         -       -       -         - </td <td>of , , , il</td>						of , , , il
Comr	oletion Note	25:					- 42 - - 44 - - 44 - - 46 - - 48 - - 50 -			PROPOSED INID			
										APN 3	14-091-005	1	
1									Project No:	644-20039			
1									Report No	20-12-094		- rage	5

										BORE	LOG		
	SL/	ADD	EN	ENG	GINI	EERIN	G		Drill Rig:	Mobile B-61	Date Drilled:	12/8/	2020
		T	r			<u> </u>	Т		levation:	1550 Ft (MSL)	Boring No:	BH	[-6
Sample	Blow Counts	Bulk Sample	Expansion Index	% Minus #200	% Moisture	Dry Density	Depth (Feet)	Graphic Litholog.		De	scription		
									Silty Sand (	(SM); brown, dry, fin	e to coarse grainedw/	gravel (F	ill).
	27/50-4"			10.6	3.9		- 2		Granitic Be strong, hig type.	drock (gr); light gray hly weathered, break	y, moderately hard, m is down into silty sand	oderately 1 (SM) soi	il
								1		Terminated	l at ~5.0 Feet bgs		
	ļ	}								No Groundwater o	or Seepage Encounter	ed	
							- 8			Bedrock Encour	itered at ~1.0 Feet bgs		
		[	[			1		1	(				
		1							]				
							- 12 -						
-		{											
			ļ	1			- 16 -						
		]	]						]				
	3					Ì	- 20 -						
		]											
						[			ĺ				
				ļ			- 24 -						
							26 -						
1				ł					]				
		]		ļ			- 28 -						
							<b>30</b>	Í	Í				
							- 32 -						
								1					
							-  _						
							- 36 -						
				1			38-						
	1						- 40 -						
							42 -						
						1	- 44 -						
									1				
				1		]							
							- 48 -						
				[		[							
0007	pletion Not	<u> </u>	l	L	1	<u> </u>		<u> </u>					
~~·ļ										APN 3	314-091-005	T	
									Project No:	644-20039	·····	Page	 ۲
									Report No:	20-12-094		- 46°	0

										BORE	LOG		
	E) SL/	DD	EN	ENG	GINE	ERIN	G		Drill Rig:	Mobile B-61	Date Drilled:	12/8	/2020
		<u> </u>		<u> </u>	1		T	E >	levation:	1550 Ft (MSL)	Boring No:	BI	I-7
Sample	Blow Counts	Bulk Sample	Expansion Index	% Minus #200	% Moisture	Dry Density	Depth (Feet)	Graphic Litholog		De	scription		
Sam	10/12/17	Bulk	Expa	9.8	W%		$\begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} $	Grap	Silty Sand ( Granitic Be strong, hig' type.	SM); brown, dry, fir drock (gr); light gray hly weathered, breal Terminate No Groundwater Bedrock Encour	he to coarse grainedw/ y, moderately hard, moderately ha	gravel (i oderately i (SM) so ed	Fill).
Com	pletion Note	25:				 	- 50 -	] 		PROPOSED INI APN	DUSTRIAL BUILDING 314-091-005	;	
									Project No:	644-20039		- Page	7

		<u></u>								BORE	LOG	. <u></u>	
	E) SL/	ADD	EN	ENG	GINE	ERIN	lG	I	Drill Rig:	Mobile B-61	Date Drilled:	12/8/	/2020
r		1			r	r		E	Elevation:	1550 Ft (MSL)	Boring No:	P	-1
Sample	Blow Counts	Bulk Sample	Expansion Index	% Minus #200	% Moisture	Dry Density	Depth (Feet)	Graphic Litholog		Des	scription		
Sample		Bulk	Expa	W %	W %	Dry	$\begin{bmatrix} 1 & - & - & - \\ - & 2 & - & - \\ - & 4 & - & - \\ - & 4 & - & - \\ - & 6 & - & - \\ - & 6 & - & - \\ - & 6 & - & - \\ - & 6 & - & - \\ - & 10 & -$	Grap Caracterized and Car	Silty Sand gravel (Fill Silty Sand grained wi	(SM); brown, dry, fin /Disturbed). (SM); yellowish brow th trace of gravel (Qa Terminated No Groundwater o No Bedroo Cased to Facilita	e-to coarse-grained wi m, slightly moist, fine- l). l at ~5.0 Feet bgs or Seepage Encountered te Percolation Testing	ith trace -to coars ed	of e-
Comp	letion Not	es:					- 44 - - 46 - - 48 - - 48 - - 50 -	44 - 4 46 - 48 - 50 - 50 - 50 - 50 - 50 - 50 - 50 - 5					
									Project No.	: 644-20039		Page	8

								[		BORE	LOG		
	E) SLA	1DD	EN	ENG	GINE	ERIN	G	)	Drill Rig:	Mobile B-61	Date Drilled:	12/8	2020
								E	levation:	1550 Ft (MSL)	Boring No:	Р	-2
Sample	Blow Counts	Bulk Sample	Expansion Index	% Minus #200	% Moisture	Dry Density	Depth (Feet)	Graphic Lithology		De	scription		
									Silty Sand (S gravel (Fill/I	6M); brown, dry, fir Disturbed).	ne-to coarse-grained w	ith trace	of
							- 2 - 		Silty Sand (S	GM); yellowish brov	vn, slightly moist, fine		e-
							- 4 -		grained with	n trace of gravel (Qa	al).		
				5			- 6 -			Terminate	d at ~5.0 Feet bys		
							8-			No Groundwater	or Seepage Encounter	ed	
								Cased to Facilitate Percolation Testing					
					1		- 12 -						
							- 14 -		*				
				E.			- 16 -						
							- 18						
							- 20 -						
							- 22						
							- 24 -						
							- 26						
							- 28 -						
							- 30 - 						
							- 32 -						
				l			- 34 -						
							- 36 -						
							- 38 -						
							- 40 -						
							- 42 -						
							- 44 -						
							- 46 -						,
							48-						
							- 50 -						
Comp	pletion Note	es:								PROPOSED IND APN	USTRIAL BUILDING 314-091-005		
									Project No:	644-20039		Page	9
1									Ikenort No	20-12-094			- 1

η

RIVERSIDE COUNTY STORMWATER TESTING FIELD SHEET

Project Name: APN 314-091-005 Job Number: 644-20039 Test Date: 12/9/2020 Drill-Rig: Mobil B-61 Test Hole: P-1 Depth: 5' Testing By: Robert

	SANDY SOIL CRITERIA TEST												
READING*	START TIME	END TIME	TIME	DEPTH (ft)	INITIAL W (in)	FINAL W (in)	ΔW (in)	Greater Tha	n or Equal to 6"				
·	<u> </u>							res					
A	10:00	10:25	25	5'	20	0	20	<u>x</u>					
В	10:27	10:52	25	5'	20	4 4/8	15 4/8	х					

\*Sandy soil testing procedure, if two consecutive readings (Tests A & B) show that 6.0" of water seeps away in less than 25 minutes, testing shall be performed for an additional hour with measurements taken every 10 minutes. The final 10 minute test shall be used to calculate final percolation rate (ie. min/in)\*

\*\*Non-sandy soil testing procedure, if two consecutive reads (Tests A & B) show that less than 6.0" of water seeps away in less than 25 minutes, test hole shall be pre-soaked (filled) overnight. Following overnight presoak, Testing shall be performed for an additional 6 hours with measurements taken every 30 minutes. The final 30 minute test shall be used to calculate final percolation rate (i.e. min/in)\*\*

READING*	TIMER	TIME INTERVAL	DEPTH (ft)	INITIAL W (in)	FINAL W (in)	ΔW (in)	PERCOLATION RATE (in/hr)
1	TIMER	10	5'	20	12 1/8	7 7/8	46.32
2	TIMER	10	5'	20	12 3/8	7 5/8	44.85
3	TIMER	10	5'	20	13	7	41.18
4	TIMER	10	5'	20	13 2/8	6 6/8	39.71
5	TIMER	10	5'	20	13 4/8	6 4/8	38.24
6	TIMER	10	5'	20	13 5/8	6 3/8	37.50
7**						0	
8**						0	
9**						0	
10**						0	
11**						0	
12**						0	i

Comments:

Presoak: Invert a 5 gallon jug of water over test hole so waters flows into and holds constant at least 5 times the holes radius inside test hole prior to testing.

Test Procedure: Fill test hole to 5 times the hole radius (ie. 8 inch diameter test hole = 4 inch radius = minimum 20 inches of water).

Leave Stake with ribbon attached within testing area. Label stake with Siadden Engineering, date & test number.

RIVERSIDE COUNTY STORMWATER TESTING FIELD SHEET

Project Name: APN 314-091-005 Job Number: 644-20039 Test Date: 12/9/2020 Drill-Rig: Mobil B-61 Test Hole: P-2 Depth: 5' Testing By: Robert

SANDY SOIL CRITERIA TEST									
READING*	START TIME	END TIME		DEPTH (ft)	INITIAL W (in)	FINAL W (in)	ΔW (in)	Greater Th	an or Equal to 6"
A	10:02	10:27	25	5'	20	7	13	X	
B	10:29	10:54	25	5'	20	10 3/8	9 5/8	x	

\*Sandy soil testing procedure, if two consecutive readings (Tests A & B) show that 6.0" of water seeps away in less than 25 minutes, testing shall be performed for an additional hour with measurements taken every 10 minutes. The final 10 minute test shall be used to calculate final percolation rate (ie. min/in)\*

\*\*Non-sandy soil testing procedure, if two consecutive reads (Tests A & B) show that less than 6.0" of water seeps away in less than 25 minutes, test hole shall be pre-soaked (filled) overnight. Following overnight presoak, Testing shall be performed for an additional 6 hours with measurements taken every 30 minutes. The final 30 minute test shall be used to calculate final percolation rate (ie, min/in)\*\*

READING*	TIMER		TIME INTERVAL	DEPTH (ft)	INITIAL W (in)	FINAL W (in)	∆W (in)	PERCOLATION RATE (in/hr)
1	TIMER		10	5'	20	14 7/8	5 1/8	30.15
2	TIMER	_	10	5'	20	15 2/8	4 6/8	27.94
3	TIMER		10	5'	20	15 3/8	4 5/8	27.21
4	TIMER		10	5'	20	15 3/8	4 5/8	27.21
5	TIMER		10	5'	20	15 4/8	4 4/8	26.47
6	TIMER		10	5'	20	15 4/8	4 4/8	26.47
7**							0	
8**							0	
9**							0	
10**							0	
11**							0	
12**							0	

Comments:

Presoak: Invert a 5 gallon jug of water over test hole so waters flows into and holds constant at least 5 times the holes radius inside test hole prior to testing.

Test Procedure: Fill test hole to 5 times the hole radius (ie. 8 inch diameter test hole = 4 inch radius = minimum 20 inches of water).

Leave Stake with ribbon attached within testing area. Label stake with Sladden Engineering, date & test number.

### **PERCOLATION RATE CONVERSION (PORCHET METHOD)**

l<sub>t≓</sub>

<u>ΔH 60 R</u>

 $\Delta t(r+2H_{avg})$ 

 $\Delta t$  (minutes)

 $\begin{array}{l} \mathsf{D}_{\mathsf{f}}\left(\mathsf{Final Depth to water}\right)\\ \mathsf{r}\left(\mathsf{hole radius in inches}\right)\\ \mathsf{D}_{0}\left(\mathsf{Initial Depth to water}\right)\\ \mathsf{D}_{t}\left(\mathsf{Total Depth of test hole}\right)\\ \mathsf{H}_{0}\left(\mathsf{initial height of water at selected time interval}\right)\\ \mathsf{H}_{0} = \mathsf{D}_{t}\text{-}\mathsf{D}_{0}\\ \mathsf{H}_{\mathsf{f}}\left(\mathsf{final height of water at the selected time interval}\right)\\ \mathsf{H}_{\mathsf{f}} = \mathsf{D}_{t}\text{-}\mathsf{D}_{\mathsf{f}}\\ \Delta\mathsf{H}\left(\mathsf{change in head over the time interval}\right)\\ \Delta\mathsf{H} = \mathsf{H}_{0}\text{-}\mathsf{H}_{\mathsf{f}}\end{array}$ 

 ${\rm H}_{\rm avg}$  (average head height over the time interval)

 $H_{avg} = (H_0 + H_f)/2$ 

Test Hole: P-1

∆t =	10
D <sub>f</sub> =	46.375
r =	4.00
D <sub>0</sub> =	40
D <sub>t</sub> =	60.00
H <sub>o</sub> =	20
H <sub>f</sub> =	13.625
ΔH =	6.38
H <sub>avg</sub> =	16.81

all in second as

l<sub>t</sub>= 4.07 in/hr



### PERCOLATION RATE CONVERSION (PORCHET METHOD)

∆H 60 R

 $I_{t=}$ 

 $\Delta t(r+2H_{avg})$ 

 $\Delta t$  (minutes)

D<sub>f</sub> (Final Depth to water)

r (hole radius in inches)  $D_0$  (Initial Depth to water)  $D_t$  (Total Depth of test hole)  $H_0$  (initial height of water at selected time interval)  $H_0 = D_t - D_0$   $H_f$  (final height of water at the selected time interval)  $H_f = D_t - D_f$   $\Delta H$  (change in head over the time interval)  $\Delta H = H_0 - H_f$ 

 $H_{avg}$  (average head height over the time interval)

 $H_{avg} = (H_0 + H_f)/2$ 

Test Hole: P-2

∆t =	10
D <sub>f</sub> ≕	44.5
r =	4.00
D <sub>0</sub> =	40
D <sub>t</sub> =	60.00
H <sub>0</sub> =	20
H <sub>f</sub> =	15.5
∆H =	4.50
H <sub>avg</sub> =	17.75

e - e e un a la seconda

l<sub>t</sub>= 2.73 in/hr



# Appendix 4: Historical Site Conditions

Phase I Environmental Site Assessment or Other Information on Past Site Use

Not Applicable

# Appendix 5: LID Infeasibility

LID Technical Infeasibility Analysis

Not Applicable

# Appendix 6: BMP Design Details

BMP Sizing, Design Details and other Supporting Documentation



THE STANDARD CDS2015-4-C CONFIGURATION IS SHOWN. ALTERN CONFIGURATIONS MAY BE COMBINED TO SUIT SITE REQUIREMENT
CONFIGURATION DESCRIPTION
GRATED INLET ONLY (NO INLET PIPE)
GRATED INLET WITH INLET PIPE OR PIPES
CURB INLET ONLY (NO INLET PIPE)
CURB INLET WITH INLET PIPE OR PIPES
SEPARATE OIL BAFFLE (SINGLE INLET PIPE REQUIRED FOR THIS CO
SEDIMENT WEIR FOR NIDEP / NICAT CONFORMING LINITS



(DIAMETER VARIES) N.T.S.

**GENERAL NOTES** 

- 1. CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.
- 2. DIMENSIONS MARKED WITH () ARE REFERENCE DIMENSIONS. ACTUAL DIMENSIONS MAY VARY.
- SOLUTIONS LLC REPRESENTATIVE, www.contechES.com
- MAINTENANCE CLEANING.

### INSTALLATION NOTES

- Α. SPECIFIED BY ENGINEER OF RECORD.
- B (LIFTING CLUTCHES PROVIDED).
- CONTRACTOR TO ADD JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS, AND ASSEMBLE STRUCTURE. C.
- D. CONTRACTOR TO PROVIDE, INSTALL, AND GROUT PIPES. MATCH PIPE INVERTS WITH ELEVATIONS SHOWN.
- CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ASSURE UNIT IS WATER TIGHT, HOLDING WATER TO FLOWLINE INVERT MINIMUM. IT IS E. SUGGESTED THAT ALL JOINTS BELOW PIPE INVERTS ARE GROUTED.



### CDS2015-4-C DESIGN NOTES

ATE CONFIGURATIONS ARE AVAILABLE AND ARE LISTED BELOW. SOME

NFIGURATION)

SITE SPECIFIC DATA REQUIREMENTS					
STRUCTURE ID			1		
			*		
WATER GUALITT					
PEAK FLOW RATE	E (CES OR L	Js)			
RETURN PERIOD	OF PEAK F	LOW (YRS)	•		
SCREEN APERTU	RE (2400 O	R 4700)	*		
PIPE DATA:	E DATA: I.E. MATERIAL DIAMETER				
INLET PIPE 1	*	*	*		
INLET PIPE 2		• •			
OUTLET PIPE		*	* *		
RIM ELEVATION			*		
ANTI-FLOTATION	BALLAST	WIDTH	HEIGHT		
*					
NOTES/SPECIAL REQUIREMENTS:					
* PER ENGINEER OF RECORD					

3. FOR FABRICATION DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHTS, PLEASE CONTACT YOUR CONTECH ENGINEERED

4. CDS WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. 5. STRUCTURE SHALL MEET AASHTO HS20 AND CASTINGS SHALL MEET HS20 (AASHTO M 306) LOAD RATING, ASSUMING GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION.

6. PVC HYDRAULIC SHEAR PLATE IS PLACED ON SHELF AT BOTTOM OF SCREEN CYLINDER. REMOVE AND REPLACE AS NECESSARY DURING

ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE

CDS2015-4-C

**INLINE CDS** 

STANDARD DETAIL

CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CDS MANHOLE STRUCTURE

Santa Ana Watershed - BMP Design Volume, V <sub>BMP</sub>						Lagandi		Required Entrie	
(Rev. 10-2011)						Legend:		Calculated Ce	
	NT	(Note this works	heet shall <u>only</u> be used	in conjunction	n with BMP	designs from the	LID BMP I	<u>Design Handbook</u>	) 2/21/2021
ompan	ly Name	Goodman an	d Associates				r	Date Case No	3/21/2021
ompon	u Dy W Project I	Aaron Skeen	8		Seaton Ar	Derris Area	Diverside	Case No	
Jinpan	ly Hojeet I		C .		Scatoli A		Riverside	<u> </u>	
				BMP I	dentificati	on			
MP NA	AME / ID	1							
			Mus	st match Nan	ne/ID used o	on BMP Design	Calculation	Sheet	
				Design I	Rainfall De	epth			
5th Per	centile, 24	l-hour Rainfal	ll Depth,				D <sub>85</sub> =	0.59	inches
om the	e Isohyetal	Map in Hand	book Appendix E						
			Drain	nage Manag	ement Are	a Tabulation			
		Ir	nsert additional rows	if needed to a	accommode	ate all DMAs dro	aining to the	e BMP	
				Effective	DMA		Design	Design Capture	Proposed Volume on
	DMA	DMA Area	Post-Project Surface	Imperivous	Runoff	DMA Areas x	Storm	Volume, <b>V<sub>BMP</sub></b>	Plans (cubic
	Type/ID	(square feet)	Туре	Fraction, I <sub>f</sub>	Factor	Runoff Factor	Depth (in)	(cubic feet)	feet)
	DA 1/A	119103	Concrete or Asphalt	1	0.89	106239.9			
	DA 1/B	34403	Ornamental Landscaping	0.1	0.11	3800.1			
	DA 1/C	49680	Roofs	1	0.89	44314.6			
	DA 1/D	10050	Concrete or Asphalt	1	0.89	8964.6			
			-						

Infiltration Tranch	Design Procedure	BMP ID	Lagandi	Required Entries		ies
	BMP 1		Legend.	Calc	culated Ce	ells
Company Name:	Goodman & Ass	ociates, Inc.		Date:	6/18/2	2021
Designed by:	Aaron Sk	eers	County/City C	Case No.:		
		Design Volume	:			
Enter the area tribu	tary to this feature, Max	x = 10 acres		$A_t =$	5	acres
Enter V <sub>BMP</sub> determi	ned from Section 2.1 of	f this Handbook		V <sub>BMP</sub> =	8,044	$ft^3$
	Calculate Maxim	nium Depth of the	Reservoir Layer			
Enter Infiltration ra	te			I =	2.7	in/hr
Enter Factor of Safe	etv. FS (unitless)			FS =	2	
Obtain from Table	l, Appendix A: "Infiltra	tion Testing" of t	his BMP Handboo	- ok		-
				n =	40	%
Calculate D <sub>1</sub> .	$D_1 = I (in/h)$	r) x 72 hrs		D <sub>1</sub> =	20.48	ft
	12 (in/ft) x	x (n /100) x FS	•			_
Enter depth to historic high groundwater mark (measured from finished grade)						
Enter depth to top of bedrock or impermeable layer (measured from finished grade)					100	ft
$D_2$ is the smaller of				-		-
Depth to groundwater - 11 ft; & Depth to impermeable layer - 6 ft $D_2 =$						ft
D <sub>MAX</sub> is the smaller	$D_{MAX}$ is the smaller value of $D_1$ and $D_2$ must be less than or equal to 8 feet. $D_{MAX} =$					
	,	Trench Sizing				
Enter proposed rese	ervoir laver depth D <sub>p</sub> , m	$ust be < D_{MAX}$		$D_R =$	8.00	ft
						_
Calculate the design	n depth of water, d <sub>w</sub>					
	Design d <sub>w</sub> =	$= (D_R) x (n/100)$	De	esign d <sub>w</sub> =	3.20	ft
Minimum Surface	Area, $A_S$ $A_{S}^{=}$	= V <sub>BMP</sub>		$A_{S} =$	2,514	-ft <sup>2</sup>
		d <sub>w</sub>		-		
Proposed Design St	urface Area			$A_D =$	3,663	$\mathrm{ft}^2$
		Minimum Widtl	$h = D_R + 1$ foot pe	ea gravel	9.00	ft
Sadimant Control P						
Sediment Control Provided? (Use pulldown)						
Geotechnical report attached? (Use pulldown)						
If the trench has been designed correctly, there should be no error messages on the spreadsheet.						
Notes: Dr 1s ac	Notes: Dr is adjusted to account for 100% porosity of the StormTech Chamber					
LIVE. LITE LYDICAL LUU% Averside County Best Manageme	ent Practice Design Handbook					
ANUARY 2010						



### User Inputs

SC-740

**Chamber Model:** 

### <u>Results</u>

System Volume and Bed S	Size
-------------------------	------

Outlet Control Structure:	Yes		<u>a bea 6.20</u>
Project Name:	DP Seaton Building 1	Installed Storage Volume:	7772.39 cubic ft.
Engineer:	Aaron Skeers	Storage Volume Per Chamber:	45.90 cubic ft.
Project Location:	California	Number Of Chambers Required:	96
Measurement Type:	Imperial	Number Of End Caps Required:	8
Required Storage Volume:	7602 cubic ft.	Chamber Rows:	4
Stone Porosity:	40%	Maximum Length:	178.70 ft.
Stone Foundation Depth:	6 in.	Maximum Width:	20.50 ft.
Stone Above Chambers:	6 in.	Approx. Bed Size Required:	3663.25 square ft.
Average Cover Over Chambers:	18 in.	System Compo	nents
Design Constraint Dimensions:	(26 ft. x 200 ft.)	<u>System compe</u>	

Amount Of Stone Required:311.67 cubic yardsVolume Of Excavation (Not Including474.87 cubic yardsFill):



\*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 24\* (600 mm).

ENGINEERED PRODUCT MANAGER	
ADS SALES REP	
PROJECT NO.	



ADVANCED DRAINAGE SYSTEMS, INC.

# **DP SEATON BUILDING 1**

# PERRIS, CA

# SC-740 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH SC-740.
- CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE 2 COPOLYMERS.
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS"
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD 4 IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS. THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE 5 THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
- CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, 6 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- REQUIREMENTS FOR HANDLING AND INSTALLATION: 7
  - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING. CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
  - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2"
  - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN 8 ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:
  - THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
  - THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
  - THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2418 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN.
- CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

- **IMPORTANT NOTES FOR THE BIDDING AND INSTALLATION OF THE SC-740 SYSTEM**
- STORMTECH SC-740 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE". 2.
- 3 CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
  - STONESHOOTER LOCATED OFF THE CHAMBER BED. ٠
  - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
  - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS. 4
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE. 5.
- 6. MAINTAIN MINIMUM - 6" (150 mm) SPACING BETWEEN THE CHAMBER ROWS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE 3/4-2" (20-50 mm). 7.
- 8 THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN FNGINEER
- 9. ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.

### NOTES FOR CONSTRUCTION EQUIPMENT

- 1 STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- 2. THE USE OF CONSTRUCTION EQUIPMENT OVER SC-740 CHAMBERS IS LIMITED: NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
  - WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
  - WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE"
- 3. FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.

### USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO THE CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.

CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.



NO RUBBER TIRED LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE







PLACE MINIMUM 12.50' OF ADSPLUS125 WOVEN GEOTEXTILE OVER BEDDING STONE AND UNDERNEATH CHAMBER FEET FOR SCOUR PROTECTION AT ALL CHAMBER INLET ROWS

NOTES

MANIFOLD SIZE TO BE DETERMINED BY SITE DESIGN ENGINEER. SEE TECH NOTE #6.32 FOR MANIFOLD SIZING GUIDANCE. DUE TO THE ADAPTATION OF THIS CHAMBER SYSTEM TO SPECIFIC SITE AND DESIGN CONSTRAINTS, IT MAY BE NECESSARY TO CUT AN COMPONENTS IN THE FIELD.

THE SITE DESIGN ENGINEER MUST REVIEW ELEVATIONS AND IF NECESSARY ADJUST GRADING TO ENSURE THE CHAMBER COVER REC THIS CHAMBER SYSTEM WAS DESIGNED WITHOUT SITE-SPECIFIC INFORMATION ON SOIL CONDITIONS OR BEARING CAPACITY. THE SIT

DETERMINING THE SUITABILITY OF THE SOIL AND PROVIDING THE BEARING CAPACITY OF THE INSITU SOILS. THE BASE STONE DEPTH MAY BE INCREASED PROVIDED.

NOT FOR CONSTRUCTION: THIS LAYOUT IS FOR DIMENSIONAL PURPOSES ONLY TO PROVE CONCEPT & THE REQUIRED STOR/

----- BED LIMITS

	*INVERT AB	OVE BAS	E OF CHAMBER					E,
Imported ALL 24* ISOLATOR ROW       0.10*         OF ALL 15* TOP CONNECTIONS       0.01*         Imported ALL 15* TOP CONNECTIONS       0.00*         Imported ALL 15* TOP CONNECTIONS       0.00*         Imported ALL 15*		INVERT*	MAX FLOW					JLTIMA
DEFALL 18' TOP CONNECTIONS 5.01' TYP OF ALL 18' BOTTOM 1.60' 1.00' 1	2 / TYP OF ALL 24" ISOLATOR ROW	0.10"		- -			I/A	S THE .
In contract to both communications       1.60°         Intermediation       5.00°         Intermediation       5.00°         Intermediation       1.60°	OF ALL 18" TOP CONNECTIONS	5.01"		N		AS	- Z Z	N. IT K
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD UNDUCUEPLE ADDITIONAL PIPE TO STANDARD		1.60"			Ą	1WN:	ECKE	RUCTIC
A 10 CFS OUT 4.0 CFS OUT 4.0 CFS OUT 0 0 0 0 0 0 0 0 0 0 0 0 0		5.00"		B	S,	DR/	В	ONSTF
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOL DURING HEAT TABLE MET TO BESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.			4.0 CFS OUT	0 <u>N</u>	<b>I</b> RR			R TO CC
ND COUPLE ADDITIONAL PIPE TO STANDARD MAINTEND TO ESCIONE REPORT SAFE MET. TO ESCIONE REPORT SAFE MET				EAT	Ę			PRIOF
ND COUPLE ADDITIONAL PIPE TO STANDARD MAINTENE ND COUPLE ADDITIONAL PIPE TO S				P SI		2020		AWING
ND COUPLE ADDITIONAL PIPE TO STANDARD MAINTEND ND COUPLE ADDITIONAL PIPE TO S				Ō		12/7/	CT #	HIS DR
ND COUPLE ADDITIONAL PIPE TO STANDARD MAINTEND ND COUPLE ADDITIONAL PIPE TO S						\TE:	SOJE	VIEW T
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOL 2012 MILLION AND AND AND AND AND AND AND AND AND AN				$\vdash$			L R	
ND COUPLE ADDITIONAL PIPE TO STANDARD MONITORIE TO STANDARD MONITORIES AND MONITO								ER SHA
ND COUPLE ADDITIONAL PIPE TO STANDARD MAILED RESPONSIBLE FOR COUPLE ADDITIONAL PIPE TO STANDARD MAILED RESPONSIBLE FOR CO DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE:				_				NGINEE ENTS.
Image: State of the state				TION				UIREME
ND COUPLE ADDITIONAL PIPE TO STANDARD MAINTEND TO BOOK TO BOO				CRIP				te des T reqi
Image: State of the state				DES(				RHE SI'
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD								AND PF
ND COUPLE ADDITIONAL PIPE TO STANDARD MAINIFUL								SENTA IONS, J
ND COUPLE ADDITIONAL PIPE TO STANDARD MAINIFUL UNDERGENTING AND DECOUPLE ADDITIONAL PIPE TO STANDARD MAINIFUL UNDERGENTING AND DECOUPLE ADDITIONAL PIPE TO STANDARD MAINIFUL UNDERGENTING U				¥				REPRE
ND COUPLE ADDITIONAL PIPE TO STANDARD MAINTEN TO EXCLUSION ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE:				Ч Ч				OJECT WS, RE
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLIA UNIT COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLI				DRW				ER PRO
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD URINGENERS ARE MET. TO EDESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.								R OTHI PLICAE
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD URINEMENTS ARE MET. TO EDESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.				R				EER O
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD UIREMENTS ARE MET. T DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.							UM NO	ENGIN MEET #
A COULT HAVE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE. AGE VOLUME CAN BE ACHIEVED ON SITE.		0 0			Ś	r Quality	-   0606 ECH.C	ESIGN
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD UTICAL BASE OF A 1300 TO DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE. AGE VOLUME CAN BE ACHIEVED ON SITE.	B	-18.5				on Wate	LL   CT TORMT	SITE D
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD UTIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.						Pretenti	CKY HI	PF THE SOCIAT
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.					5	Detention	894   VO	LION O
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD QUIREMENTS ARE MET. TO DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.							4VENUI	DIRECT
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.						)	888  888- 8   888-	R THE I
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.					Ż		CROM 29-8188	UNDEF S) DEF
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.					V	J	520 860-52	O ADS
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.								DED T(
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.					026	ļ.	THE .	PROVI HAT TH
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.				ANE	H 43 73			ATION URE TI
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.				UEW	0, O			IFORM O ENS
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.					-1ARI 0-73			ON IN
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.				4640	HILL 1-80			BASEC
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.				7	n.	15 <sup>1</sup>		ARED
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.				X		EWS,		A PREF
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. THE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.				ŀ		2603		S BEEN F THE :
ND COUPLE ADDITIONAL PIPE TO STANDARD MANIFOLD DUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONSIBLE FOR OR DECREASED ONCE THIS INFORMATION IS AGE VOLUME CAN BE ACHIEVED ON SITE.								NG HAS
QUIREMENTS ARE MET.         THE DESIGN ENGINEER IS RESPONSIBLE FOR         OR DECREASED ONCE THIS INFORMATION IS         AGE VOLUME CAN BE ACHIEVED ON SITE.	ND COUPLE ADDITIONAL PIPE TO S	STANDAF	RD MANIFOLD	E				DRAWIN DNSIBIL
OR DECREASED ONCE THIS INFORMATION IS SHEET AGE VOLUME CAN BE ACHIEVED ON SITE. 2 OF 6	QUIREMENTS ARE MET. TE DESIGN ENGINEER IS RESPONS		२	E				THIS D
AGE VOLUME CAN BE ACHIEVED ON SITE. 2 OF 6	OR DECREASED ONCE THIS INFOR	RMATION	IS		S	SHEE	Т	_
	AGE VOLUME CAN BE ACHIEVED C	N SITE.			2	OF	6	

# ACCEPTABLE FILL MATERIALS: STORMTECH SC-740 CHAMBER SYSTEMS

	MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMF
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER.	ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS.	N/A	PREPA INSTA
С	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 18" (450 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145 <sup>1</sup> A-1, A-2-4, A-3 OR AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN CC THE CHAM 6" (150 mr WELL GI PROC VEHICLE
В	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57	
А	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57	PLATE C

PLEASE NOTE:

THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE". 1.

STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6" (150 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR. 2

WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR 3. COMPACTION REQUIREMENTS.

ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION. 4



## NOTES:

- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS" 1.
- 2. SC-740 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 3 THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- 4. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- 5. REQUIREMENTS FOR HANDLING AND INSTALLATION:
  - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
  - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
  - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 • LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.

### PACTION / DENSITY REQUIREMENT

ARE PER SITE DESIGN ENGINEER'S PLANS. PAVED LLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.

MPACTIONS AFTER 12" (300 mm) OF MATERIAL OVER BERS IS REACHED. COMPACT ADDITIONAL LAYERS IN m) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR RADED MATERIAL AND 95% RELATIVE DENSITY FOR ESSED AGGREGATE MATERIALS. ROLLER GROSS WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAMIC FORCE NOT TO EXCEED 20,000 lbs (89 kN).

NO COMPACTION REQUIRED.

COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE.<sup>2,3</sup>

			REV DRW C	Ŧ	DESCRIPTION		A RUILDING 1
	4640 TRUEMAN BLVD						
י א	1-800-733-7473					PERR	RIS, CA
sr (	ADVANCED DRAINAGE SYSTEMS, INC.	こうりここうの					
HEE DF		Detention•Retention•Water Quality				DATE: 12/7/2020	DRAWN: AS
Т							
				_			
6		860-529-8188   888-892-2694   WWW.STORMTECH.COM					
	THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDI RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE	ED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEE I PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETALS MEET ALL	R OR OTHER PROJEC - APPLICABLE LAWS, F	T REPRESENTATIVE. REGULATIONS, AND PI	THE SITE DESIGN ENGINEER SHALI ROJECT REQUIREMENTS.	L REVIEW THIS DRAWING PRIOR TO C	CONSTRUCTION. IT IS THE ULTIMAT



### SC-740 ISOLATOR ROW PLUS DETAIL

NTS

### **INSPECTION & MAINTENANCE**

### INSPECT ISOLATOR ROW PLUS FOR SEDIMENT STEP 1)

- A. INSPECTION PORTS (IF PRESENT)
  - A.1. REMOVE/OPEN LID ON NYLOPLAST INLINE DRAIN
  - A.2. REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
  - USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL) A.3.
  - A.4.
  - A.5. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
- B. ALL ISOLATOR PLUS ROWS
- B.1. REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS
- USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW PLUS THROUGH OUTLET PIPE B.2.
- i) MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY ii) FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE
- IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
- B.3.
- STEP 2) CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS
  - A. A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45" (1.1 m) OR MORE IS PREFERRED
  - APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN Β.
  - C. VACUUM STRUCTURE SUMP AS REQUIRED
- STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.
- STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

### NOTES

- 1. INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS.
- 2. CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.

			-	_	VOVEN GEOTEXTILE BETWEEN MBERS US FABRIC WITHOUT SEAMS		SC-740 END CAP	ON PORT	
	4640 TRUEMAN BLVD		REV	DRW CH	¥	DESCRIPTION	DP SEAT	ON BUILDING 1	
s 4(	DEVANCED PRIMACE SYSTEMS, INC. ADVANCED PRIMACE SYSTEMS, INC. 1200-733-7473	StormTech					B	RRIS, CA	
hee" OF		Detention-Retention-Water Quality					DATE: 12/7/2020	DRAWN: AS	
т 6		520 CROMWELL AVENUE   ROCKY HILL   CT   06067 860-529-8188   888-892-2694   WWW.STORMTECH.COM					PROJECT #:	CHECKED: N/A	
;	THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE	ED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEE : PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET AL	ER OR OTH	IER PROJECT BLE LAWS, RI	REPRESENT/ EGULATIONS,	ATIVE. THE SITE DESIGN ENGINEER S AND PROJECT REQUIREMENTS.	SHALL REVIEW THIS DRAWING PRIOR	TO CONSTRUCTION. IT IS THE ULTIMAT	
									1





51.0" X 30.0" X 85.4"	(1295 m
45.9 CUBIC FEET	(1.30 m <sup>3</sup>
74.9 CUBIC FEET	(2.12 m <sup>3</sup>
75 0 lbs	(33 6 kg)

		-
STUB	Α	
6" (150 mm)	10.0" (277 mm)	
0 (130 mm)	10.9 (277 1111)	
8" (200 mm)	12.2" (310 mm)	
0 (200 mm)	12.2 (310 1111)	
10" (250 mm)	13 //" (3/0 mm)	
10 (200 mm)	10.4 (040 mm)	
12" (300 mm)	14 7" (373 mm)	
12 (300 mm)	14.7 (373 1111)	
15" (375 mm)	18 /" (/67 mm)	
15 (37511111)	10.4 (407 11111)	
18" (450 mm)	10.7" (500 mm)	
10 (400 mm)	19.7 (500 mm)	
24" (600 mm)	18.5" (470 mm)	
24" (600 mm)	18.5" (470 mm)	
	<b>STUB</b> 6" (150 mm) 8" (200 mm) 10" (250 mm) 12" (300 mm) 15" (375 mm) 18" (450 mm) 24" (600 mm) 24" (600 mm)	STUB         A           6" (150 mm)         10.9" (277 mm)           8" (200 mm)         12.2" (310 mm)           10" (250 mm)         13.4" (340 mm)           10" (250 mm)         13.4" (340 mm)           12" (300 mm)         14.7" (373 mm)           15" (375 mm)         18.4" (467 mm)           18" (450 mm)         19.7" (500 mm)           24" (600 mm)         18.5" (470 mm)           24" (600 mm)         18.5" (470 mm)

DIAMETER OF THE STUB IS FLUSH WITH THE BOTTOM OF THE END CAP. FOR ADDITIONAL INFORMATION CONTACT STORMTECH AT 1-888-892-2694.

\* FOR THE SC740EPE24B/SC740EPE24BR THE 24" (600 mm) STUB LIES BELOW THE BOTTOM OF THE END CAP APPROXIMATELY 1.75" (44 mm). BACKFILL MATERIAL SHOULD BE REMOVED FROM BELOW THE N-12 STUB SO THAT THE FITTING SITS LEVEL.

SHEET 5 OF 6

NOTE: ALL DIMENSIONS ARE NOMINAL



### NOTES

- 1. 8-30" (200-750 mm) GRATES/SOLID COVERS SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
- 12-30" (300-750 mm) FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
   DRAIN BASIN TO BE CUSTOM MANUFACTURED ACCORDING TO PLAN DETAILS
- DRAINAGE CONNECTION STUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D3212 4.
- FOR CORRUGATED HDPE (ADS & HANCOR DUAL WALL) & SDR 35 PVC 5. FOR COMPLETE DESIGN AND PRODUCT INFORMATION: WWW.NYLOPLAST-US.COM
- 6. TO ORDER CALL: 800-821-6710

Α	PART #	GRATE/S	SOLID COVER (	OPTIONS
8" (200 mm)	2808AG	PEDESTRIAN LIGHT DUTY	STANDARD LIGHT DUTY	SOLID LIGHT DUTY
10" (250 mm)	2810AG	PEDESTRIAN LIGHT DUTY	STANDARD LIGHT DUTY	SOLID LIGHT DUTY
12"	2812AG	PEDESTRIAN	PEDESTRIAN STANDARD AASHTO	
(300 mm)		AASHTO H-10	AASHTO H-10 H-20	
15"	2815AG	PEDESTRIAN	STANDARD AASHTO	SOLID
(375 mm)		AASHTO H-10	H-20	AASHTO H-20
18"	2818AG	PEDESTRIAN	STANDARD AASHTO	SOLID
(450 mm)		AASHTO H-10	H-20	AASHTO H-20
24"	2824AG	PEDESTRIAN	STANDARD AASHTO	SOLID
(600 mm)		AASHTO H-10	H-20	AASHTO H-20
30"	2830AG	PEDESTRIAN	STANDARD AASHTO	SOLID
(750 mm)		AASHTO H-20	H-20	AASHTO H-20

					REV	JRW CF	¥	DESCRIPTION		
(	4640 TRL	JEMAN BLVD	(	3130 VERONA AVE						
6 6	anvancen pranace systems inc. 1-800-733	, UH 43020	e C	BUFORD, GA 30518 PHN (770) 932-2443					PERF	RIS, CA
OF			Nyloplast	<ul> <li>FAX (770) 932-2490</li> <li>www.nyloplast-us.com</li> </ul>					DATE: 12/7/2020	DRAWN: AS
6	T								-PROJECT #:	CHECKED: N/A
	THIS DRAWING HAS BEEN PREPARED BASED ON INF RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO	CORMATION PROVID	ED TO ADS UNDER THE DIRECTION PRODUCT(S) DEPICTED AND ALL A	OF THE SITE DESIGN ENGINEI SSOCIATED DETAILS MEET AL	EER OR OTH	ER PROJECT 3LE LAWS, RE	REPRESENTA1 EGULATIONS, A	TIVE. THE SITE DESIGN ENGINEER SHALI ND PROJECT REQUIREMENTS.	L REVIEW THIS DRAWING PRIOR TO	CONSTRUCTION. IT IS THE ULTIMATE



	<u>Santa</u>	Ana Wat	ershed - BMP I	Design Vo	lume, V <sub>B</sub>	BMP	Legend:		Required Ent
			(Rev. 10-2011)						Calculated C
	<b>N</b> 7	(Note this works)	heet shall <u>only</u> be used	in conjunction	n with BMP	designs from the	LID BMP L	<u>Design Handbook</u>	)
ompan	y Name	Goodman an	d Associates					Date	3/21/2021
signe	a by Droigot l	Aaron Skeers	8		Caston Ar		Dimensida	Case No	
mpan	ly Project	Number/mame	e		Seaton Av	e Perris Area	Riverside		
				BMP I	dentificati	on			
MP NA	AME / ID	2							
			Mus	st match Nan	ne/ID used o	on BMP Design	Calculation	Sheet	
				Design I	Rainfall De	epth			
th Per	centile, 24 Isohvetal	l-hour Rainfal Man in Hand	l Depth, book Appendix F				D <sub>85</sub> =	0.59	inches
JIII the	, isonyetai	wap in Haid							
				hage Manage	ement Are	a Tabulation		- 040	
ſ		lr	nsert additional rows	if needed to d	accommoda	ate all DMAs dro	aining to the	e BIVIP	Proposed
				Effective	DMA		Design	Design Capture	Volume on
	DMA	DMA Area	Post-Project Surface	Imperivous	Runoff	DMA Areas x	Storm	Volume, <b>V<sub>BMP</sub></b>	Plans (cubic
	Type/ID	(square feet)	Туре	Fraction, I <sub>f</sub>	Factor	Runoff Factor	Depth (in)	(cubic feet)	feet)
	DA 2/A	123882	Concrete or Asphalt	1	0.89	110502.7			
	DA 2/B	33940	Ornamental	0.1	0.11	3748.9			
	DA 2/C	49680	Roofs	1	0.89	44314.6			
		207502	7	otal		158566.2	0.59	7809.4	7809.4

Infiltration Tranch	Dagian Procedure	BMP ID	Lagandi	Requ	uired Entries	
	- Design Procedure	BMP 2	Legend.	Calc	culated Ce	ells
Company Name:	Goodman & As	sociates, Inc.	_	Date:	6/18/2	2021
Designed by:	Aaron S	keers	County/City C	Case No.:		
Enter the area tribu	5	acres				
Enter V <sub>BMP</sub> determi	ned from Section 2.1 o	of this Handbook		V <sub>BMP</sub> =	7,809	ft <sup>3</sup>
	Calculate Maxin	nium Depth of the	Reservoir Layer			
Enter Infiltration ra	te			I =	2.7	in/hr
Enter Factor of Safe	etv. FS (unitless)			FS =	2	
Obtain from Table	l, Appendix A: "Infiltr	ation Testing" of t	his BMP Handbo	- ok		-
	n =	40	%			
Calculate D <sub>1</sub> .	$D_1 = I (in/h)$	nr) x 72 hrs		D <sub>1</sub> =	20.25	ft
	12 (in/ft)	x (n /100) x FS	-			_
Enter depth to histo	100	ft				
Enter depth to top o	100	ft				
$D_2$ is the smaller of		_				
Depth to groundwa	89.0	ft				
D <sub>MAX</sub> is the smaller	D <sub>MAX</sub> =	8.0	ft			
		Trench Sizing				_
Enter proposed rese	ervoir layer depth $D_{R}$ , 1	must be $\leq D_{MAX}$		$D_R =$	8.00	ft
		- MAA		-		_
Calculate the design	n depth of water, $d_w$					
	Design d <sub>w</sub>	$= (D_R) x (n/100)$	De	esign d <sub>w</sub> =	3.20	ft
Minimum Surface	Area, A <sub>S</sub> A <sub>S</sub>	= V <sub>BMP</sub>		$A_{S} =$	2,440	-ft <sup>2</sup>
		d <sub>w</sub>				_
Proposed Design St	urface Area			$A_D =$	3,741	$\mathrm{ft}^2$
		Minimum Widt	$h = D_R + 1$ foot pe	- ea gravel	9.00	ft
				-		
Sediment Control P	rovided? (Use pulldov	vn)				
Geotechnical report	t attached? (Use pulldo	own)				
	If the trench has been designed c	orrectly, there should be no e	error messages on the spread	sheet.		
Notes: Dr is ac	djusted to account for	r 100% porosity	of the StormTec	h Chambe	r	
IVS. THE TVPICAL 100% Riverside County Best Manageme	ent Practice Design Handbook	th 40% porosity)				
ANUARY 2010						


## <u>User Inputs</u>

SC-740

**Chamber Model:** 

### **Results**

System Volume and Bed S	Size
-------------------------	------

Outlat Control Structure:	Voc	<u>System volume and</u>	
outlet control structure.	les		
Project Name:	DP Seaton Building 2	Installed Storage Volume:	7937.06 cubic ft.
Engineer:	Aaron Skeers	Storage Volume Per Chamber:	45.90 cubic ft.
Project Location:	California	Number Of Chambers Required:	98
Measurement Type:	Imperial	Number Of End Caps Required:	8
Required Storage Volume:	7809 cubic ft.	Chamber Rows:	4
Stone Porosity:	40%	Maximum Length:	185.81 ft.
Stone Foundation Depth:	6 in.	Maximum Width:	20.50 ft.
Stone Above Chambers:	6 in.	Approx. Bed Size Required:	3741.53 square ft.
Average Cover Over Chambers:	18 in.	System Compo	nants
Design Constraint Dimensions:	(26 ft. x 200 ft.)	<u>System compe</u>	

Amount Of Stone Required: 318.41 cubic yards Volume Of Excavation (Not Including 485.01 cubic yards Fill):



\*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 24\* (600 mm).

ENGINEERED PRODUCT MANAGER	
ADS SALES REP	
PROJECT NO.	



ADVANCED DRAINAGE SYSTEMS, INC.

# **DP SEATON BUILDING 2**

# PERRIS, CA

# SC-740 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH SC-740.
- CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE 2 COPOLYMERS.
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS"
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD 4 IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS. THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE 5 THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
- CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787, 6 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) AASHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2) MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- REQUIREMENTS FOR HANDLING AND INSTALLATION: 7
  - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING. CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
  - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2"
  - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN 8 ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:
  - THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
  - THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
  - THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2418 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN.
- CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.

- **IMPORTANT NOTES FOR THE BIDDING AND INSTALLATION OF THE SC-740 SYSTEM**
- STORMTECH SC-740 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE". 2.
- 3 CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
  - STONESHOOTER LOCATED OFF THE CHAMBER BED. ٠
  - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
  - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS. 4
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE. 5.
- 6. MAINTAIN MINIMUM - 6" (150 mm) SPACING BETWEEN THE CHAMBER ROWS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE 3/4-2" (20-50 mm). 7.
- 8 THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN FNGINEER
- 9. ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.

### NOTES FOR CONSTRUCTION EQUIPMENT

- 1 STORMTECH SC-740 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
- 2. THE USE OF CONSTRUCTION EQUIPMENT OVER SC-740 CHAMBERS IS LIMITED: NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
  - WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".
  - WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE"
- 3. FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.

### USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO THE CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.

CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.



NO RUBBER TIRED LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE







PLACE MINIMUM 12.50' OF ADSPLUS125 WOVEN GEOTEXTILE OVER BEDDING STONE AND UNDERNEATH CHAMBER FEET FOR SCOUR PROTECTION AT ALL CHAMBER INLET ROWS

NOTES

MANIFOLD SIZE TO BE DETERMINED BY SITE DESIGN ENGINEER. SEE TECH NOTE #6.32 FOR MANIFOLD SIZING GUIDANCE. DUE TO THE ADAPTATION OF THIS CHAMBER SYSTEM TO SPECIFIC SITE AND DESIGN CONSTRAINTS, IT MAY BE NECESSARY TO CUT AN COMPONENTS IN THE FIELD.

THE SITE DESIGN ENGINEER MUST REVIEW ELEVATIONS AND IF NECESSARY ADJUST GRADING TO ENSURE THE CHAMBER COVER REC THIS CHAMBER SYSTEM WAS DESIGNED WITHOUT SITE-SPECIFIC INFORMATION ON SOIL CONDITIONS OR BEARING CAPACITY. THE SIT

DETERMINING THE SUITABILITY OF THE SOIL AND PROVIDING THE BEARING CAPACITY OF THE INSITU SOILS. THE BASE STONE DEPTH MAY BE INCREASED PROVIDED.

NOT FOR CONSTRUCTION: THIS LAYOUT IS FOR DIMENSIONAL PURPOSES ONLY TO PROVE CONCEPT & THE REQUIRED STOR/

----- BED LIMITS

*INVERT AB	OVE BAS	E OF CHAMBER					ЧЕ
	INVERT*	MAX FLOW					JLTIMA
/ TYP OF ALL 24" ISOLATOR ROW	0.10"		2			A'	S THE (
OF ALL 18" TOP CONNECTIONS	5.01"		2 Z		AS	Z Z	N. IT IS
TYP OF ALL 18 BOTTOM	1.60"			Ă	NN:	CKE	UCTIO
	5.00"		BU	S, C	DRA	풍	ONSTR
		4.0 CES OUT	NO	<b>R</b> R			10 00
		4.0 01 0 001	Ā	Ц			PRIOR
			S S		2020		AWING
			ä		12/7/:	CT #	HIS DR.
					Ë	SOJE	IEW TI
			$\vdash$			ЦЦ НЦ	LL REV
							R SHA
							IGINEE NTS.
			TION				IGN EN
			CRIP				TE DES T REQL
			DES(				THE SIT
			-				AND PF
							SENTA
►			¥				REPRE
			Ъ С				DUECT NS, RE
			DRW				ER PRO
							R OTH PLICAE
	<b></b>	_	R				IEER O ALL AP
				•	<u> </u>	57 XOM	ENGIN MEET,
	50'			-	er Quality	T   0606	DESIGN
B	- 18.5 - 20.5				on Wate	LL   CI TORMI	SITE D
					-Retent	CKY HI WWW.S	PF THE SOCIA
				5	Detention	E   RO 694   V	TION C
		_				AVENU 1-892-21	DIREC
					2	AWELL 38   886	ER THE
				Į	Ā	0 CRON 529-81	S UNDE
						52 860-!	TO AD( ODUC)
				)			VIDED HE PR
				3026	30,	3	N PRO
				0H 4 473			MATIO
				33-7			INFOR TO EN
			10 TE	LIAF			ED ON
			191	₽ <u></u> ₽ <u></u> ₽	īc	,	ED BAS
			7	Â			EPARE
					SYSTEM		EN PR E SITE
					NAGE S		HAS BE
	STANDAR						WING F
QUIREMENTS ARE MET	STANDAF	NU MANIFULD				,⊥⊥	S DRAV
TE DESIGN ENGINEER IS RESPONS	SIBLE FOR	R			₹   2µгг	т	THI REG
OR DECREASED ONCE THIS INFOR	RMATION	IS		2		- -	
AGE VOLUME CAN BE ACHIEVED O	N SITE.			2		U	

# ACCEPTABLE FILL MATERIALS: STORMTECH SC-740 CHAMBER SYSTEMS

	MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMF
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER.	ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS.	N/A	PREPA INSTA
С	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 18" (450 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145 <sup>1</sup> A-1, A-2-4, A-3 OR AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	BEGIN CC THE CHAM 6" (150 mr WELL GF PROC VEHICLE
В	EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57	
А	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57	PLATE C

PLEASE NOTE:

THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE". 1.

STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6" (150 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR. 2

WHERE INFILTRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT. FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR 3. COMPACTION REQUIREMENTS.

ONCE LAYER 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP TO THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO REPLACE THE MATERIAL REQUIREMENTS OF LAYER 'C' OR 'D' AT THE SITE DESIGN ENGINEER'S DISCRETION. 4



## NOTES:

- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS" 1.
- 2. SC-740 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 3 THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- 4. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- 5. REQUIREMENTS FOR HANDLING AND INSTALLATION:
  - TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
  - TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2".
  - TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 • LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.

### PACTION / DENSITY REQUIREMENT

ARE PER SITE DESIGN ENGINEER'S PLANS. PAVED LLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.

MPACTIONS AFTER 12" (300 mm) OF MATERIAL OVER BERS IS REACHED. COMPACT ADDITIONAL LAYERS IN m) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR RADED MATERIAL AND 95% RELATIVE DENSITY FOR ESSED AGGREGATE MATERIALS. ROLLER GROSS WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAMIC FORCE NOT TO EXCEED 20,000 lbs (89 kN).

NO COMPACTION REQUIRED.

COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE.<sup>2,3</sup>

			REV DRW CHK	DESCRIPTION	DP SFATON	I BUILDING 2
2	1-800-733-7473				PERR	tis, ca
Sł	ADVANCED DRAINAGE SYSTEMS, INC.					-
		Detention• Retention• Water Quality			DATE: 12/7/2020	DRAWN: AS
T		520 CROMMELL AVENUE   ROCKY HILL   CT   06067				
6		860-529-8188   888-892-2694   WWW.STORMTECH.COM				
	THIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVIDE RESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE F	ED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET AL	ER OR OTHER PROJECT REPRESE L APPLICABLE LAWS, REGULATION	NTATIVE. THE SITE DESIGN ENGINEER SHA VS, AND PROJECT REQUIREMENTS.	ALL REVIEW THIS DRAWING PRIOR TO C	ONSTRUCTION. IT IS THE ULTIMA



### SC-740 ISOLATOR ROW PLUS DETAIL

NTS

### **INSPECTION & MAINTENANCE**

### INSPECT ISOLATOR ROW PLUS FOR SEDIMENT STEP 1)

- A. INSPECTION PORTS (IF PRESENT)
  - A.1. REMOVE/OPEN LID ON NYLOPLAST INLINE DRAIN
  - A.2. REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
  - USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG LOWER A CAMERA INTO ISOLATOR ROW PLUS FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL) A.3.
  - A.4.
  - A.5. IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
- B. ALL ISOLATOR PLUS ROWS
- B.1. REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW PLUS
- USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW PLUS THROUGH OUTLET PIPE B.2.
- i) MIRRORS ON POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY ii) FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE
- IF SEDIMENT IS AT, OR ABOVE, 3" (80 mm) PROCEED TO STEP 2. IF NOT, PROCEED TO STEP 3.
- B.3.
- STEP 2) CLEAN OUT ISOLATOR ROW PLUS USING THE JETVAC PROCESS
  - A. A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45" (1.1 m) OR MORE IS PREFERRED
  - APPLY MULTIPLE PASSES OF JETVAC UNTIL BACKFLUSH WATER IS CLEAN Β.
  - C. VACUUM STRUCTURE SUMP AS REQUIRED
- STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.
- STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

### NOTES

- 1. INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS.
- 2. CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.

					I GEOTEXTILE BETWEEN RS BRIC WITHOUT SEAMS		D CAP		
	4640 TRIFEMAN BLVD		REV DF	RW CH	×	DESCRIPTION	DP SEATON	N BUILDING 2	
s 4	ANANCED PRIMICE SYSTEMS INC. 1-800-733-7473	Ctormich.					PERF	RIS, CA	
ore OF		Detertion-Retention-Water Quality					DATE: 12/7/2020	DRAWN: AS	
т 6		520 CROMWELL AVENUE   ROCKY HILL   CT   06067 860-529-8188   888-892-2694   WWW.STORMTECH.COM					PROJECT #:	CHECKED: N/A	
;	HIS DRAWING HAS BEEN PREPARED BASED ON INFORMATION PROVID (ESPONSIBILITY OF THE SITE DESIGN ENGINEER TO ENSURE THAT THE	IED TO ADS UNDER THE DIRECTION OF THE SITE DESIGN ENGINEE PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL	ER OR OTHER L APPLICABLE	R PROJECT E LAWS, RE	REPRESENTA GULATIONS,	ATIVE. THE SITE DESIGN ENGINEER SI AND PROJECT REQUIREMENTS.	HALL REVIEW THIS DRAWING PRIOR TO 0	CONSTRUCTION. IT IS THE ULTIMATE	
SHEET 4 OF 6	AB40 TRUEMAN BLVD ADVANCED DRAINAGE SYSTEMS, INC. 1-800-733-7473 1-800-733-7473 1-800-733-7473 1-800-733-7473 1-800-733-7473	EDITO ADDITING CONTRACTION OF THE STREET ALL AND ALL ASSOCIATED DEFINITION OF THE STREET DESIGN FOR THE STREET OF TO ADDITING THE STREET ALL ASSOCIATED DETAILS MEET ALL PRODUCT(S) DEPICTED AND ALL ASSOCIATED DETAILS MEET ALL	REV DF	CH CH CH	K REPRESENTA GULATIONS, 1	DESCRIPTION	DP SEATON PERF DATE: 12/7/2020 PROJECT #: HALL REVIEW THIS DRAWING PRIOR TO (	N BUILDING : RIS, CA DRAWN: AS CHECKED: N/A CONSTRUCTION. IT IS TI	2 de ultimate





51.0" X 30.0" X 85.4"	(1295 m
45.9 CUBIC FEET	(1.30 m <sup>3</sup>
74.9 CUBIC FEET	(2.12 m <sup>3</sup>
75 0 lbs	(33 6 kg)

		-
STUB	Α	
6" (150 mm)	10.0" (277 mm)	
0 (130 mm)	10.9 (277 1111)	
8" (200 mm)	12.2" (310 mm)	
0 (200 mm)	12.2 (310 1111)	
10" (250 mm)	13 //" (3/0 mm)	
10 (200 mm)	10.4 (040 mm)	
12" (300 mm)	14 7" (373 mm)	
12 (300 mm)	14.7 (373 1111)	
15" (375 mm)	18 /" (/67 mm)	
15 (37511111)	10.4 (407 11111)	
18" (450 mm)	10.7" (500 mm)	
10 (400 mm)	19.7 (300 mm)	
24" (600 mm)	18.5" (470 mm)	
24" (600 mm)	18.5" (470 mm)	
	<b>STUB</b> 6" (150 mm) 8" (200 mm) 10" (250 mm) 12" (300 mm) 15" (375 mm) 18" (450 mm) 24" (600 mm) 24" (600 mm)	STUB         A           6" (150 mm)         10.9" (277 mm)           8" (200 mm)         12.2" (310 mm)           10" (250 mm)         13.4" (340 mm)           10" (250 mm)         13.4" (340 mm)           12" (300 mm)         14.7" (373 mm)           15" (375 mm)         18.4" (467 mm)           18" (450 mm)         19.7" (500 mm)           24" (600 mm)         18.5" (470 mm)           24" (600 mm)         18.5" (470 mm)

DIAMETER OF THE STUB IS FLUSH WITH THE BOTTOM OF THE END CAP. FOR ADDITIONAL INFORMATION CONTACT STORMTECH AT 1-888-892-2694.

\* FOR THE SC740EPE24B/SC740EPE24BR THE 24" (600 mm) STUB LIES BELOW THE BOTTOM OF THE END CAP APPROXIMATELY 1.75" (44 mm). BACKFILL MATERIAL SHOULD BE REMOVED FROM BELOW THE N-12 STUB SO THAT THE FITTING SITS LEVEL.

NOTE: ALL DIMENSIONS ARE NOMINAL

SHEET 5 OF 6



### NOTES

- 1. 8-30" (200-750 mm) GRATES/SOLID COVERS SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
- 12-30" (300-750 mm) FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
   DRAIN BASIN TO BE CUSTOM MANUFACTURED ACCORDING TO PLAN DETAILS
- DRAINAGE CONNECTION STUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D3212 4.
- FOR CORRUGATED HDPE (ADS & HANCOR DUAL WALL) & SDR 35 PVC 5. FOR COMPLETE DESIGN AND PRODUCT INFORMATION: WWW.NYLOPLAST-US.COM
- 6. TO ORDER CALL: 800-821-6710

Α	PART #	GRATE/S	SOLID COVER (	OPTIONS
8" (200 mm)	2808AG	PEDESTRIAN LIGHT DUTY	STANDARD LIGHT DUTY	SOLID LIGHT DUTY
10" (250 mm)	2810AG	PEDESTRIAN LIGHT DUTY	STANDARD LIGHT DUTY	SOLID LIGHT DUTY
12"	2812AG	PEDESTRIAN	STANDARD AASHTO	SOLID
(300 mm)		AASHTO H-10	H-20	AASHTO H-20
15"	2815AG	PEDESTRIAN	STANDARD AASHTO	SOLID
(375 mm)		AASHTO H-10	H-20	AASHTO H-20
18"	2818AG	PEDESTRIAN	STANDARD AASHTO	SOLID
(450 mm)		AASHTO H-10	H-20	AASHTO H-20
24"	2824AG	PEDESTRIAN	STANDARD AASHTO	SOLID
(600 mm)		AASHTO H-10	H-20	AASHTO H-20
30"	2830AG	PEDESTRIAN	STANDARD AASHTO	SOLID
(750 mm)		AASHTO H-20	H-20	AASHTO H-20

					REV D	RW C	Ŧ	DESCRIPTION	DP SFATON	L RI III DING 2
6			(	3130 VERONA AVE						
5		1-800-733-7473		BUFORD, GA 30518 PHN (770) 932-2443					PERF	RIS, CA
ын С										
)F			Nyloplast	www.nyloplast-us.com					DATE: 12/7/2020	DRAWN: AS
f.			*							
6									PROJECT #:	CHECKED: N/A
	THIS DRAWING HAS BEEN PREPARED RESPONSIBILITY OF THE SITE DESIGN	BASED ON INFORMATION PROVID	E PRODUCT(S) DEPICTED AND ALL A	OF THE SITE DESIGN ENGINEE SSOCIATED DETAILS MEET ALI	ER OR OTHE L APPLICABI	ER PROJEC	T REPRESENT EGULATIONS,	ATIVE. THE SITE DESIGN ENGINEER SHALL AND PROJECT REQUIREMENTS.	REVIEW THIS DRAWING PRIOR TO (	CONSTRUCTION. IT IS THE ULTIMATE



# Appendix 7: Hydromodification

Supporting Detail Relating to Hydrologic Conditions of Concern

HCOC Applicability Map



Maybe not HCOC?



# WQMP Project Report

### **County of Riverside Stormwater Program**

Santa Ana River Watershed Geodatabase

Sunday, March 21, 2021

Note: The information provided in this report and on the Stormwater Geodatabase for the County of Riverside Stormwater Program is intended to provide basic guidance in the preparation of the applicantï¿1/2s Water Quality Management Plan (WQMP) and should not be relied upon without independent verification.

Project Site Parcel Number(s):	314230003, 314230014, 314091005, RW
Latitude/Longitude:	33.8496, -117.2637
Thomas Brothers Page:	
Project Site Acreage:	8.56
Watershed(s):	SANTA ANA
This Project Site Resides in the	HUC Name - HUC Number
following Hydrologic Unit(s) (HUC):	Perris Reservoir - 180702020305
The HUCs Contribute stormwater	WBID Name - WBID Number
to the following 303d listed water	Canyon Lake (Railroad Canyon Reservoir) -
bodies and TMDLs which may	CAL8021100019990208151525
proposed Project Site:	Elsinore, Lake - CAL8023100019990208151100
These 303d listed Water bodies	Bacterial Indicators - Pathogens
and TMDLs have the following	Nutrients - Nutrients, Organic Enrichment/Low
Pollutants of Concern (POC):	Dissolved Oxygen
	<b>Toxicity</b> - Sediment Toxicity, Unknown Toxicity
Is the Site subject to Hydromodification:	Yes
Limitations on Infiltration:	Project Site Onsite Soils Group(s) - A, C, D Known Groundwater Contamination Plumes within 1000' - No
	Adjacent Water Supply Wells(s) - No information available please contact your local water agency for more information. Your local contact agency is EASTERN MUNICIPAL W.D Your local wholesaler contact agency is METROPOLITAN WATER DISTRICT.
Environmentally Sensitive Areas within 200'(Fish and Wildlife Habitat/Species):	None
	N I a un a

None

Burrowing Owl Survey Required Area
1425
0.591
Perris-North
No Data
No Data
Comprehensive Nutrient Reduction Plan IBI Scores - Southern Cal bulletin118_4-sc water_fact_3_7.11 8039-SAR-Hydromodification Perris Valley MDP West San Jacinto GW Basin Management Plan Perris Valley ADP Report Perris Valley ADP Map

### 2. PRE-DEVELOPMENT CONDITION

The existing vacant property generally slopes from west to east at approximately 3%. Per the County's Perris Valley Area Drainage Plan, the site is part of the area tributary to Lateral F-1, with approximately 60 acres of upstream off-site area that is tributary to the site. Existing drainage sheet flows through and across the site, discharging to an existing inlet structure at the northeast corner of the site. There is an existing 48" storm drain pipe in Seaton Avenue, constituting the current upstream end of Lateral F-1.





ļ	PERRIS	VALLEY	LINE F a	a I-2'	15 100-1	YR					~	Sit	e is a	a por	tion of	
)												unis	sare	a		
			147													
 	FOR OF	FICIAL U	JSE ONLY	- Riv	verside	County	Offic	es - S/	N 43	3						
Project:   Study	PVLFOY.rrv Date: 03/04/91	Moistur	e Condi	tion(/	AMC): 2	1		1	Page	1 C	alcul Che	ated   cked	By: By:			
100.0 Yea	r Storm 1 hour ra	ainfall	= 1.12	2 (In	) Int	ensity	Slope :	= 0.490	στν	срети		- o *	*****	*****	*****	*****
  Station/	Soil Type	Devel.	Area		- "	IL Elev		Q	Slope	Section		L L	ΙT	Tc	Hvdraulic	s
Point No.	A,B,C,D	Туре	(Acres)	  in/h		()	(sub)	Total	v/hz	I	Fps	ft.	min.	min.	or notes	
2.00	C-100%	SF 1ac	8.2	2.39	0.7557	1700.0	14.8							12.8		>
	Natural Channel	travel	time + s	subare	ea flow	additi	on									
3.001	c-100%	SE 1ac	26.2	12.08	0.7393	  1598_0	40 4	14.80 	0.051	Nat Ch 	8.1	2000	4.1	16.9	qavg= 38. 	46
No. Pipes	= 1 Pipe flow to	ravel ti	ime	'N' =	= 0.013			55.2	0.027	  d= 30	15.2	2550	2.8	19.7	hgl= 1.7(	Ft.)
4.00	A 0 B20 C79 D 1	SF 1/2	35.7	1.93	0.7606	1530.0	52.5							19.7		
No. Pipes	= 1 Pipe flow to c-100%	ravel ti	me	'N' =	= 0.013			107.7	0.008	d= 45	10.8	800	1.2	20.9	hgl= 3.2(	Ft.)
No. Pipes	= 1 Pipe flow to	ravel ti	ime	'N' =	= 0.013			   154.8	0.025	  d= 42	18.7	650	0.6	21.5	  hgl= 2.8(	Ft.)
*	*****	******	CONFLUE	ENCE O	DF MAIN	STREAM	S ****	*******	*****	*******	*					
6 00		******														
			90.7					 		 			[ []	21.5	stream sum	mary
íi													[]			
11.00	C-100%	SF 1ac	2.8	2.70	0.7692	1652.0	5.8							10.0		
	Natural Channel	travel	time + s	subare 	еа тіом 	add111	on 	5.81	0.047	Nat Ch	6.2	1000	2.7			82
12.00	C-100%	SF 1ac	10.6	2.40	0.7562	1605.3	19.2				j			12.7		
No. Pipes	= 1 Pipe flow ti	ravel ti	me	'N' =	= 0.013			25.1	0.003	d= 33	5.7	400	1.2	13.8	hgl= 1.9(	Ft.)
9.00	*************		13.4	2 30			25 1							13.8	Stream Sum	marv
	C-100%	SF 1ac	7.6	2.35	0.7535	1720.0	13.4							13.3		
8.00																
8.00																

¥.



### Encompass Associates, Inc.

npass Associates, Inc.	Job DP Se	Job DP Seaton Ave Perris/RivCo							
Civil Engineers	Sheet No.	1	of	1					
5699 Cousins Place	Calculated by: ats		Date	3/20/21					
Rancho Cucamonga, CA 91737	Checked by:		Date						
(909) 684-0093 Fax 586-6979			Scale	nts					

### 2-YEAR STORM (CALIBRATED WITH 100-YEAR STORM)

### Calibration Hydrology (duplicate hydrology from MDP)

RATIONAL METHOD CALCULATION FORM (Plate D-2 RCFC&WCD Manual)

Drainage	Soil &	А	I	С	DQ	SQ	Slope	Section	v	L	Т	ST	Remarks
Area	Development	Acres	in/hr		CFS	CFS		inches	FPS	FT.	Min.	Min.	and Hydraulic Calculation Ref.
Initial->2	C-1du/ac	8.2	1.26	0.6564	6.78						12.8	12.8	
				<u> </u>		6.78	0.05	nat	8.10	2000	4.1		_
Node 2->3	C-1du/ac	26.2	1.1	0.634	18.27		•				•	16.9	
						25.05	0.027	30	12.65	2550	3.4		Section: pipe size (inches)
Node 3->4	C-2du/ac	35.7	1.01	0.681	24.55							20.3	
					-	49.61							_
·				•									-
							•						
			1		<b>T</b>								-
		-					1			1	1		
			1	T									7
								1		1			
r				I									7
							1	1		1	1		
r				I									7
							1	1		1	1		
[			1	1	1								7
							T	T		T	1		
[			1	1	1								л
							1	r		r	1		
·					1								7



# Encompass Associates, Inc.

**Civil Engineers** 

5699 Cousins Place

Rancho Cucamonga, CA 91737

(909) 684-0093 Fax 586-6979

Job	DP Sea	aton	Ave Per	ris/Riv	Co
Sheet No.		1	of		1
Calculated by:	ats		Date	3/	/20/21
Checked by:			Date		
			Scale	nts	

# 2-YEAR STORM

					<u>Propo</u>	sed Col	ndition						
			RATI	ONAL METH	OD CALC	ULATION	I FORM (I	Plate D-2	RCFC&W	CD Manu	ıal)		
Drainage Area	Soil & Development	A Acres	l in/hr	С	DQ CFS	SQ CFS	Slope	Section inches	v FPS	L FT.	T Min.	ST Min.	Remarks and Hydraulic Calculation Ref.
Initial->2	C-1du/ac	8.2	1.26	0.6564	6.78					-	12.8	12.8	
					•	6.78	0.05	nat	8.10	2000	4.1		_
Node 2->3	C-1du/ac	26.2	1.1	0.634	18.27		1			1		16.9	
Node 3->4 (Site)	C-Com	9.43	1.01	0.8602	8.19	25.05	0.027	30	12.65	2550	3.4	20.3	Section: pipe size (inches)
Node 3->4 (S'ly)	C-2du/ac	26.27	1.01	0.681	18.07							20.3	]
					-	51.32							_
							1						
					-	ļ							7
							1				1		
				I									7
							1						
													7
				1	ļ								
											1		7
	I			1									-
				r	-								-

# Appendix 8: Source Control

Pollutant Sources/Source Control Checklist

### How to use this worksheet (also see instructions in Section G of the WQMP Template):

- 1. Review Column 1 and identify which of these potential sources of stormwater pollutants apply to your site. Check each box that applies.
- 2. Review Column 2 and incorporate all of the corresponding applicable BMPs in your WQMP Exhibit.
- 3. Review Columns 3 and 4 and incorporate all of the corresponding applicable permanent controls and operational BMPs in your WQMP. Use the format shown in Table G.1on page 23 of this WQMP Template. Describe your specific BMPs in an accompanying narrative, and explain any special conditions or situations that required omitting BMPs or substituting alternative BMPs for those shown here.

IF THESE S ON THE PR	OURCES WILL BE	THEN YOUR WOMP SHOULD INCLUDE THESE SOURCE CONTROL BMPs, AS APPLICABLE									
Poten Runc	1 tial Sources of off Pollutants	2 Permanent Controls—Show on WQMP Drawings	3 Permanent Controls—List in WQMP Table and Narrative			4 Operational BMPs—Include in WQMP Table and Narrative					
Air	A. On-site storm drain nlets	Locations of inlets.		Mark all inlets with the words "Only Rain Down the Storm Drain" or similar. Catch Basin Markers may be available from the Riverside County Flood Control and Water Conservation District, call 951.955.1200 to verify.		Maintain and periodically repaint or replace inlet markings. Provide stormwater pollution prevention information to new site owners, lessees, or operators. See applicable operational BMPs in Fact Sheet SC-44, "Drainage System Maintenance," in the CASQA Stormwater Quality Handbooks at www.cabmphandbooks.com Include the following in lease agreements: "Tenant shall not allow anyone to discharge anything to storm drains or to store or deposit materials so as to create a potential discharge to storm drains."					
B au p	<ol> <li>Interior floor drains and elevator shaft sump pumps</li> </ol>			State that interior floor drains and elevator shaft sump pumps will be plumbed to sanitary sewer.		Inspect and maintain drains to prevent blockages and overflow.					
C C g	2. Interior parking garages			State that parking garage floor drains will be plumbed to the sanitary sewer.		Inspect and maintain drains to prevent blockages and overflow.					

IF THESE SOURCES WILL BE ON THE PROJECT SITE	THEN YOUR WOMP SHOULD INCLUDE THESE SOURCE CONTROL BMPS, AS APPLICABLE							
1 Potential Sources of Runoff Pollutants	2 Permanent Controls—Show on WQMP Drawings	3 Permanent Controls—List in WQMP Table and Narrative	4 Operational BMPs—Include in WQMP Table and Narrative					
D1. Need for future indoor & structural pest control		Note building design features that discourage entry of pests.	Provide Integrated Pest Management information to owners, lessees, and operators.					
D2. Landscape/ Outdoor Pesticide Use	<ul> <li>Show locations of native trees or areas of shrubs and ground cover to be undisturbed and retained.</li> <li>Show self-retaining landscape areas, if any.</li> <li>Show stormwater treatment and hydrograph modification management BMPs. (See instructions in Chapter 3, Step 5 and guidance in Chapter 5.)</li> </ul>	<ul> <li>State that final landscape plans will accomplish all of the following.</li> <li>Preserve existing native trees, shrubs, and ground cover to the maximum extent possible.</li> <li>Design landscaping to minimize irrigation and runoff, to promote surface infiltration where appropriate, and to minimize the use of fertilizers and pesticides that can contribute to stormwater pollution.</li> <li>Where landscaped areas are used to retain or detain stormwater, specify plants that are tolerant of saturated soil conditions.</li> <li>Consider using pest-resistant plants, especially adjacent to hardscape.</li> <li>To insure successful establishment, select plants appropriate to site soils, slopes, climate, sun, wind, rain, land use, air movement, ecological consistency, and plant interactions.</li> </ul>	<ul> <li>Maintain landscaping using minimum or no pesticides.</li> <li>See applicable operational BMPs in "What you should know forLandscape and Gardening" at http://rcflood.org/stormwater/Error! Hyperlink reference not valid.</li> <li>Provide IPM information to new owners, lessees and operators.</li> </ul>					

IF THESE SOURCES WILL BE ON THE PROJECT SITE	THEN YOUR WOMP SHO	OULD INCLUDE THESE SOURCE CONT	ROL BMPs, AS APPLICABLE		
1 Potential Sources of Runoff Pollutants	2 Permanent Controls—Show on WQMP Drawings	3 Permanent Controls—List in WQMP Table and Narrative	4 Operational BMPs—Include in WQMP Table and Narrative		
E. Pools, spas, ponds, decorative fountains, and other water features.	<ul> <li>Show location of water feature and a sanitary sewer cleanout in an accessible area within 10 feet. (Exception: Public pools must be plumbed according to County Department of Environmental Health Guidelines.)</li> </ul>	If the Co-Permittee requires pools to be plumbed to the sanitary sewer, place a note on the plans and state in the narrative that this connection will be made according to local requirements.	See applicable operational BMPs in "Guidelines for Maintaining Your Swimming Pool, Jacuzzi and Garden Fountain" at http://rcflood.org/stormwater/		
<b>F</b> . Food service	<ul> <li>For restaurants, grocery stores, and other food service operations, show location (indoors or in a covered area outdoors) of a floor sink or other area for cleaning floor mats, containers, and equipment.</li> <li>On the drawing, show a note that this drain will be connected to a grease interceptor before discharging to the sanitary sewer.</li> </ul>	<ul> <li>Describe the location and features of the designated cleaning area.</li> <li>Describe the items to be cleaned in this facility and how it has been sized to insure that the largest items can be accommodated.</li> </ul>	<ul> <li>See the brochure, "The Food Service Industry Best Management Practices for: Restaurants, Grocery Stores, Delicatessens and Bakeries" at http://rcflood.org/stormwater/</li> <li>Provide this brochure to new site owners, lessees, and operators.</li> </ul>		
G. Refuse areas	<ul> <li>Show where site refuse and recycled materials will be handled and stored for pickup. See local municipal requirements for sizes and other details of refuse areas.</li> <li>If dumpsters or other receptacles are outdoors, show how the designated area will be covered, graded, and paved to prevent runon and show locations of berms to prevent runoff from the area.</li> <li>Any drains from dumpsters, compactors, and tallow bin areas shall be connected to a grease removal device before discharge to sanitary sewer.</li> </ul>	<ul> <li>State how site refuse will be handled and provide supporting detail to what is shown on plans.</li> <li>State that signs will be posted on or near dumpsters with the words "Do not dump hazardous materials here" or similar.</li> </ul>	<ul> <li>State how the following will be implemented:</li> <li>Provide adequate number of receptacles. Inspect receptacles regularly; repair or replace leaky receptacles. Keep receptacles covered. Prohibit/prevent dumping of liquid or hazardous wastes. Post "no hazardous materials" signs. Inspect and pick up litter daily and clean up spills immediately. Keep spill control materials available on-site. See Fact Sheet SC-34, "Waste Handling and Disposal" in the CASQA Stormwater Quality Handbooks at www.cabmphandbooks.com</li> </ul>		

IF THES ON THE	E SOURCES WILL BE PROJECT SITE	THEN YOUR WOMP SH	BMPs, AS APPLICABLE			
Po	1 Itential Sources of Runoff Pollutants	2 Permanent Controls—Show on WQMP Drawings	Ре	3 rmanent Controls—List in WQMP Table and Narrative	Ор	4 Derational BMPs—Include in WQMP Table and Narrative
	H. Industrial processes.	□ Show process area.		If industrial processes are to be located on site, state: "All process activities to be performed indoors. No processes to drain to exterior or to storm drain system."		See Fact Sheet SC-10, "Non- Stormwater Discharges" in the CASQA Stormwater Quality Handbooks at www.cabmphandbooks.com
						See the brochure "Industrial & Commercial Facilities Best Management Practices for: Industrial, Commercial Facilities" at http://rcflood.org/stormwater/

IF THESE SOURCES WILL BE ON THE PROJECT SITE	THEN YOUR WOMP SHO	THEN YOUR WOMP SHOULD INCLUDE THESE SOURCE CONTROL BMPS, AS APPLICABLE								
1 Potential Sources of Runoff Pollutants	2 Permanent Controls—Show on WQMP Drawings	3 Permanent Controls—List in WQMP Table and Narrative	4 Operational BMPs—Include in WQMP Table and Narrative							
I. Outdoor storage of equipment or materials. (See rows J and K for source control measures for vehicle cleaning, repair, and maintenance.)	<ul> <li>Show any outdoor storage areas, including how materials will be covered. Show how areas will be graded and bermed to prevent runon or run-off from area.</li> <li>Storage of non-hazardous liquids shall be covered by a roof and/or drain to the sanitary sewer system, and be contained by berms, dikes, liners, or vaults.</li> <li>Storage of hazardous materials and wastes must be in compliance with the local hazardous materials ordinance and a Hazardous Materials Management Plan for the site.</li> </ul>	Include a detailed description of materials to be stored, storage areas, and structural features to prevent pollutants from entering storm drains. Where appropriate, reference documentation of compliance with the requirements of Hazardous Materials Programs for: • Hazardous Waste Generation • Hazardous Materials Release Response and Inventory • California Accidental Release (CalARP) • Aboveground Storage Tank • Uniform Fire Code Article 80 Section 103(b) & (c) 1991 • Underground Storage Tank www.cchealth.org/groups/hazmat /	See the Fact Sheets SC-31, "Outdoor Liquid Container Storage" and SC-33, "Outdoor Storage of Raw Materials" in the CASQA Stormwater Quality Handbooks at www.cabmphandbooks.com							

IF THESE SOURCES WILL BE ON THE PROJECT SITE	THEN YOUR WOMP SHO	OULD INCLUDE THESE SOURCE CONT	ROL BMPs, AS APPLICABLE
1 Potential Sources of Runoff Pollutants	2 Permanent Controls—Show on WQMP Drawings	3 Permanent Controls—List in WQMP Table and Narrative	4 Operational BMPs—Include in WQMP Table and Narrative
J. Vehicle and Equipment Cleaning	<ul> <li>Show on drawings as appropriate:         <ul> <li>(1) Commercial/industrial facilities having vehicle/equipment cleaning needs shall either provide a covered, bermed area for washing activities or discourage vehicle/equipment washing by removing hose bibs and installing signs prohibiting such uses.</li> <li>(2) Multi-dwelling complexes shall have a paved, bermed, and covered car wash area (unless car washing is prohibited on-site and hoses are provided with an automatic shutoff to discourage such use).</li> <li>(3) Washing areas for cars, vehicles, and equipment shall be paved, designed to prevent run-on to or runoff from the area, and plumbed to drain to the sanitary sewer.</li> <li>(4) Commercial car wash facilities shall be designed such that no runoff from the facility is discharged to the storm drain system. Wastewater from the facility shall discharge to the sanitary sewer, or a wastewater reclamation system shall be installed.</li> </ul> </li> </ul>	□ If a car wash area is not provided, describe any measures taken to discourage on-site car washing and explain how these will be enforced.	<ul> <li>Describe operational measures to implement the following (if applicable):</li> <li>Washwater from vehicle and equipment washing operations shall not be discharged to the storm drain system. Refer to "Outdoor Cleaning Activities and Professional Mobile Service Providers" for many of the Potential Sources of Runoff Pollutants categories below. Brochure can be found at http://rcflood.org/stormwater/</li> <li>Car dealerships and similar may rinse cars with water only.</li> </ul>

IF THESE SOURCES WILL BE ON THE PROJECT SITE	THEN YOUR WOMP SHO	OULD INCLUDE THESE SOURCE CONT	ROL BMPs, AS APPLICABLE
1 Potential Sources of Runoff Pollutants	2 Permanent Controls—Show on WQMP Drawings	3 Permanent Controls—List in WQMP Table and Narrative	4 Operational BMPs—Include in WQMP Table and Narrative
K. Vehicle/Equipment Repair and Maintenance	<ul> <li>Accommodate all vehicle equipment repair and maintenance indoors. Or designate an outdoor work area and design the area to prevent run-on and runoff of stormwater.</li> <li>Show secondary containment for exterior work areas where motor oil, brake fluid, gasoline, diesel fuel, radiator fluid, acid-containing batteries or other hazardous materials or hazardous wastes are used or stored. Drains shall not be installed within the secondary containment areas.</li> <li>Add a note on the plans that states either (1) there are no floor drains, or (2) floor drains are connected to wastewater pretreatment systems prior to discharge to the sanitary sewer and an industrial waste discharge permit will be obtained.</li> </ul>	<ul> <li>State that no vehicle repair or maintenance will be done outdoors, or else describe the required features of the outdoor work area.</li> <li>State that there are no floor drains or if there are floor drains, note the agency from which an industrial waste discharge permit will be obtained and that the design meets that agency's requirements.</li> <li>State that there are no tanks, containers or sinks to be used for parts cleaning or rinsing or, if there are, note the agency from which an industrial waste discharge permit will be obtained and that the design meets that agency's requirements.</li> </ul>	<ul> <li>In the Stormwater Control Plan, note that all of the following restrictions apply to use the site:</li> <li>No person shall dispose of, nor permit the disposal, directly or indirectly of vehicle fluids, hazardous materials, or rinsewater from parts cleaning into storm drains.</li> <li>No vehicle fluid removal shall be performed outside a building, nor on asphalt or ground surfaces, whether inside or outside a building, except in such a manner as to ensure that any spilled fluid will be in an area of secondary containment. Leaking vehicle fluids shall be contained or drained from the vehicle immediately.</li> <li>No person shall leave unattended drip parts or other open containers containing vehicle fluid, unless such containers are in use or in an area of secondary containment.</li> <li>Refer to "Automotive Maintenance &amp; Car Care Best Management Practices for Auto Body Shops, Auto Repair Shops, Car Dealerships, Gas Stations and Fleet Service Operations". Brochure can be found at http://rcflood.org/stormwater/</li> <li>Refer to Outdoor Cleaning Activities and Professional Mobile Service Providers for many of the Potential Sources of Runoff Pollutants categories below. Brochure can be found at http://rcflood.org/stormwater/</li> </ul>

IF THESE SOURCES WILL BE ON THE PROJECT SITE	THEN YOUR WOMP SHOULD INCLUDE THESE SOURCE CONTROL BMPs, AS APPLICABLE		
1 Potential Sources of Runoff Pollutants	2 Permanent Controls—Show on WQMP Drawings	3 Permanent Controls—List in WQMP Table and Narrative	4 Operational BMPs—Include in WQMP Table and Narrative
L. Fuel Dispensing Areas	<ul> <li>Fueling areas<sup>6</sup> shall have impermeable floors (i.e., portland cement concrete or equivalent smooth impervious surface) that are: a) graded at the minimum slope necessary to prevent ponding; and b) separated from the rest of the site by a grade break that prevents run-on of stormwater to the maximum extent practicable.</li> <li>Fueling areas shall be covered by a canopy that extends a minimum of ten feet in each direction from each pump. [Alternative: The fueling area must be covered and the cover's minimum dimensions must be equal to or greater than the area within the grade break or fuel dispensing area<sup>1</sup>.] The canopy [or cover] shall not drain onto the fueling area.</li> </ul>		<ul> <li>The property owner shall dry sweep the fueling area routinely.</li> <li>See the Fact Sheet SD-30, "Fueling Areas" in the CASQA Stormwater Quality Handbooks at www.cabmphandbooks.com</li> </ul>

<sup>&</sup>lt;sup>6</sup> The fueling area shall be defined as the area extending a minimum of 6.5 feet from the corner of each fuel dispenser or the length at which the hose and nozzle assembly may be operated plus a minimum of one foot, whichever is greater.

IF THESE SOURCES WILL BE ON THE PROJECT SITE	THEN YOUR WOMP SHOULD INCLUDE THESE SOURCE CONTROL BMPS, AS APPLICABLE		
1 Potential Sources of Runoff Pollutants	2 Permanent Controls—Show on WQMP Drawings	3 Permanent Controls—List in WQMP Table and Narrative	4 Operational BMPs—Include in WQMP Table and Narrative
M. Loading Docks	<ul> <li>Show a preliminary design for the loading dock area, including roofing and drainage. Loading docks shall be covered and/or graded to minimize run-on to and runoff from the loading area. Roof downspouts shall be positioned to direct stormwater away from the loading area. Water from loading dock areas shall be drained to the sanitary sewer, or diverted and collected for ultimate discharge to the sanitary sewer.</li> <li>Loading dock areas draining directly to the sanitary sewer shall be equipped with a spill control valve or equivalent device, which shall be kept closed during periods of operation.</li> <li>Provide a roof overhang over the loading area or install door skirts (cowling) at each bay that enclose the end of the trailer.</li> </ul>		<ul> <li>Move loaded and unloaded items indoors as soon as possible.</li> <li>See Fact Sheet SC-30, "Outdoor Loading and Unloading," in the CASQA Stormwater Quality Handbooks at www.cabmphandbooks.com</li> </ul>

IF THESE SOURCES WILL BE ON THE PROJECT SITE	THEN YOUR WOMP SHO	OULD INCLUDE THESE SOURCE CONT	ROL BMPs, AS APPLICABLE
1 Potential Sources of Runoff Pollutants	2 Permanent Controls—Show on WQMP Drawings	3 Permanent Controls—List in WQMP Table and Narrative	4 Operational BMPs—Include in WQMP Table and Narrative
N. Fire Sprinkler Test Water		Provide a means to drain fire sprinkler test water to the sanitary sewer.	<ul> <li>See the note in Fact Sheet SC-41, "Building and Grounds Maintenance," in the CASQA Stormwater Quality Handbooks at www.cabmphandbooks.com</li> </ul>
<ul> <li>O. Miscellaneous Drain or Wash Water or Other Sources</li> <li>Boiler drain lines</li> <li>Condensate drain lines</li> <li>Rooftop equipment</li> <li>Drainage sumps</li> <li>Roofing, gutters, and trim.</li> <li>Other sources</li> </ul>		<ul> <li>Boiler drain lines shall be directly or indirectly connected to the sanitary sewer system and may not discharge to the storm drain system.</li> <li>Condensate drain lines may discharge to landscaped areas if the flow is small enough that runoff will not occur. Condensate drain lines may not discharge to the storm drain system.</li> <li>Rooftop equipment with potential to produce pollutants shall be roofed and/or have secondary containment.</li> <li>Any drainage sumps on-site shall feature a sediment sump to reduce the quantity of sediment in pumped water.</li> <li>Avoid roofing, gutters, and trim made of copper or other unprotected metals that may leach into runoff. Include controls for other sources as specified by local reviewer.</li> </ul>	

IF THESE SOURCES WILL BE ON THE PROJECT SITE	THEN YOUR WOMP SH	OULD INCLUDE THESE SOURCE CONT	ROL BMPs, AS APPLICABLE
1 Potential Sources of Runoff Pollutants	2 Permanent Controls—Show on WQMP Drawings	3 Permanent Controls—List in WQMP Table and Narrative	4 Operational BMPs—Include in WQMP Table and Narrative
P. Plazas, sidewalks, and parking lots.			Sweep plazas, sidewalks, and parking lots regularly to prevent accumulation of litter and debris. Collect debris from pressure washing to prevent entry into the storm drain system. Collect washwater containing any cleaning agent or degreaser and discharge to the sanitary sewer not to a storm drain.

# Appendix 9: O&M

Operation and Maintenance Plan and Documentation of Finance, Maintenance and Recording Mechanisms

# Goodman &associates

# Structural and Treatment Control BMPS Operation and Maintenance Plan

For

# **Seaton Ave Warehouses**

Seaton Avenue North of Perry St. Unincorporated Perris, Riverside County, CA

March 24, 2021

Douglas L. Goodman

## **Table of Contents**

I.	Inspection and Maintenance Logs2
II.	Updates, Revisions, and Errata3
III.	Introduction4
IV.	Responsibility for Maintenance4
V.	Summary of Drainage Management Areas and Stormwater BMPs4
VI.	Maintenance Schedule or Matrix5

### I. Inspection and Maintenance Logs

Inspection and Maintenance Logs are in the Appendix.

II. Updates, Revisions, and Errata

### III. Introduction

The proposed project is for the construction of two warehouse buildings with truck loading docks and associated parking on 9 acres. The project is located on Seaton Avenue, extending westerly to Beck Street, between Perry Street and Markham Street, in the unincorporated Perris Area, County of Riverside. Access to the proposed site building will be from two driveway entrances off of Seaton Avenue on the east side of the site.

The existing vacant property generally slopes from west to east at approximately 3%. Existing drainage sheet flows across the site, discharging to an existing inlet structure at the northeast corner of the site. There is an existing 48" storm drain pipe in Seaton Avenue, constituting the current upstream end of Perris Valley Area Drain Plan Lateral F-1. The project will be required to extend Lateral F-1 to the west side in order to collect off-site runoff. There is also existing runoff from properties to the south that will be collected by a system on-site and conveyed directly to Lateral F-1. No run-on from off-site areas will surface drain to the site.

The proposed project will consist of two buildings, each on dedicated parcel. Each parcel will have a dedicated LID BMP, proposed to be a CDS clarifier for pre-treatment ahead of an underground infiltration system. Each system is proposed to be situated to the east of each building. Over-flows in excess of water quality capture volume requirements will be directed to the aforementioned Lateral F-1 for conveyance off-site.

### IV. Responsibility for Maintenance

- A. General
  - 1) Name and contact information for responsible individual:

Benjamin Horning Dedeaux Properties 1430 S. Eastman Avenue Los Angeles, CA 90023 909-730-0186

- 2) The owner or his designee will be responsible for onsite maintenance and operations.
- 3) Maintenance funding is part of business operating budget.
- B. Staff Training Program: Operation and Maintenance procedures for stormwater BMPs shall be part of regular employee orientation and training.
- C. Records: Records shall be maintained onsite.
- D. Safety: Personnel shall perform duties consistent with local and CAL-OSHA employee safety regulations.

### V. Summary of Drainage Management Areas and Stormwater BMPs

Please refer to the description in Section III and the WQMP Plan included in the Project-Specific WQMP.

### VI. Maintenance Schedule or Matrix

### Underground Infiltration Systems

Infiltration System maintenance should include frequent inspections to ensure that water infiltrates into the subsurface completely within the recommended infiltration time of 72 hours or less after a storm. The proposed maintenance procedures shall be incorporated into the routine landscaping maintenance of the property, including cleaning out of catch basin filter inserts.

The following are general maintenance requirements:

- 1. If water is noticed in either chamber/manhole more than 72 hours after a major storm the facility may be clogged. Maintenance activities triggered by a potentially clogged facility include:
  - a. Check for debris/sediment accumulation, and remove sediment (if any) and evaluate potential sources of sediment and vegetative or other debris (e.g., embankment erosion, channel scour, overhanging trees, etc). If suspected upland sources are outside of the city's jurisdiction, additional pretreatment operations (e.g., trash racks, vegetated swales, etc.) may be necessary.
- 2. Any debris or algae growth located on top of the facility should be removed and disposed of properly.
- 3. Facilities should be inspected annually. Trash and debris should be removed as needed, but at least annually prior to the beginning of the wet season.
- 4. Site vegetation should be maintained as frequently as necessary to maintain the aesthetic appearance of the site, and as follows:
  - a. Vegetation, large shrubs, or trees that limit access or interfere with basin operation should be pruned or removed.
  - b. Slope areas that have become bare should be revegetated and eroded areas should be regraded prior to being revegetated.
  - c. Grass should be mowed to 4"-9" high and grass clippings should be removed.
  - d. Fallen leaves and debris from deciduous plant foliage should be raked and removed.
  - e. Invasive vegetation, such as Alligatorweed (Alternanthera philoxeroides), Halogeton (Halogeton glomeratus), Spotted Knapweed (Centaurea maculosa), Giant Reed (Arundo donax), Castor Bean (Ricinus communis), Perennial Pepperweed (Lepidium latifolium), and Yellow Starthistle (Centaurea solstitalis) must be removed and replaced with non- invasive species. Invasive species should never contribute more than 25% of the vegetated area. For more information on invasive weeds, including biology and control of listed weeds, look at the "encycloweedia" located at the California Department of Food and Agriculture website at
http://www.cdfa.ca.gov/wma or the California Invasive Plant Council website at http://portal.cal-ipc.org/weedlist. .

- f. Dead vegetation should be removed if it exceeds 10% of area coverage. Vegetation should be replaced immediately to maintain cover density and control erosion where soils are exposed.
- g. Excess sediment buildup should be removed. Sediment should be removed when 6 inches of sediment accumulates. Sediments should be tested for toxic substance accumulation in compliance with current disposal requirements if visual or olfactory indications of pollution are noticed. If toxic substances are encountered at concentrations exceeding thresholds of Title 22, Section 66261 of the California Code of Regulations, the sediment must be disposed of in a hazardous waste landfill and the source of the contaminated sediments should be investigated and mitigated to the extent possible.
- h. Following sediment removal activities, replanting and/or reseeding of vegetation may be required for reestablishment.

		Inspection and Maintenance Activities Summary				
	٠	Remove trash and debris as required (from system and inlet filters)				
	٠	Repair and reseed erosion near inlet if necessary				
Ð	٠	Remove any visual evidence of contamination from floatables such as oil and grease				
nc	•	Remove minor sediment accumulation, debris, and obstructions near inlets and outlet				
e na		structures as needed.				
tin Ite	•	Mow routinely to maintain ideal grass height and to suppress weeds				
ou air	٠	Periodically observe function under wet weather conditions				
2 2	٠	Take photographs before and after maintenance				
or ntenance	•	Repair structural damage to flow control structures including inlet, outlet, and overflow structures				
Maj( Maiı	•	De-thatch grass to remove accumulated sediment and aerate compacted areas to promote infiltration				

#### Routine Maintenance for Infiltration Systems/Dry Wells

Defect	Condition When Maintenance is Needed	Results Expected when Maintenance is Performed	Frequency
Trash & Debris	Any trash and debris which exceed 5 cubic feet per 1000 square feet (one standard garbage can). In general there should be no visual evidence of dumping. If less than threshold, all trash and debris will be removed as part of next	Trash and debris cleared from site	Annually prior to wet season. After major storm events. (>0.75 in/24 hours) if spot checks indicate widespread damage and/or
	scheduled maintenance.		maintenance

Defect	Condition When Maintenance is Needed	Results Expected when Maintenance is Performed	Frequency
Inlet Erosion	Visible evidence of erosion occurring near inlet structures.	Eroded areas repaired/reseeded	needs. Litter removal is
Visual Contaminants and Pollution	Any evidence of oil, gasoline, contaminants, or other pollutants.	No contaminants or pollutants present.	dependent on site conditions and desired aesthetics
Slow Drain Time	Standing water long after storm has passed (after 72 hours) indicates that design drain times are not being achieved	Water drains within 72 hours. Accumulated litter on surface is removed, and top 1" to 2" of soil is raked or replaced.	and should be done at a frequency to meet those objectives.
Inlets Blocked	Trash and debris or sediment blocking inlet structures	Inlets clear and free of trash and debris.	
Appearance of Poisonous, Noxious, or Nuisance Vegetation	Excessive grass and weed growth. Noxious weeds, woody vegetation establishing. Turf growing over rock filter.	Vegetation is mowed or trimmed to restore function. Weeds are removed to prevent noxious and nuisance plants from becoming established.	Monthly or as part of normal landscaping service, whichever is more frequent.

# **APPENDIX**

# Inspection and Maintenance Logs

**Training Logs** 

### **BMP TRAINING ACKNOWLEDGEMENT FORM**

By signing this form, the undersigned certifies that they have received the listed materials and training for the BMP's that they are responsible for operation and maintenance, or responsible to meet the requirements. The undersigned also acknowledged that punitive actions may be imposed if they fail to comply. The punitive actions can be in terms of monetary fine or termination of the contract or the rights that are transferred to the undersigned through contracts. If necessary, the owner or public agencies may complete the corrective actions and bill the undersigned.

Item	Training Description	Related BMPs	Handout Materials	Comments

### **BMP TRAINING ACKNOWLEDGEMENT FORM**

Item	Training Description	Related BMPs	Handout Materials	Comments
Name (Print)	1	1		
Rusiness Name				
Title /Degition:				
nue/Position:				
Signature:			Date:	

### **CDS Inspection & Maintenance Log**

CDS Model:

CDS Mode	DS Model: Location:					
Date	Water depth to sediment <sup>1</sup>	Floatable Layer Thickness <sup>2</sup>	Describe Maintenance Performed	Maintenance Personnel	Comments	

- The water depth to sediment is determined by taking two measurements with a stadia rod: one measurement from the manhole opening to the 1. top of the sediment pile and the other from the manhole opening to the water surface. If the difference between these measurements is less than the values listed in table 1 the system should be cleaned out. Note: to avoid underestimating the volume of sediment in the chamber, the measuring device must be carefully lowered to the top of the sediment pile.
- For optimum performance, the system should be cleaned out when the floating hydrocarbon layer accumulates to an appreciable thickness. In 2. the event of an oil spill, the system should be cleaned immediately.

# Appendix 10: Educational Materials

BMP Fact Sheets, Maintenance Guidelines and Other End-User BMP Information

# 10 Ways to Save Water Outdoors



**TIP #1** The average homeowner uses twice the amount of water needed to keep plants healthy. Use the watering calculator and index at **bewaterwise.com** to know exactly how much water your plants need.

**TIP #2** Check your sprinkler system for leaks, overspray and broken sprinkler heads. Update with drip or other more water-efficient sprinklers where appropriate.

**TIP #3** This fall, plant a portion of your garden with beautiful native and California Friendly plants. Browse the plant database at **bewaterwise.com** to find just the right look for your outdoor spaces.

**TIP #4** Reduce the amount of water-thirsty grass. Keep only what you need and replace the rest with less-thirsty plants or permeable paving.

**TIP #5** For the grass you keep, set your lawnmower blade higher.

**TIP #6** Adjust your sprinkler timer downward in September. Plants need less water when days are shorter.

**TIP #7** Use a broom instead of the hose for cleaning sidewalks and patios.

**TIP #8** Mulch! A layer of bark, gravel, compost, sawdust or low-growing groundcover evens out soil temperature and allows better water retention.

**TIP #9** Check the list of invasive plants that hurt our environment at **caleppc.org** and remove any from your garden.

**TIP #10** Share these tips with your gardener, neighbors and friends. Water conservation should be a part of every Southern Californian's lifestyle, but that doesn't mean we can't have lush and beautiful outdoor spaces.

# bewaterwise.com

# For Information:

#### LOCAL SEWERING AGENCIES IN RIVERSIDE COUNTY:

City of Beaumont	(909) 769-8520
Belair Homeowners Association	(909) 277-1414
City of Banning	(909) 922-3130
City of Blythe	(760) 922-6161
City of Coachella	(760) 391-5008
Coachella Valley Water District	(760) 398-2651
City of Corona	(909) 736-2259
Desert Center, CSA #51	(760) 227-3203
Eastern Municipal Water District	(909) 928-3777
Elsinore Valley MWD	(909) 674-3146
Farm Mutual Water Company	(909) 244-4198
dyllwild Water District	(909) 659-2143
Jurupa Community Services Dist.	(909) 685-7434
_ake Hemet MWD	(909) 658-3241
Lee Lake Water District	(909) 277-1414
March Air Force Base	(909) 656-7000
Mission Springs Water District	(760) 329-6448
City of Palm Springs	(760) 323-8242
Rancho Caballero	(909) 780-9272
Rancho California Water Dist.	(909) 676-4101
Ripley, CSA #62	(760) 922-4909
Rubidoux Community Services Dist.	(909) 684-7580
City of Riverside	(909) 782-5341
Silent Valley Club, Inc	(909) 849-4501
/alley Sanitary District	(760) 347-2356
Nestern Municipal Water District	(909) 780-4170

#### SPILL RESPONSE AGENCY: HAZ-MAT: (9

 HAZ-MAT:
 (909) 358-5055

 HAZARDOUS WASTE DISPOSAL:
 (909) 358-5055

 TO REPORT ILLEGAL DUMPING OR A CLOGGED

 STORM DRAIN:
 1-800-506-2555



Riverside County gratefully acknowledges the Bay Area Stormwater Management Agencies Association and the Cleaning Equipment Trade Association for information provided in this brochure.

# StormWater Pollution

What you should know for...

# OUTDOOR CLEANING ACTIVITIES Non-stormwater discharges



**GUIDELINES** for disposal of washwater from:

- Sidewalk, plaza or parking lot cleaning
- Vehicle washing or detailing
- Building exterior cleaning
- Waterproofing
- Equipment cleaning or degreasing

# Do you know . . . where the water should go?



Non-stormwater discharges such as washwater generated from outdoor cleaning projects often transport harmful pollutants into storm drains and our local waterways. Polluted runoff contaminates local waterways and poses a threat to groundwater resources. Riverside County has two drainage systems - sanitary sewers and storm drains. The storm drain system is designed to prevent flooding by carrying excess rainwater away from streets...it's <u>not</u> designed to be a waste disposal system. Since the storm drain system does not provide for water treatment, it often serves the unintended function of transporting pollutants directly to our waterways.

Unlike sanitary sewers, storm drains are not connected to a treatment plant - they flow directly to our local streams, rivers and lakes.

Soaps, degreasers, automotive fluids, litter, and a host of other materials washed off buildings, sidewalks, plazas, parking areas, vehicles, and equipment can all pollute our waterways.

# The Cities and County of Riverside StormWater/CleanWater Protection Program

Since preventing pollution is much easier, and less costly than cleaning up "after the fact," the Cities and County of Riverside StormWater/CleanWater Protection Program informs residents and businesses of pollution prevention activities such as those described in this pamphlet.

The Cities and County of Riverside have adopted ordinances for stormwater management and discharge control. In accordance with state and federal law, these local stormwater ordinances **prohibit** the discharge of wastes into the storm drain system or local surface waters. This includes non-stormwater discharges containing oil, grease, detergents, degreasers, trash, or other waste materials.



**PLEASE NOTE:** The discharge of pollutants into the street, gutters, storm drain system, or waterways - without a Regional Water Quality Control Board permit or waiver - is *strictly prohibited* by local ordinances and state and federal law.

# Help Protect Our Waterways! Use These Guidelines For Outdoor Cleaning Activities and Washwater Disposal

**DO**... Dispose of small amounts of washwater from cleaning building exteriors, sidewalks, or plazas onto landscaped or unpaved surfaces provided you have the owner's permission and the discharge will not cause flooding or nuisance problems, or flow into a storm drain.

**DO NOT** . . . Discharge **large amounts** of these types of washwater onto landscaped areas or soil where water may run to a street or storm drain. Wastewater from exterior cleaning may be pumped to a sewer line with specific permission from the local sewering agency.

**DO**... Check with your local sewering agency's policies and requirements concerning waste water disposal. Water from many outdoor cleaning activities may be acceptable for disposal to the sewer system. See the list on the back of this flyer for phone numbers of the sewering agencies in your area.

**DO NOT** . . . Pour hazardous wastes or toxic materials into the storm drain or sewer system . . . properly dispose of it instead. When in doubt, contact the local sewering agency! The agency will tell you what types of liquid wastes can be accepted.

**DO**... Understand that water (without soap) used to remove dust from clean vehicles may be discharged to a street or storm drain. Washwater from sidewalk, plaza, and building surface cleaning may go into a street or storm drain if <u>ALL</u> of the following conditions are met:

- 1) The surface being washed is free of residual oil stains, debris and similar pollutants by using dry cleanup methods (sweeping, and cleaning any oil or chemical spills with rags or other absorbent materials before using water).
- 2) Washing is done with water only no soap or other cleaning materials.
- 3) You have not used the water to remove paint from surfaces during cleaning.

**DO NOT**... Dispose of water containing **soap or any other type of cleaning agent** into a storm drain or water body. This is a direct violation of state and/or local regulations. Because **wastewater from cleaning parking areas or roadways** normally contains metallic brake pad dust, oil and other automotive fluids, it should never be discharged to a street, gutter, or storm drain. **DO**... Understand that **mobile auto detailers** should divert washwater to landscaped or dirt areas. Note: Be aware that soapy washwater may adversely affect landscaping; consult with the property owner. Residual washwater may remain on paved surfaces to evaporate; sweep up any remaining residue. If there is sufficient water volume to reach the storm drain, collect the runoff and obtain permission to pump it into the sanitary sewer. Follow local sewering agency's requirements for disposal.

**DO NOT** . . . Dispose of left over cleaning agents into the gutter, storm drain or sanitary sewer.

### **Regarding Cleaning Agents:**

If you must use soap, use biodegradable/phosphate free cleaners. Avoid use of petroleum based cleaning products. Although the use of nontoxic cleaning products is strongly encouraged, <u>do</u> understand that these products can still degrade water quality and, therefore, the discharge of these products into



**Note:** When cleaning surfaces with a high pressure washer or steam cleaning methods, additional precautions should be taken to prevent the discharge of pollutants into the storm drain system. These two methods of surface cleaning, as compared to the use of a low pressure hose, can remove additional materials that can contaminate local waterways.

# OTHER TIPS TO HELP PROTECT OUR WATER...

#### **SCREENING WASH WATER**

A thorough dry cleanup before washing (without soap) surfaces such as building exteriors and decks without loose paint, sidewalks, or plaza areas, *should be sufficient to protect storm drains*. **However**, if any debris (solids) could enter storm drains or remain in the gutter or street after cleaning, washwater should first pass through a "20 mesh" or finer screen to catch the solid material, which should then be disposed of in the trash.

#### DRAIN INLET PROTECTION/ CONTAINING & COLLECTING WASH WATER

- Sand bags can be used to create a barrier around storm drain inlets.
- Plugs or rubber mats can be used to temporarily seal storm drain openings.
- You can also use vacuum booms, containment pads, or temporary berms to keep wash water away from the street, gutter, or storm drain.

#### **EQUIPMENT AND SUPPLIES**

Special materials such as absorbents, storm drain plugs and seals, small sump pumps, and vacuum booms are available from many vendors. For more information check catalogs such as New Pig (800-468-4647), Lab Safety Supply (800-356-0783), C&H (800-558-9966), and W.W. Grainger (800-994-9174); or call the Cleaning Equipment Trade Association (800-441-0111) or the Power Washers of North America (800-393-PWNA).

# For Information:

For information on "closed-loop" suppliers and recycling/disposal vendors, contact: County of Riverside Health Services Agency Department of Environmental Health at (909) 358-5055.

#### **SPILL RESPONSE AGENCY:**

HAZ-MAT: (909) 358-5055 AFTER 5:00 P.M.: (909) 358-5245 OR 911

RECYCLING AND HAZARDOUS WASTE DISPOSAL: (909) 358-5055

To Report Illegal Dumping or a CLOGGED STORM DRAIN: 1-800-506-2555

To order additional brochures or to obtain information on other pollution prevention activities, call: (909) 955-1111.

The Cities and County of Riverside StormWater/CleanWater Protection Program **1-800-506-2555** 



Riverside County gratefully acknowledges the Santa Clara Valley Nonpoint Source Pollution Control Program and the City of Los Angeles Stormwater Management Division for information provided in this brochure.

# **StormWater Pollution**

What you should know for...

# AUTOMOTIVE MAINTENANCE & CAR CARE



# **Best Management Practices (BMPS) for:**

- Auto Body Shops
- Auto Repair Shops
- Car Dealerships
- Gas Stations
- Fleet Service Operations

# StormWater Pollution . . . What You Should Know

Riverside County has two drainage systems - sanitary sewers and storm drains. The storm drain system is designed to help prevent flooding by carrying excess rainwater away from streets. Since the storm drain system does not provide for water treatment, it also serves the *unintended* function of transporting pollutants directly to our waterways.

Unlike sanitary sewers, storm drains are not connected to a treatment plant - they flow directly to our local streams, rivers and lakes.

Rain and water runoff from automotive shops and businesses can carry pollutant material into storm drains. Examples of pollutants include oil and grease from cars, copper and asbestos from worn brake linings, zinc from tires, and toxics from spilled fluids.

Stormwater pollution causes as much as 60% of our water pollution problem. It jeopardizes the quality of our waterways and poses a threat to groundwater resources if pollutants percolate through soil.



# The Cities and County of Riverside StormWater/CleanWater Protection Program

Since preventing pollution is much easier, and less costly, than cleaning up "after the fact," the Cities and County of Riverside StormWater/CleanWater Protection Program informs residents and businesses on pollution prevention activities such as the Best Management Practices (BMPs) described in this pamphlet.

The Cities and County of Riverside have adopted ordinances for stormwater management and discharge control. In accordance with state and federal law, these local stormwater ordinances **prohibit** the discharge of wastes into the storm drain system or local surface waters. This includes discharges containing oil, antifreeze, gasoline and other waste materials.

**PLEASE NOTE:** A common stormwater pollution problem associated with automotive shops and businesses is the hosing down of service bays, parking and other areas. Often, this activity flushes pollutants into the storm drain system. The discharges of pollutants is *strictly prohibited* by local ordinances and state and federal regulations.

# Keep your shop in tune. Follow these Practices to help prevent stormwater pollution . . .

#### 1. Changing Automotive Fluids

- Designate an area away from storm or sanitary drains to change automotive fluids.
- Collect, separate, and recycle motor oil, antifreeze, transmission fluid, and gear oil.
- Drain brake fluid and other non-recyclables into a proper container and handle as a hazardous waste.
- Use a radiator flushing fluid that can be recycled. and add it to the waste antifreeze

#### 2. Working on Transmissions, Engines, and Miscellaneous Repairs

Keep a drip pan or a wide low-rimmed container under vehicles to catch fluids whenever you unclip hoses, unscrew filters, or change parts, to contain unexpected leaks.

#### 3. Preventing Leaks and Spills

- Avoid spills by emptying and wiping drip pans when you move them to another vehicle or when they are half-full.
- Routinely check equipment to wipe up spills and repair leaks.
- Place large pans or an inflatable portable berm under wrecked cars.
- Drain all fluids from wrecked vehicles or "parts" cars you keep on site.

#### 4. Cleaning up Spills

Clean up small spills immediately using shop rags.

- Keep dry absorbent materials and/or a wet/dry vacuum cleaner on hand for mid-sized spills.
- Contain large spills immediately; block or shut off floor and parking lot drains and notify the authorities.
- Train employees to be familiar with hazardous spill response plans and emergency procedures.

#### 5. Identify and Control Wastewater **Discharges**

- Ensure that shop sinks and floor drains are connected to the sanitary sewer. Check with the local sewer authority regarding permitting or other requirements.
- Post signs to prevent disposal of liquid wastes into sanitary drains.

#### 6. Fueling Vehicles

- Clean-up minor spills, with a dry absorbent, rather than allowing them to evaporate. Dispose of the absorbent as a drv hazardous waste. Use a damp cloth and a
- damp mop to keep the area clean rather than a hose or a wetmop.

#### 7. Removing and Storing Batteries

- Store batteries indoors, on an open rack.
- Return used batteries to a battery vendor.
- Contain cracked batteries to prevent hazardous spills.

#### 8. Cleaning Parts

Clean parts in a selfcontained unit, solvent sink, or parts washer to prevent solvents and grease from entering a sewer or storm drain connection.

#### Metal Grinding and Finishing 9.

- Catch metal filings in an enclosed unit or on a tarpaulin.
- Sweep filing area to prevent washing metals into floor drains.

#### 10. Storing and Disposing of Waste

- Store recyclable and non-recyclable waste separately.
- Place liquid waste (hazardous or otherwise) within a bermed or secondary containment area.
- Cover outdoor storage areas to prevent contact with rain water.
- Collect used parts for delivery to a scrap metal dealer.

#### **11. Selecting and Controlling Inventory**

- Purchase recyclable or non-toxic materials.
- Select "closed-loop" suppliers and purchase supplies in bulk.



#### 12. Outdoor Parking and Auto Maintenance

- Treat outdoor areas as an extension of your service bays or avoid using altogether.
- Sweep-up trash and dirt from outdoor parking and maintenance areas. Do not hose down areas. All non-storm water discharges are prohibited.
- Drain work areas to a sanitary drain rather than a storm drain. Contact the local sewer authority to determine if pretreatment is required.

#### 13. Washing Vehicles, Cleaning Engines, and Other Steam Cleaning

- For occasional car exterior cleaning, minimize the water used and divert runoff to landscaped areas, keeping it out of the storm drain.
- Wash vehicles with biodegradable, phosphate-free detergent.
- Make sure no wastewater from engine or parts cleaning or steam cleaning is discharged where it may flow to a street, gutter, or storm drain.

#### 14. Cleaning Work Areas

- Sweep or vacuum the shop floor frequently.
- Damp mop work areas do not hose down work areas into the street or gutter.
- Do not pour mop water into the parking lot, street, gutter or storm drain.
- Use non-toxic cleaning products whenever possible.

# **Please remember:**







# Stormwater Pollution

### What you should know for...

## Riverside County Stormwater Members

Flood Control District (Lead Agency) (951) 955-1250

County of Riverside (951) 955-1000

City of Banning (951) 922-3130

City of Beaumont (951) 769-8520

City of Calimesa (909) 795-9801

City of Canyon Lake (951) 244-2955

Cathedral City (760) 770-0349

City of Coachella (760) 398-3502

City of Corona (951) 736-2248

City of Desert Hot Springs (760) 329-6411

City of Hemet (951) 765-2300

City of Indian Wells (760) 346-2489

City of San Jacinto (951) 487-7330

City of Indio (760) 391-4000 City of Lake Elsinore (951) 674-3124

City of La Quinta (760) 777-7000

City of Menifee (951) 672-6777

City of Moreno Valley (951) 413-3120

City of Murrieta (951) 304-2489

City of Norco (951) 735-3900

City of Palm Desert (760) 346-0611

City of Palm Springs (760) 323-8253

City of Perris (951) 943-6100

City of Rancho Mirage (760) 324-4511

City of Riverside (951) 926-5311

City of Temecula (951) 694-6444

City of Wildomar (951) 677-7751

Coachella Valley Water District (760) 398-2651

The Riverside County "Only Rain Down the Storm Drain" Pollution Prevention Program gratefully acknowledges San Bernardino County's Stormwater Program for their contribution to this brochure. Industrial & Commercial Facilities

Best Management Practices (BMPS) for:

Industrial

Commercial Facilities





Station in



# **STORMTECH SC-740 CHAMBER**

Designed to meet the most stringent industry performance standards for superior structural integrity while providing designers with a cost-effective method to save valuable land and protect water resources. The StormTech system is designed primarily to be used under parking lots, thus maximizing land usage for private (commercial) and public applications. StormTech chambers can also be used in conjunction with Green Infrastructure, thus enhancing the performance and extending the service life of these practices. **STORMTECH SC-740 CHAMBER** (not to scale) Nominal Chamber Specifications Size (LxWxH) 85.4" x 51" x 30" 2,170 mm x 1,295 mm x 762 mm 90.7" (2304 mm) **Chamber Storage** ACTUAL LENGTH 45.9 ft<sup>3</sup> (1.30 m<sup>3</sup>) 24" (600 mm) DIAMETER MAX. Min. Installed Storage\* 74.9 ft3 (2.12 m3) 29.3" (744 mm) Weight 74.0 lbs (33.6 kg) 12,2 ł (310 mm) 45.9" (1166 mm) Shipping 85.4" (2169 mm) INSTALLED LENGTH 30 chambers/pallet 60 end caps/pallet 30.01 12 pallets/truck (762 mm) \*Assumes 6" (150 mm) stone above, below and between chambers and 40% stone porosity. 51.0' (1295 mm) GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, < FINES, COMPACT IN 6" (150 mm) MAX LIFTS TO 95% PROCTO DENSITY. SEE THE TABLE OF ACCEPTABLE FILL MATERIALS EMBEDMENT STONE SHALL BE A CLEAN, CRUSHED AND ANGULAR STONE WITH AN AASHTO M43 DESIGNATION BETWEEN #3 AND #57 CHAMBERS SHALL MEET THE REQUIREMENTS FOR ASTM F2418 POLYPROPLENE (PP) CHAMBERS CHAMBERS SHALL BE BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS". OR ASTM F922 POLYETHYLENE (PE) CHAMBERS ADS GEDSYTHETICS 601T NON-WOVEN GEOTEXTILE ALL AROUND CLEAN, CRUSHED, ANGULAR EMBEDMENT STONE PAVEMENT LAYER (DÉSIGNED BY SITE DÉSIGN ENGINEER) (2.4 m) MAX 18 (450 mm) MIN 6" (150 mm) MIN 30' (760 mm) PERIMETER STONE EXCAVATION WALL (CAN BE SLOPED OR VERTICAL) DEPTH OF STONE TO BE DETERMINED BY SITE DESIGN ENGINEER 6" (150 mm) MIN 12" (300 mm) Mit END CAP SITE DESIGN ENGINEER IS RESPONSIBLE FOR 12" (300 mm) TYP 51" (1295 mm) (150 mm) MIN THE ENSURING THE REQUIRED BEARIN GAPACITY OF SUBGRADE SOL

\*MINIMUM COVER TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED INSTALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR, INCREASE COVER TO 24" (600 mm)





#### SC-740 CUMULATIVE STORAGE VOLUMES PER CHAMBER

Assumes 40% Stone Porosity. Calculations are Based Upon a 6" (150 mm) Stone Base Under Chambers.

			Tutol Scalars Considerate
in a start and a start of the s			
42 (1067)		AE 00 (1 200)	7/ 00 (2 121)
42 (1007)	T -	45.90 (1.300)	73 77 (2 089)
41 (1041)	ļ Stona	45.90 (1.300)	73.64 (2.009)
30 (001)	Cover	45.90 (1.300)	71 52 (2 025)
38 (965)	Ĩ	45.90 (1.300)	70 39 (1 993)
37 (940)	t	45.90 (1.300)	69.26 (1.961)
36 (914)	2 · · · · · · · · · · · · · · ·	45.90 (1.300)	68.14 (1.929)
35 (889)	···· ··· ··· ··· ··· ··· ··· ··· ··· ·	45.85 (1.298)	66.98 (1.897)
34 (864)		45.69 (1.294)	65.75 (1.862)
33 (838)		45.41 (1.286)	64.46 (1.825)
32 (813)		44.81 (1.269)	62.97 (1.783)
31 (787)		44.01 (1.246)	61.36 (1.737)
30 (762)		43.06 (1.219)	59.66 (1.689)
29 (737)		41.98 (1.189)	57.89 (1.639)
28 (711)	*****	40.80 (1.155)	56.05 (1.587)
27 (686)		39.54 (1.120)	54.17 (1.534)
26 (660)		38.18 (1.081)	52.23 (1.479)
25 (635)		36./4 (1.040)	50.23 (1.422)
24 (610)		35.22 (0.977)	48.19 (1.365)
23 (584)	••••••	33.64 (0.953)	46.11 (1.306)
22 (559) 01 (633)		31.99 (0.906)	44.00 (1.240)
21 (555)		30.29 (0.838) 39 57 (0.909)	20 67 (1 193)
10 (483)		26,74 (0,808)	33.07 (1.123)
18 (457)		24.89 (0.705)	35 23 (0 997)
17 (432)		23.00 (0.651)	32.96 (0.939)
16 (406)	)	21.06 (0.596)	30.68 (0.869)
15 (381)		19.09 (0.541)	28.36 (0.803)
14 (356)	0	17.08 (0.484)	26.03 (0.737)
13 (330)		15.04 (0.426)	23.68 (0.670)
12 (305)		12.97 (0.367)	21.31 (0.608)
11 (279)		10.87 (0.309)	18.92 (0.535)
10 (254)		8.74 (0.247)	16.51 (0.468)
9 (229)		6.58 (0.186)	14.09 (0.399)
8 (203)	ļ	4.41 (0.125)	11.66 (0.330)
7 (178)	1	2.21 (0.063)	9.21 (0.264)
6 (152)	1	0 (0)	6.76 (0.191)
5 (127)		0 (0)	5.63 (0.160)
4 (102)	Stone	U(U)	4.51 (0.128)
3 (76)		· U(U)	3,30 (U.U90) 2,25 (0,064)
2 (31) 1 (95)	<b>-</b>	U(U) 0 (0)	2.23 (0.004)
1 (20)	t <b>y</b>	U (V) U	1.13 (0.032)

#### STORAGE VOLUME PER CHAMBER FT<sup>3</sup> (M<sup>3</sup>)

SC-740 Chamber	45.9 (1.3)	74.9 (2.1)	81.7 (2.3)	88.4 (2.5)
	Skirden 1 mil	5 (150) 10 (150)	12 (200)	18 (490)
		ister selet Ister solet	Standard and S Idealan Dobjin	tane A (alum)

Note: Assumes 6" (150 mm) stone above chambers, 6" (150 mm) row spacing and 40% stone porosity.

#### **AMOUNT OF STONE PER CHAMBER**

ENGLISH TONS (9457)	Stor	e Faundelian b 125	optin Territori
SC-740	3.8 (2.8)	4.6 (3.3)	5.5 (3.9)
		all new	den werd
juli adaleh kering sering se	n the sources of		
SC-740	3,450 (2.1)	4.170 (2.5)	4,490 (3.0)

Note: Assumes 6" (150 mm) of stone above and between chambers.

#### **VOLUME EXCAVATION PER CHAMBER YD<sup>3</sup> (M<sup>3</sup>)**

	51	oes Foundation D	eyəl)
	(5.150)	12 (380)	16 (450)
SC-740	5.5 (4.2)	6.2 (4.7)	6.8 (5.2)

Note: Assumes 6" (150 mm) of row separation and 18" (450 mm) of cover. The volume of excavation will vary as depth of cover increases.



Working on a project? Visit us at www.stormtech.com and utilize the StormTech Design Tool

Note: Add 1.13 ft<sup>3</sup> (0.032 m<sup>3</sup>) of storage for each additional inch (25 mm) of stone foundation.

For more information on the StormTech SC-740 Chamber and other ADS products, please contact our Customer Service Representatives at 1-800-821-6710

#### THE MOST ADVANCED NAME IN WATER MANAGEMENT SOLUTIONS"

ADS "Terms and Conditions of Sale" are available on the ADS website, www.ads-pipe.com The ADS togo and the Green Stripe are registered trademarks of Advanced Drainage Systems, Inc. StormTech" is a registered trademark of StormTech. Inc. 9 2017 Advanced Drainage Systems, Inc. # \$16 090508 (09/17 CS Advanced Drainage Systems, Inc. 4640 Trueman Blvd., Hilliard, OH 43026 1-800-821-6710 www.ads-pipe.com

	MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL; FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'D' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAYED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER.	ANY SOL/ROCK MATERIALS, NATIVE SOLS, OR PER ENGINEER'S PLANS, CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS,	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS, PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
С	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 18' (450 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOLVAGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145' A-1, A-2-4, A-3 OR AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57, 6, 67, 66, 7, 78, 8, 89, 9, 10	BEGIN COMPACTIONS AFTER 12" (300 mm) OF MATERIAL OVE THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAVERS 6" (150 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOI WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS. ROLLER GROSS VEHICLE WEIGHT NOT TO EXCEED 12,000 lbs (53 kN). DYNAMI FORCE NOT TO EXCEED 20,000 lbs (95 kN).
В	EMBEDMENT STORE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE (A' LAYER) TO THE 'C' LAYER ABOVE,	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M431 3, 357, 4, 467, 5, 56, 57	NO COMPACTION REQUIRED.
А	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M431 3, 357, 4, 467, 5, 56, 57	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. <sup>2</sup>

PLEASE NOTE

2

LASE NOTE: THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR, FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO, 4 (AASHTO M43) STONE". STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 6" (150 mm) (MAX) LIFTS USING TWO FULL COVERAGES WITH A VIBRATORY COMPACTOR. WHERE INFILIRATION SURFACES MAY BE COMPROMISED BY COMPACTION, FOR STANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY RAKING OR DRAGGING WITHOUT COMPACTION EQUIPMENT, FOR SPECIAL LOAD DESIGNS, CONTACT STORMTECH FOR 3 COMPACTION REQUIREMENTS.

CONTROLINGUES CONTROL OF CONTROL



#### NOTES:

- 1. CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16a, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS",
- 2. SC-740 CHAMBERS SHALL BE DESIGNED IN ACCORDANCE WITH ASTM F2787 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 3. THE SITE DESIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESISTANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE DEPTH OF FOUNDATION STONE WITH
- CONSIDERATION FOR THE RANGE OF EXPECTED SOIL MOISTURE CONDITIONS.
- 4. PERIMETER STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WALL FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.
- 5. REQUIREMENTS FOR HANDLING AND INSTALLATION:
- TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
- TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS THAN 2". .
- TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2418 SHALL BE GREATER THAN OR EQUAL TO 550 . LBS/IN/N. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73" F / 23" C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.

Storm 4640 TRUEMAN BLVD HILLIARD, OH 43026 SHEET OF

SECTION Ř £ ECKED DRAWN

STANDARD CROSS SC-740

è. ģ Ŧ

5 E L C

SC-740 TECHNICAL SPECIFICATION

NTS



ALL STUBS, EXCEPT FOR THE SC740EPE24B ARE PLACED AT BOTTOM OF END CAP SUCH THAT THE OUTSIDE DIAMETER OF THE STUB IS FLUSH WITH THE BOTTOM OF THE END CAP. FOR ADDITIONAL INFORMATION CONTACT STORMTECH AT 1-888-892-2694.

18.5" (470 mm)

24" (600 mm)

1.6" (41 mm)

0.1" (3 mm)

\_\_\_\_

\* FOR THE SC740EPE24B THE 24" (600 mm) STUB LIES BELOW THE BOTTOM OF THE END CAP APPROXIMATELY 1.75" (44 mm). BACKFILL MATERIAL SHOULD BE REMOVED FROM BELOW THE N-12 STUB SO THAT THE FITTING SITS LEVEL.

NOTE: ALL DIMENSIONS ARE NOMINAL

SC740EPE18B / SC740EPE18BPC

SC740EPE248\*







#### REQUIRED MATERIALS AND EQUIPMENT LIST

- Acceptable fill materials per Table 1
- · Woven and non-woven geotextiles

- StormTech solid end caps and pre-cored end caps
- StormTech chambers
- StormTech manifolds and fittings

#### IMPORTANT NOTES:

A. This installation guide provides the minimum requirements for proper installation of chambers. Non-adherence to this guide may result in damage to chambers during installation. Replacement of damaged chambers during or after backfilling is costly and very time consuming. It is recommended that all installers are familiar with this guide, and that the contractor inspects the chambers for distortion, damage and joint integrity as work progresses.

B. Use of a dozer to push embedment stone between the rows of chambers may cause damage to chambers and is not an acceptable backfill method. Any chambers damaged by using the "dump and push" method are not covered under the StormTech standard warranty.

C. Care should be taken in the handling of chambers and end caps. Avoid dropping, prying or excessive force on chambers during removal from pallet and initial placement.

# 



Excavate bed and prepare subgrade per engineer's plans.



Place non-woven geotextile over prepared soils and up excavation walls. Install underdrains if required.



Place clean, crushed, angular stone foundation 6" (150 mm) min. Compact to achieve a flat surface.



Install manifolds and lay out woven scour geotextile at inlet rows [min. 12.5 ft (3.8 m)] at each inlet end cap. Place a continuous piece (no seams, double layer) along entire length of Isolator<sup>®</sup> Row(s).



Align the first chamber and end cap of each row with inlet pipes. Contractor may choose to postpone stone placement around end chambers and leave ends of rows open for easy inspection of chambers during the backfill process.



Continue installing chambers by overlapping chamber end corrugations. Chamber joints are labeled "Lower Joint – Overlap Here" and "Build this direction – Upper Joint" Be sure that the chamber placement does not exceed the reach of the construction equipment used to place the stone. Maintain minimum 6" (150 mm) spacing between rows.

## 



Lift the end of the chamber a few inches off the ground. With the curved face of the end cap facing outward, place the end cap into the chamber's end corrugation.

## Protobricated End Caps



24" (600 mm) inlets are the maximum size that can fit into a SC-740/DC-780 end cap and must be prefabricated with a 24" (600 mm) pipe stub. SC-310 chambers with a 12" (300 mm) inlet pipe must use a prefabricated end cap with a 12" (300 mm) pipe stub.

### Isolator Row



Place two continuous layers of ADS Woven fabric between the foundation stone and the isolator row chambers, making sure the fabric lays flat and extends the entire width of the chamber feet. Drape a strip of ADS non-woven geotextile over the row of chambers (not required over DC-780). This is the same type of non-woven geotextile used as a separation layer around the angular stone of the StormTech system. **2** 



Initial embedment shall be spotted along the centerline of the chamber evenly anchoring the lower portion of the chamber. This is best accomplished with a stone conveyor or excavator reaching along the row.



No equipment shall be operated on the bed at this stage of the installation. Excavators must be located off the bed. Dump trucks shall not dump stone directly on to the bed. Dozers or loaders are not allowed on the bed at this time.

### 



Backfill chambers evenly. Stone column height should never differ by more than 12" (300 mm) between adjacent chamber rows or between chamber rows and perimeter.



#### PERIMETER NOT BACKFILLED

PERIMETER FULLY BACKFILLED

Perimeter stone must be brought up evenly with chamber rows. Perimeter must be fully backfilled, with stone extended horizontally to the excavation wall.

## Rackfill - Embodmont Stone & Cover Stone



Continue evenly backfilling between rows and around perimeter until embedment stone reaches tops of chambers. Perimeter stone must extend horizontally to the excavation wall for both straight or sloped sidewalls. Only after chambers have been backfilled to top of chamber and with a minimum 6" (150 mm) of cover stone on top of chambers can small dozers be used over the chambers for backfilling remaining cover stone.



Small dozers and skid loaders may be used to finish grading stone backfill in accordance with ground pressure limits in Table 2. They must push material parallel to rows only. Never push perpendicular to rows. StormTech recommends that the contractor inspect chambers before placing final backfill. Any chambers damaged by construction shall be removed and replaced.

# 



Install non-woven geotextile over stone. Geotextile must overlap 24" (600 mm) min, where edges meet, Compact each lift of backfill as specified in the site design engineer's drawings. Roller travel parallel with rows,

### inserta Tee Defai



CONTACT STORMTECH FOR MORE INFORMATION.

### StormTech Isolator Row Detail



#### Table 1-Acceptable Fill Materials

i - 17 Series de la constante d La constante de la constante de	- Destripten	AA MU MAS Totalahan	Semperior Bindly Bigurette IP
(D)Final Fill: Fill Material for layer 'D' starts from the top of the 'C' layer to the bottom offlexible pavement or unpaved finished gacle above. Note that the pave- ment sublase may be part of the 'D' layer.	Any solVrock materials, native soils or per engineer's plans. Check plans for pavement subgrade requirements.	N∕A	Prepare per site design engineer's plans. Paved Installations may have stringent material and prepara- tion requirements.
(C) Initial Fill: Fill Material for layer 'C' starts from the top of the embedment stone ('B' layer) to 18" (450 mm) above the top of the chamber. Note that pavement sublase may be part of the 'C' layer.	Granular well-graded soll/ aggregate mktures, <35% fines or processed aggregate. Most pavement subbase materials can be used in lieu of this layer.	AASHTO M45 A-1, A-2-4, A-3 or AASHTO M431 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	Begin compaction after min. 12" (300 mm) of mate- rial over the chambers is reached. Compact additional layers in 6" (150 mm) max. Iffits to a min. 95% Proctor density for well-graded material and 95% relative density for processed aggregate materials. Roller gross vehicle weight not to exceed 12,000 bs (53 kN). Dynamic force not to exceed 20,000 bs (69 kN)
(B) Emberiment Stone: Embedment Stone surrounding chambers from the foundation stone to the 'C' layer above.	Clean, crushed, angular stone	AASHTO M431 3, 357, 4, 467, 5, 56, 57	No compaction required.
(A) Foundation Stone: Foundation Stone below the chambers from the subgrade up to the fool (bottom) of the chamber.	Clean, crushed, angular stone,	AASHTO M431 3, 357, 4, 467, 5, 56, 57	Place and compact in 6" (150 mm) lifts using two full coverages with a vibratory compactor. <sup>2,3</sup>



可自知的论

- We detect AASHTC designations are for gradations only. The stone must also be clean, crushed, angular, For example, a specification for #4 stons would state: "bloan, crushed, angular no. 4 (AASHTO M43) stone".
- F. StermTech compaction requirements are met for 'A' location materials when placest and compacted in 6" (150 mm) (max) lifts using two full coverages with a vibratory compactor.
- 3. Where infiliration surfaces may be comprised by compaction, for standard installations and atandard design load conditions, a tist surface may be achieved by raking or dragging without compaction equipment. For special load
- devigns, contact StormTech for compaction regularements.

#### Figure 2 - Fill Material Locations



- 35' (992) mm) of stabilized cover materials over the chambers is regulard for full dump track travel and dumping.
- 2. Juing paving operations, dump truck axis loads on 18" (450 mm) of cover may be recessary. Precautions should be taken to evoid radiing of the road base layer, to ensure that compaction requirements have been met, and that a minimum of 18" (450 mea) of cover exists over the chambers. Contact StarmTech for activitien guidence on allowable axis loads during paving.
- Grand pressure for back dozers is the vehicle operating weight ducted by lotal grand contact and for both backs. Excavalins witescent higher grand pressures based on loaded backet weight and bacm extension.
- Advi-executors (< 8,000lbs/3,628 kg) can be used with at least 12' (300 mm) of stone over the chambers and are limited by the maximum ground pressures in Table 2 based on a full bucket at maximum homm extension.
- 5. Storage of materials such as construction materials, equipment, spairs, etc. should not be located over the StarmTech system. The uss of equipment over the StarmTech system not covered in Table 2 (ex. self mixing equipment, cranes, etc) is limited. Please contact StormTechs for mera information.
- C. Algorable track loads besed on vehicle travel only. Excavators shell not aperate on chember bads until the total backfill reaches 3 wet (300 mm) over the entire bad.

ADS "Terms and Conditions of Sale" are available on the ADS website, www.ads-pipe.com. Advanced Drainage Systems, the ADS logo, and the green stripe are registered trademarks of Advanced Drainage Systems, Inc. StormTech® and the Isolator® Row are registered trademarks of StormTech, Inc #11010 07/19 CS

©2019 Advanced Drainage Systems, Inc.

#### Table 2 - Maximum Allowable Construction Vehicle Loads<sup>5</sup>

		Meenhum Allows	edia Wheel Loads	Maximum Alless	alue Tracki Convis-	Steernam Allowent Kaller Loug-
Hanstri Location	aver Chambers 1- Jinn	Mess Jack Losal Jorfführtes Ins fred	Max Wheel 1 (54) for Loaders fos (MN)	inger Width Sidt partiers	Miss formulat Premaine dist. (APa)	Marill Incharge Research Dynamic Bolder Research Die Killer
) Final Fill Material	36" [900] Compacted	32,000 [142]	16,000 [71]	12" [305] 18" [457] 24" [610] 30" [762] 36" [914]	3420 [164] 2350 [113] 1850 [89] 1510 [72] 1310 [63]	38,000 [169]
C Initial Fill Material	24" (600) Compacted	32,000 [142]	16,000 (71)	12" [305] 18" [457] 24" [610] 30" [762] 36" [914]	2480 [119] 1770 [85] 1430 [68] 1210 [58] 1070 [51]	20,000 [89]
ne waa ne waa ka k	24" [600] Loose/Dumped	32,000 [142]	16,000 [71]	12" [305] 18" [457] 24" [610] 30" [762] 36" [914]	2245 [107] 1625 [78] 1325 [63] 1135 [54] 1010 [48]	20,000 (89) Roller gross vehicle weight not to exceed 12,000 lbs. (53 kN)
ng uniter of the manufacture of the state of	18" [450]	32,000 [142]	16,000 [71]	12" [305] 18" [457] 24" [610] 30" [762] 36" [914]	2010 [96] 1480 [71] 1220 [58] 1060 [51] 950 [45]	20,000 (89) Roller gross vehicle weight not to exceed 12,000 bs. (53 kV)
Embedment Stone	12" [300]	16,000 [71]	NOT ALLOWED	12" [305] 18" [457] 24" [610] 30" [762] 36" [914]	1540 [74] 1190 [57] 1010 [48] 910 [43] 840 [40]	20,000 (89) Roller gross vehicle weight not to exceed 12,000 lbs. [53 kN]
	6" [150]	8,000 [35]	NOT ALLOWED	12" [305] 18" [457] 24" [610] 30" [762] 36" [914]	1070 [51] 900 [43] 800 [38] 760 [36] 720 [34]	NOT ALLOWED

#### Table 3 - Placement Methods and Descriptions

Matorial	Provide H Methods/ Resultitions	- Winz, Linn Restinctions Frankright Shell	i sen -oad rentrationo. Ste o tariffaxanan Calismust	in territori da la companya Managina da la companya da la company Managina da la companya da la company
⑦ Final Fill Material	A variety of placement methods may be used. All construction loads must not exceed the maximum limits in Table 2.	36" (900 mm) minimum cover required for dump trucks to dump over chambers.	Dozers to push paraliel to rows until 36" (900mm) compaced cover is reached. <sup>4</sup>	Roller travel parallel to rows only until 36" (900 mm) compacted cover is reached.
© Initial Fill Material	Excavator positioned off bed recommended. Small excavator allowed over chambers. Small dozer allowed.	Asphalt can be dumped into paver when compacted pavement subbase reaches 18" (450 mm) above top of chambers.	Small LGP track dozers & skid loaders allowed to grade cover stone with at least 6" (150 mm) stone under tracks at all times. Equipment must push parallel to rows at all times.	Use dynamic force of roller only after compacted fill depth reaches 12" (300 mm) over chambers. Roller travel parallel to chamber rows only.
B Embedment Stone	No equipment allowed on bare chambers. Use excavator or stone conveyor positioned off bed or on foundation stone to evenly fill around all chambers to at least the top of chambers.	No wheel loads allowed: Material must be placed outside the limits of the chamber bed.	No tracked equipment is allowed on chambers until a min. 6" (150 mm) cover stone is in place.	No rollers allowed,
A Foundation Stone	No StormTech restrictions. Contractor respond capacity, dewatering or protection of subgrad	sible for any conditions or requirem. é.	ents by others relative to subgrade b	earing



#### STANDARD LIMITED WARRANTY OF STORMTECH LLC ("STORMTECH"): PRODUCTS

- (A) This Limited Warranty applies solely to the StormTech chambers and end plates manufactured by StormTech and sold to the original purchaser (the "Purchaser"). The chambers and end plates are collectively referred to as the "Products."
- The structural integrity of the Products, when installed (B)strictly in accordance with StormTech's written installation instructions at the time of installation, are warranted to the Purchaser against defective materials and workmanship for one (1) year from the date of purchase. Should a defect appear in the Limited Warranty period, the Purchaser shall provide StormTech with written notice of the alleged defect at StormTech's corporate headquarters within ten (10) days of the discovery of the defect. The notice shall describe the alleged defect in reasonable detail. StormTech agrees to supply replacements for those Products determined by StormTech to be defective and covered by this Limited Warranty. The supply of replacement products is the sole remedy of the Purchaser for breaches of this Limited Warranty, StormTech's liability specifically excludes the cost of removal and/or installation of the Products.
- (C) THIS LIMITED WARRANTY IS EXCLUSIVE. THERE ARE NO OTHER WARRANTIES WITH RESPECT TO THE PRODUCTS, INCLUDING NO IMPLIED WARRANTIES OF MERCHANTABILITY OR OF FITNESS FOR A PARTICULAR PURPOSE.
- (D) This Limited Warranty only applies to the Products when the Products are installed in a single layer. UNDER NO CIRCUMSTANCES, SHALL THE PRODUCTS BE INSTALLED IN A MULTI-LAYER CONFIGURATION.
- (E) No representative of StormTech has the authority to change this Limited Warranty in any manner or to extend this Limited Warranty. This Limited Warranty does not apply to any person other than to the Purchaser.

- (F) Under no circumstances shall StormTech be liable to the Purchaser or to any third party for product liability claims; claims arising from the design, shipment, or installation of the Products, or the cost of other goods or services related to the purchase and installation of the Products. For this Limited Warranty to apply, the Products must be installed in accordance with all site conditions required by state and local codes; all other applicable laws; and StormTech's written installation instructions.
- THE LIMITED WARRANTY DOES NOT EXTEND (G)TO INCIDENTAL, CONSEQUENTIAL, SPECIAL OR INDIRECT DAMAGES. STORMTECH SHALL NOT BE LIABLE FOR PENALTIES OR LIQUIDATED DAMAGES. INCLUDING LOSS OF PRODUCTION AND PROFITS; LABOR AND MATERIALS: OVERHEAD COSTS: OR OTHER LOSS OR EXPENSE INCURRED BY THE PURCHASER OR ANY THIRD PARTY. SPECIFICALLY EXCLUDED FROM LIMITED WARRANTY COVERAGE ARE DAMAGE TO THE PRODUCTS ARISING FROM ORDINARY WEAR AND TEAR: ALTERATION. ACCIDENT, MISUSE, ABUSE OR NEGLECT; THE PRODUCTS BEING SUBJECTED TO VEHICLE TRAFFIC OR OTHER CONDITIONS WHICH ARE NOT PERMITTED BY STORMTECH'S WRITTEN SPECIFICATIONS OR INSTALLATION INSTRUCTIONS; FAILURE TO MAINTAIN THE MINIMUM GROUND COVERS SET FORTH IN THE INSTALLATION INSTRUCTIONS; THE PLACEMENT OF IMPROPER MATERIALS INTO THE PRODUCTS; FAILURE OF THE PRODUCTS DUE TO IMPROPER SITING OR IMPROPER SIZING; OR ANY OTHER EVENT NOT CAUSED BY STORMTECH. A PRODUCT ALSO IS EXCLUDED FROM LIMITED WARRANTY COVERAGE IF SUCH PRODUCT IS USED IN A PROJECT OR SYSTEM IN WHICH ANY GEOTEXTILE PRODUCTS OTHER THAN THOSE PROVIDED BY ADVANCED DRAINAGE SYSTEMS ARE USED. THIS LIMITED WARRANTY REPRESENTS STORMTECH'S SOLE LIABILITY TO THE PURCHASER FOR CLAIMS RELATED TO THE PRODUCTS, WHETHER THE CLAIM IS BASED UPON CONTRACT, TORT, OR OTHER LEGAL THEORY.





#### ADS GEOSYNTHETICS 0601T NONWOVEN GEOTEXTILE

#### Scope

This specification describes ADS Geosynthetics 6.0 oz (0601T) nonwoven geotextile.

#### **Filter Fabric Requirements**

ADS Geosynthetics 6.0 oz (0601T) is a needle-punched nonwoven geotextile made of 100% polypropylene staple fibers, which are formed into a random network for dimensional stability. ADS Geosynthetics 6.0 oz (0601T) resists ultraviolet deterioration, rotting, biological degradation, naturally encountered basics and acids. Polypropylene is stable within a pH range of 2 to 13. ADS Geosynthetics 6.0 oz (0601T) conforms to the physical property values listed below:

PROPERTY	TEST METHOD	UNIT	M.A.R.V. (Minimum Average Roll Value)
Weight (Typical)	ASTM D 5261	oz/yd <sup>2</sup> (g/m <sup>2</sup> )	6.0 (203)
Grab Tensile	ASTM D 4632	lbs (kN)	160 (0.711)
Grab Elongation	ASTM D 4632	%	50
Trapezoid Tear Strength	ASTM D 4533	lbs (kN)	60 (0.267)
CBR Puncture Resistance	ASTM D 6241	lbs (kN)	410 (1.82)
Permittivity*	ASTM D 4491	sec <sup>-1</sup>	1.5
Water Flow*	ASTM D 4491	gpm/ft <sup>2</sup> (Vmin/m <sup>2</sup> )	110 (4480)
AOS*	ASTM D 4751	US Sieve (mm)	70 (0.212)
UV Resistance	ASTM D 4355	%/hrs	70/500

Filter Fabric Properties

PACKAGING					
Roll Dimensions (W x L) – ft	12.5 x 360 / 15 x 300				
Square Yards Per Roll	500				
Estimated Roll Weight – Ibs	195				

\* At the time of manufacturing. Handling may change these properties.



#### ADS GEOSYNTHETICS 315W WOVEN GEOTEXTILE

#### Scope

This specification describes ADS Geosynthetics 315W woven geotextile.

#### **Filter Fabric Requirements**

ADS Geosynthetics 315W is manufactured using high tenacity polypropylene yarns that are woven to form a dimensionally stable network, which allows the yarns to maintain their relative position. ADS Geosynthetics 315W resists ultraviolet deterioration, rotting and biological degradation and is inert to commonly encountered soil chemicals. ADS Geosynthetics 315W conforms to the physical property values listed below:

PROPERTY	TEST	ENGLISH M.A.R.V.	METRIC M.A.R.V.	
	METHOD	(Minimum Average Roll Value)	(Minimum Average Roll Value)	
Tensile Strength (Grab)	ASTM D-4632	315 lbs	1400 N	
Elongation	ASTM D-4632	15%	15%	
CBR Puncture	ASTM D-6241	900 lbs	4005 N	
Puncture	ASTM D-4833	150 lbs	667 N	
Mullen Burst	ASTM D-3786	600 psi	4134 kPa	
Trapezoidal Tear	ASTM D-4533	120 lbs	533 N	
UV Resistance (at	ASTM D-4355	70%	70%	
500 hrs)				
Apparent Opening Size	ASTM D-4751	40 US Std.	0.425 mm	
(AOS)*		Sieve		
Permittivity	ASTM D-4491	.05 sec <sup>-1</sup>	.05 sec <sup>-1</sup>	
Water Flow Rate	ASTM D-4491	4 gpm/ft <sup>2</sup>	163 l/min/m <sup>2</sup>	
		12.5' x 360'	3.81 m x 109.8 m	
Roll Sizes		15.0' x 300'	4.57 m x 91.5 m	
	1	17.5' x 258'	5.33 m x 78.6 m	

Filter Fabric Properties

\*Maximum average roll value.



# CDS Guide Operation, Design, Performance and Maintenance



### **CDS**<sup>®</sup>

Using patented continuous deflective separation technology, the CDS system screens, separates and traps debris, sediment, and oil and grease from stormwater runoff. The indirect screening capability of the system allows for 100% removal of floatables and neutrally buoyant material without blinding. Flow and screening controls physically separate captured solids, and minimize the re-suspension and release of previously trapped pollutants. Inline units can treat up to 6 cfs, and internally bypass flows in excess of 50 cfs (1416 L/s). Available precast or cast-in-place, offline units can treat flows from 1 to 300 cfs (28.3 to 8495 L/s). The pollutant removal capacity of the CDS system has been proven in lab and field testing.

### **Operation Overview**

Stormwater enters the diversion chamber where the diversion weir guides the flow into the unit's separation chamber and pollutants are removed from the flow. All flows up to the system's treatment design capacity enter the separation chamber and are treated.

Swirl concentration and screen deflection force floatables and solids to the center of the separation chamber where 100% of floatables and neutrally buoyant debris larger than the screen apertures are trapped.

Stormwater then moves through the separation screen, under the oil baffle and exits the system. The separation screen remains clog free due to continuous deflection.

During the flow events exceeding the treatment design capacity, the diversion weir bypasses excessive flows around the separation chamber, so captured pollutants are retained in the separation cylinder.



### **Design Basics**

There are three primary methods of sizing a CDS system. The Water Quality Flow Rate Method determines which model size provides the desired removal efficiency at a given flow rate for a defined particle size. The Rational Rainfall Method<sup>™</sup> or the and Probabilistic Method is used when a specific removal efficiency of the net annual sediment load is required.

Typically in the Unites States, CDS systems are designed to achieve an 80% annual solids load reduction based on lab generated performance curves for a gradation with an average particle size (d50) of 125 microns ( $\mu$ m). For some regulatory environments, CDS systems can also be designed to achieve an 80% annual solids load reduction based on an average particle size (d50) of 75 microns ( $\mu$ m) or 50 microns ( $\mu$ m).

#### Water Quality Flow Rate Method

In some cases, regulations require that a specific treatment rate, often referred to as the water quality design flow (WQQ), be treated. This WQQ represents the peak flow rate from either an event with a specific recurrence interval, e.g. the six-month storm, or a water quality depth, e.g. 1/2-inch (13 mm) of rainfall.

The CDS is designed to treat all flows up to the WQQ. At influent rates higher than the WQQ, the diversion weir will direct most flow exceeding the WQQ around the separation chamber. This allows removal efficiency to remain relatively constant in the separation chamber and eliminates the risk of washout during bypass flows regardless of influent flow rates.

Treatment flow rates are defined as the rate at which the CDS will remove a specific gradation of sediment at a specific removal efficiency. Therefore the treatment flow rate is variable, based on the gradation and removal efficiency specified by the design engineer.

#### Rational Rainfall Method™

Differences in local climate, topography and scale make every site hydraulically unique. It is important to take these factors into consideration when estimating the long-term performance of any stormwater treatment system. The Rational Rainfall Method combines site-specific information with laboratory generated performance data, and local historical precipitation records to estimate removal efficiencies as accurately as possible.

Short duration rain gauge records from across the United States and Canada were analyzed to determine the percent of the total annual rainfall that fell at a range of intensities. US stations' depths were totaled every 15 minutes, or hourly, and recorded in 0.01-inch increments. Depths were recorded hourly with 1-mm resolution at Canadian stations. One trend was consistent at all sites; the vast majority of precipitation fell at low intensities and high intensity storms contributed relatively little to the total annual depth.

These intensities, along with the total drainage area and runoff coefficient for each specific site, are translated into flow rates using the Rational Rainfall Method. Since most sites are relatively small and highly impervious, the Rational Rainfall Method is appropriate. Based on the runoff flow rates calculated for each intensity, operating rates within a proposed CDS system are determined. Performance efficiency curve determined from full scale laboratory tests on defined sediment PSDs is applied to calculate solids removal efficiency. The relative removal efficiency at each operating rate is added to produce a net annual pollutant removal efficiency estimate.

#### **Probabilistic Rational Method**

The Probabilistic Rational Method is a sizing program Contech developed to estimate a net annual sediment load reduction for a particular CDS model based on site size, site runoff coefficient, regional rainfall intensity distribution, and anticipated pollutant characteristics.

The Probabilistic Method is an extension of the Rational Method used to estimate peak discharge rates generated by storm events of varying statistical return frequencies (e.g. 2-year storm event). Under the Rational Method, an adjustment factor is used to adjust the runoff coefficient estimated for the 10-year event, correlating a known hydrologic parameter with the target storm event. The rainfall intensities vary depending on the return frequency of the storm event under consideration. In general, these two frequency dependent parameters (rainfall intensity and runoff coefficient) increase as the return frequency increases while the drainage area remains constant.

These intensities, along with the total drainage area and runoff coefficient for each specific site, are translated into flow rates using the Rational Method. Since most sites are relatively small and highly impervious, the Rational Method is appropriate. Based on the runoff flow rates calculated for each intensity, operating rates within a proposed CDS are determined. Performance efficiency curve on defined sediment PSDs is applied to calculate solids removal efficiency. The relative removal efficiency at each operating rate is added to produce a net annual pollutant removal efficiency estimate.

#### **Treatment Flow Rate**

The inlet throat area is sized to ensure that the WQQ passes through the separation chamber at a water surface elevation equal to the crest of the diversion weir. The diversion weir bypasses excessive flows around the separation chamber, thus preventing re-suspension or re-entrainment of previously captured particles.

#### **Hydraulic Capacity**

The hydraulic capacity of a CDS system is determined by the length and height of the diversion weir and by the maximum allowable head in the system. Typical configurations allow hydraulic capacities of up to ten times the treatment flow rate. The crest of the diversion weir may be lowered and the inlet throat may be widened to increase the capacity of the system at a given water surface elevation. The unit is designed to meet project specific hydraulic requirements.

### Performance

#### **Full-Scale Laboratory Test Results**

A full-scale CDS system (Model CDS2020-5B) was tested at the facility of University of Florida, Gainesville, FL. This CDS unit was evaluated under controlled laboratory conditions of influent flow rate and addition of sediment.

Two different gradations of silica sand material (UF Sediment & OK-110) were used in the CDS performance evaluation. The particle size distributions (PSDs) of the test materials were analyzed using standard method "Gradation ASTM D-422 "Standard Test Method for Particle-Size Analysis of Soils" by a certified laboratory.

UF Sediment is a mixture of three different products produced by the U.S. Silica Company: "Sil-Co-Sil 106", "#1 DRY" and "20/40 Oil Frac". Particle size distribution analysis shows that the UF Sediment has a very fine gradation (d50 = 20 to 30  $\mu$ m) covering a wide size range (Coefficient of Uniformity, C averaged at 10.6). In comparison with the hypothetical TSS gradation specified in the NJDEP (New Jersey Department of Environmental Protection) and NJCAT (New Jersey Corporation for Advanced Technology) protocol for lab testing, the UF Sediment covers a similar range of particle size but with a finer d50 (d50 for NJDEP is approximately 50  $\mu$ m) (NJDEP, 2003).

The OK-110 silica sand is a commercial product of U.S. Silica Sand. The particle size distribution analysis of this material, also included in Figure 1, shows that 99.9% of the OK-110 sand is finer than 250 microns, with a mean particle size (d50) of 106 microns. The PSDs for the test material are shown in Figure 1.



Figure 1. Particle size distributions

Tests were conducted to quantify the performance of a specific CDS unit (1.1 cfs (31.3-L/s) design capacity) at various flow rates, ranging from 1% up to 125% of the treatment design capacity of the unit, using the 2400 micron screen. All tests were conducted with controlled influent concentrations of approximately 200 mg/L. Effluent samples were taken at equal time intervals across the entire duration of each test run. These samples were then processed with a Dekaport Cone sample splitter to obtain representative sub-samples for Suspended Sediment Concentration (SSC) testing using ASTM D3977-97 "Standard Test Methods for Determining Sediment Concentration in Water Samples", and particle size distribution analysis.

### **Results and Modeling**

Based on the data from the University of Florida, a performance model was developed for the CDS system. A regression analysis was used to develop a fitting curve representative of the scattered data points at various design flow rates. This model, which demonstrated good agreement with the laboratory data, can then be used to predict CDS system performance with respect to SSC removal for any particle size gradation, assuming the particles are inorganic sandy-silt. Figure 2 shows CDS predictive performance for two typical particle size gradations (NJCAT gradation and OK-110 sand) as a function of operating rate.



Figure 2. CDS stormwater treatment predictive performance for various particle gradations as a function of operating rate.

Many regulatory jurisdictions set a performance standard for hydrodynamic devices by stating that the devices shall be capable of achieving an 80% removal efficiency for particles having a mean particle size (d50) of 125 microns (e.g. Washington State Department of Ecology — WASDOE - 2008). The model can be used to calculate the expected performance of such a PSD (shown in Figure 3). The model indicates (Figure 4) that the CDS system with 2400 micron screen achieves approximately 80% removal at the design (100%) flow rate, for this particle size distribution (d50 = 125  $\mu$ m).



Figure 3. WASDOE PSD





Figure 4. Modeled performance for WASDOE PSD.

#### Maintenance

The CDS system should be inspected at regular intervals and maintained when necessary to ensure optimum performance. The rate at which the system collects pollutants will depend more heavily on site activities than the size of the unit. For example, unstable soils or heavy winter sanding will cause the grit chamber to fill more quickly but regular sweeping of paved surfaces will slow accumulation.

#### Inspection

Inspection is the key to effective maintenance and is easily performed. Pollutant transport and deposition may vary from year to year and regular inspections will help ensure that the system is cleaned out at the appropriate time. At a minimum, inspections should be performed twice per year (e.g. spring and fall) however more frequent inspections may be necessary in climates where winter sanding operations may lead to rapid accumulations, or in equipment washdown areas. Installations should also be inspected more frequently where excessive amounts of trash are expected.

The visual inspection should ascertain that the system components are in working order and that there are no blockages or obstructions in the inlet and separation screen. The inspection should also quantify the accumulation of hydrocarbons, trash, and sediment in the system. Measuring pollutant accumulation can be done with a calibrated dipstick, tape measure or other measuring instrument. If absorbent material is used for enhanced removal of hydrocarbons, the level of discoloration of the sorbent material should also be identified



during inspection. It is useful and often required as part of an operating permit to keep a record of each inspection. A simple form for doing so is provided.

Access to the CDS unit is typically achieved through two manhole access covers. One opening allows for inspection and cleanout of the separation chamber (cylinder and screen) and isolated sump. The other allows for inspection and cleanout of sediment captured and retained outside the screen. For deep units, a single manhole access point would allows both sump cleanout and access outside the screen.

The CDS system should be cleaned when the level of sediment has reached 75% of capacity in the isolated sump or when an appreciable level of hydrocarbons and trash has accumulated. If absorbent material is used, it should be replaced when significant discoloration has occurred. Performance will not be impacted until 100% of the sump capacity is exceeded however it is recommended that the system be cleaned prior to that for easier removal of sediment. The level of sediment is easily determined by measuring from finished grade down to the top of the sediment pile. To avoid underestimating the level of sediment in the chamber, the measuring device must be lowered to the top of the sediment pile carefully. Particles at the top of the pile typically offer less resistance to the end of the rod than consolidated particles toward the bottom of the pile. Once this measurement is recorded, it should be compared to the as-built drawing for the unit to determine weather the height of the sediment pile off the bottom of the sump floor exceeds 75% of the total height of isolated sump.

### Cleaning

Cleaning of a CDS systems should be done during dry weather conditions when no flow is entering the system. The use of a vacuum truck is generally the most effective and convenient method of removing pollutants from the system. Simply remove the manhole covers and insert the vacuum hose into the sump. The system should be completely drained down and the sump fully evacuated of sediment. The area outside the screen should also be cleaned out if pollutant build-up exists in this area.

In installations where the risk of petroleum spills is small, liquid contaminants may not accumulate as quickly as sediment. However, the system should be cleaned out immediately in the event of an oil or gasoline spill. Motor oil and other hydrocarbons that accumulate on a more routine basis should be removed when an appreciable layer has been captured. To remove these pollutants, it may be preferable to use absorbent pads since they are usually less expensive to dispose than the oil/water emulsion that may be created by vacuuming the oily layer. Trash and debris can be netted out to separate it from the other pollutants. The screen should be cleaned to ensure it is free of trash and debris.

Manhole covers should be securely seated following cleaning activities to prevent leakage of runoff into the system from above and also to ensure that proper safety precautions have been followed. Confined space entry procedures need to be followed if physical access is required. Disposal of all material removed from the CDS system should be done in accordance with local regulations. In many jurisdictions, disposal of the sediments may be handled in the same manner as the disposal of sediments removed from catch basins or deep sump manholes. Check your local regulations for specific requirements on disposal.



CDS Model	Diaı	meter	Distance from to Top of S	ance from Water Surface Sediment o Top of Sediment Pile Storage Capacity			
	ft	m	ft	m	yd3	m3	
CDS2015-4	4	1.2	3.0	0.9	0.5	0.4	
CDS2015	5	1.5	3.0	0.9	1.3	1.0	
CDS2020	5	1.5	3.5	1.1	1.3	1.0	
CDS2025	5	1.5	4.0	1.2	1.3	1.0	
CDS3020	6	1.8	4.0	1.2	2.1	1.6	
CDS3030	6	1.8	4.6	1.4	2.1	1.6	
CDS3035	6	1.8	5.0	1.5	2.1	1.6	
CDS4030	8	2.4	4.6	1.4	5.6	4.3	
CDS4040	8	2.4	5.7	1.7	5.6	4.3	
CDS4045	8	2.4	6.2	1.9	5.6	4.3	

Table 1: CDS Maintenance Indicators and Sediment Storage Capacities

Note: To avoid underestimating the volume of sediment in the chamber, carefully lower the measuring device to the top of the sediment pile. Finer silty particles at the top of the pile may be more difficult to feel with a measuring stick. These finer particles typically offer less resistance to the end of the rod than larger particles toward the bottom of the pile.



### **CDS Inspection & Maintenance Log**

CDS Model:

CDS Mode	DS Model: Location:					
Date	Water depth to sediment <sup>1</sup>	Floatable Layer Thickness <sup>2</sup>	Describe Maintenance Performed	Maintenance Personnel	Comments	

- The water depth to sediment is determined by taking two measurements with a stadia rod: one measurement from the manhole opening to the 1. top of the sediment pile and the other from the manhole opening to the water surface. If the difference between these measurements is less than the values listed in table 1 the system should be cleaned out. Note: to avoid underestimating the volume of sediment in the chamber, the measuring device must be carefully lowered to the top of the sediment pile.
- For optimum performance, the system should be cleaned out when the floating hydrocarbon layer accumulates to an appreciable thickness. In 2. the event of an oil spill, the system should be cleaned immediately.

**SUPPORT** 

- Drawings and specifications are available at www.ContechES.com.
- Site-specific design support is available from our engineers.



#### ©2017 Contech Engineered Solutions LLC, a QUIKRETE Company

Contech Engineered Solutions provides site solutions for the civil engineering industry. Contech's portfolio includes bridges, drainage, sanitary sewer, earth stabilization and stormwater treatment products. For information on other Contech division offerings, visit www.ContechES.com or call 800.338.1122

NOTHING IN THIS CATALOG SHOULD BE CONSTRUED AS A WARRANTY. APPLICATIONS SUGGESTED HEREIN ARE DESCRIBED ONLY TO HELP READERS MAKE THEIR OWN EVALUATIONS AND DECISIONS, AND ARE NEITHER GUARANTEES NOR WARRANTIES OF SUITABILITY FOR ANY APPLICATION. CONTECH MAKES NO WARRANTY WHATSOEVER, EXPRESS OR IMPLIED, RELATED TO THE APPLICATIONS, MATERIALS, COATINGS, OR PRODUCTS DISCUSSED HEREIN. ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND ALL IMPLIED WARRANTIES OF FITNESS FOR ANY PARTICULAR PURPOSE ARE DISCLAIMED BY CONTECH. SEE CONTECH'S CONDITIONS OF SALE (AVAILABLE AT WWW.CONTECHES.COM/COS) FOR MORE INFORMATION.

The product(s) described may be protected by one or more of the following US patents: 5,322,629; 5,624,576; 5,707,527; 5,759,415; 5,788,848; 5,985,157; 6,027,639; 6,350,374; 6,406,218; 6,641,720; 6,511,595; 6,649,048; 6,991,114; 6,998,038; 7,186,058; 7,296,692; 7,297,266; related foreign patents or other patents pending.

